10646390
01-09-04

The
Patent
Office

INVESTOR IN PEOPLE

The Patent Office
Concept House
Cardiff Road
Newport
South Wales
NP10 8QQ

I, the undersigned, being an officer duly authorised in accordance with Section74(1) and (4) of the Deregulation and Contracting Out Act 1994, to sign and issue certificates on behalf of the Comptroller-General, hereby certify that annexed hereto is a true copy of the international application filed on 18 January 2002 under the Patent Cooperation Treaty at the UK Receiving Office. The application was allocated the number PCT/GB2002/00215.

In accordance with the Patents (Companies Re-registration) Rules 1982, if a company named in this certificate and any accompanying documents has re-registered under the Companies Act 1980 with the same name as that with which it was registered immediately before re-registration save for the substitution as, or the inclusion as, the last part of the name of the words "public limited company" or their equivalents in Welsh, references to the name of the company in this certificate and any accompanying documents shall be treated as references to the name with which it is so re-registered.

In accordance with the rules, the words "public limited company" may be replaced by p.l.c., plc, P.L.C. or PLC.

Re-registration under the Companies Act does not constitute a new legal entity but merely subjects the company to certain additional company law rules.

Signed   *TE Taylor*

Dated   10 December 2003

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only
International Application No. **PCT/GB 0 2 / 0 0 2 1 5**
International Filing Date *18 — 0(— 02.* **18 JANUARY 2002**
United Kingdom Patent Office PCT International Application
Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference
(if desired) (12 characters maximum) P010490WO CYK

Box No. I   TITLE OF INVENTION

Genes

Box No. II   APPLICANT   ☐ This person is also inventor

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

Cambridge University Technical Services Limited
20 Trumpington Street
Cambridge
CB2 1QA
United Kingdom

Telephone No.
Facsimile No.
Teleprinter No.
Applicant's registration No. with the Office

State *(that is, country)* of nationality:
GB

State *(that is, country)* of residence:
GB

This person is applicant for the purposes of:
☐ all designated States
☒ all designated States except the United States of America
☐ the United States of America only
☐ the States indicated in the Supplemental Box

Box No. III   FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

SAITOU, Mitinori
Wellcome CRC Institute
University of Cambridge
Tennis Court Road
Cambridge
CB2 1QR
United Kingdom

This person is:
☐ applicant only
☒ applicant and inventor
☐ inventor only *(If this check-box is marked, do not fill in below.)*

Applicant's registration No. with the Office

State *(that is, country)* of nationality:
JP

State *(that is, country)* of residence:
JP

This person is applicant for the purposes of:
☐ all designated States
☐ all designated States except the United States of America
☒ the United States of America only
☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV   AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as: ☒ agent   ☐ common representative

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

MASCHIO, Antonio
D Young & Co
21 New Fetter Lane
London
EC4A 1DA
United Kingdom

Telephone No.
+44 23 8071 9500
Facsimile No.
+44 23 8071 9800
Teleprinter No.
477667 YOUNGS G
Agent's registration No. with the Office

☐ **Address for correspondence:** Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Form PCT/RO/101 (first sheet) (March 2001; reprint July 2001)

See Notes to the request form

PCT/GB 0 2 / 0 0 2 1 5

Continuation of Box No. III   FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

If none of the following sub-boxes is used, this sheet should not be included in the request.

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

SURANI, Azim
Wellcome CRC Institute
University of Cambridge
Tennis Court Road
Cambridge
CB2 1QR
United Kingdom

This person is:

[ ] applicant only

[X] applicant and inventor

[ ] inventor only *(If this check-box is marked, do not fill in below.)*

Applicant's registration No. with the Office

State *(that is, country)* of nationality:
GB

State *(that is, country)* of residence:
GB

This person is applicant for the purposes of: [ ] all designated States   [ ] all designated States except the United States of America   [X] the United States of America only   [ ] the States indicated in the Supplemental Box

---

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

This person is:

[ ] applicant only

[ ] applicant and inventor

[ ] inventor only *(If this check-box is marked, do not fill in below.)*

Applicant's registration No. with the Office

State *(that is, country)* of nationality:

State *(that is, country)* of residence:

This person is applicant for the purposes of: [ ] all designated States   [ ] all designated States except the United States of America   [ ] the United States of America only   [ ] the States indicated in the Supplemental Box

---

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

This person is:

[ ] applicant only

[ ] applicant and inventor

[ ] inventor only *(If this check-box is marked, do not fill in below.)*

Applicant's registration No. with the Office

State *(that is, country)* of nationality:

State *(that is, country)* of residence:

This person is applicant for the purposes of: [ ] all designated States   [ ] all designated States except the United States of America   [ ] the United States of America only   [ ] the States indicated in the Supplemental Box

---

Name and address: *(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)*

This person is:

[ ] applicant only

[ ] applicant and inventor

[ ] inventor only *(If this check-box is marked, do not fill in below.)*

Applicant's registration No. with the Office

State *(that is, country)* of nationality:

State *(that is, country)* of residence:

This person is applicant for the purposes of: [ ] all designated States   [ ] all designated States except the United States of America   [ ] the United States of America only   [ ] the States indicated in the Supplemental Box

---

[ ] Further applicants and/or (further) inventors are indicated on another continuation sheet.

Form PCT/RO/101 (continuation sheet) (March 2001; reprint July 2001)   *See Notes to the request form*

Box No. V   DESIGNATION OF STATES   *Mark the applicable check-boxes below; at least one must be marked.*

The following designations are hereby made under Rule 4.9(a):

Regional Patent

☒ **AP**   ARIPO Patent: GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, MZ Mozambique, SD Sudan, SL Sierra Leone, SZ Swaziland, TZ United Republic of Tanzania, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT

☒ **EA**   Eurasian Patent: AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT

☒ **EP**   European Patent: AT Austria, BE Belgium, CH & LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, TR Turkey, and any other State which is a Contracting State of the European Patent Convention and of the PCT

☒ **OA**   OAPI Patent: BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT *(if other kind of protection or treatment desired, specify on dotted line)* ....

National Patent *(if other kind of protection or treatment desired, specify on dotted line):*

☒ AE United Arab Emirates
☒ AG Antigua and Barbuda
☒ AL Albania
☒ AM Armenia
☒ AT Austria
☒ AU Australia
☒ AZ Azerbaijan
☒ BA Bosnia and Herzegovina
☒ BB Barbados
☒ BG Bulgaria
☒ BR Brazil
☒ BY Belarus
☒ BZ Belize
☒ CA Canada
☒ CH & LI Switzerland and Liechtenstein
☒ CN China
☒ CO Colombia
☒ CR Costa Rica
☒ CU Cuba
☒ CZ Czech Republic
☒ DE Germany
☒ DK Denmark
☒ DM Dominica
☒ DZ Algeria
☒ EC Ecuador
☒ EE Estonia
☒ ES Spain
☒ FI Finland
☒ GB United Kingdom
☒ GD Grenada
☒ GE Georgia

☒ GH Ghana
☒ GM Gambia
☒ HR Croatia
☒ HU Hungary
☒ ID Indonesia
☒ IL Israel
☒ IN India
☒ IS Iceland
☒ JP Japan
☒ KE Kenya
☒ KG Kyrgyzstan
☒ KP Democratic People's Republic of Korea
☒ KR Republic of Korea
☒ KZ Kazakhstan
☒ LC Saint Lucia
☒ LK Sri Lanka
☒ LR Liberia
☒ LS Lesotho
☒ LT Lithuania
☒ LU Luxembourg
☒ LV Latvia
☒ MA Morocco
☒ MD Republic of Moldova
☒ MG Madagascar
☒ MK The former Yugoslav Republic of Macedonia
☒ MN Mongolia
☒ MW Malawi

☒ MX Mexico
☒ MZ Mozambique
☒ NO Norway
☒ NZ New Zealand
☒ PL Poland
☒ PT Portugal
☒ RO Romania
☒ RU Russian Federation
☒ SD Sudan
☒ SE Sweden
☒ SG Singapore
☒ SI Slovenia
☒ SK Slovakia
☒ SL Sierra Leone
☒ TJ Tajikistan
☒ TM Turkmenistan
☒ TR Turkey
☒ TT Trinidad and Tobago
☒ TZ United Republic of Tanzania
☒ UA Ukraine
☒ UG Uganda
☒ US United States of America
☒ UZ Uzbekistan
☒ VN Viet Nam
☒ YU Yugoslavia
☒ ZA South Africa
☒ ZW Zimbabwe

Check-boxes below reserved for designating States which have become party to the PCT after issuance of this sheet:

☒ PH Philippines ....
☒ OM Oman ....
☒ ZM Zambia ....
☒ TN Tunisia ....
☐ ....
☐ ....

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. *(Confirmation (including fees) must reach the receiving Office within the 15-month time limit.)*

PCT/GB 0 2 / 0 0 2 1 5

| Supplemental Box | *If the Supplemental Box is not used, this sheet should not be included in the request.* |

1. *If, in any of the Boxes, except Boxes Nos. VIII(i) to (v) for which a special continuation box is provided, the space is insufficient to furnish all the information: in such case, write "Continuation of Box No...." (indicate the number of the Box) and furnish the information in the same manner as required according to the captions of the Box in which the space was insufficient, in particular:*

  (i) *if more than two persons are to be indicated as applicants and/or inventors and no "continuation sheet" is available: in such case, write "Continuation of Box No. III" and indicate for each additional person the same type of information as required in Box No. III. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below;*

  (ii) *if, in Box No. II or in any of the sub-boxes of Box No. III, the indication "the States indicated in the Supplemental Box" is checked: in such case, write "Continuation of Box No. II" or "Continuation of Box No. III" or "Continuation of Boxes No. II and No. III" (as the case may be), indicate the name of the applicant(s) involved and, next to (each) such name, the State(s) (and/or, where applicable, ARIPO, Eurasian, European or OAPI patent) for the purposes of which the named person is applicant;*

  (iii) *if, in Box No. II or in any of the sub-boxes of Box No. III, the inventor or the inventor/applicant is not inventor for the purposes of all designated States or for the purposes of the United States of America: in such case, write "Continuation of Box No. II" or "Continuation of Box No. III" or "Continuation of Boxes No. II and No. III" (as the case may be), indicate the name of the inventor(s) and, next to (each) such name, the State(s) (and/or, where applicable, ARIPO, Eurasian, European or OAPI patent) for the purposes of which the named person is inventor;*

  (iv) *if, in addition to the agent(s) indicated in Box No. IV, there are further agents: in such case, write "Continuation of Box No. IV" and indicate for each further agent the same type of information as required in Box No. IV;*

  (v) *if, in Box No. V, the name of any State (or OAPI) is accompanied by the indication "patent of addition," or "certificate of addition," or if, in Box No. V, the name of the United States of America is accompanied by an indication "continuation" or "continuation-in-part": in such case, write "Continuation of Box No. V" and the name of each State involved (or OAPI), and after the name of each such State (or OAPI), the number of the parent title or parent application and the date of grant of the parent title or filing of the parent application;*

  (vi) *if, in Box No. VI, there are more than five earlier applications whose priority is claimed: in such case, write "Continuation of Box No. VI" and indicate for each additional earlier application the same type of information as required in Box No. VI.*

2. *If, with regard to the precautionary designation statement contained in Box No. V, the applicant wishes to exclude any State(s) from the scope of that statement: in such case, write "Designation(s) excluded from precautionary designation statement" and indicate the name or two-letter code of each State so excluded.*

Continuation of Box No. IV

PILCH, Adam John Michael
CRISP, David Norman
ROBINSON, Nigel Alexander Julian
HARRIS, Ian Richard
HARDING, Charles Thomas
TURNER, James Arthur
MALLALIEU, Catherine Louise
PRATT, Richard Wilson
PRICE, Paul Anthony King
HORNER, David Richard
MASCHIO, Antonio
NACHSHEN, Neil
POTTER, Julian Mark
HAINES, Miles John
DEVILE, Jonathan Mark
TANNER, James Percival
KHOO, Chong-Yee
HOLLIDAY, Louise Caroline
MILLS, Julia
HECTOR, Annabel
ALCOCK, David

Box No. VI   PRIORITY CLAIM

The priority of the following earlier application(s) is hereby claimed:

Filing date of earlier application *(day/month/year)*	Number of earlier application	Where earlier application is:		
		national application: country	regional application:* regional Office	international application: receiving Office
item (1) *18 JAN'01* 18/1/2001	0101300.2	GB		
item (2)				
item (3)				
item (4)				
item (5)				

☐ Further priority claims are indicated in the Supplemental Box.

The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) *(only if the earlier application was filed with the Office which for the purposes of this international application is the receiving Office)* identified above as:

☒ all items   ☐ item (1)   ☐ item (2)   ☐ item (3)   ☐ item (4)   ☐ item (5)   ☐ other, see Supplemental Box

* Where the earlier application is an ARIPO application, indicate at least one country party to the Paris Convention for the Protection of Industrial Property or one Member of the World Trade Organization for which that earlier application was filed (Rule 4.10(b)(ii)): . . . .
. . . .

Box No. VII   INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA) *(if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used)*:

ISA / .EPO. . . . .

Request to use results of earlier search; reference to that search *(if an earlier search has been carried out by or requested from the International Searching Authority)*:
Date *(day/month/year)*   Number   Country *(or regional Office)*

Box No. VIII   DECLARATIONS

The following **declarations** are contained in Boxes Nos. VIII (i) to (v) *(mark the applicable check-boxes below and indicate in the right column the number of each type of declaration)*:   Number of declarations

☐   Box No. VIII (i)   Declaration as to the identity of the inventor   :

☐   Box No. VIII (ii)   Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent   :

☐   Box No. VIII (iii)   Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application   :

☐   Box No. VIII (iv)   Declaration of inventorship (only for the purposes of the designation of the United States of America)   :

☐   Box No. VIII (v)   Declaration as to non-prejudicial disclosures or exceptions to lack of novelty   :

Form PCT/RO/101 (third sheet) (March 2001; reprint July 2001)   *See Notes to the request form*

PCT/GB 02/00215

Box No. IX CHECK LIST; LANGUAGE OF FILING

This international application contains:		This international application is accompanied by the following item(s) *(mark the applicable check-boxes below and indicate in right column the number of each item):*	Number of items
(a) the following number of **sheets in paper form:**			
request (including declaration sheets)	: 6	1. ☒ fee calculation sheet	: 1
description (excluding sequence listing part)	: 68	2. ☐ original separate power of attorney	:
claims	: 3	3. ☐ original general power of attorney	:
abstract	: 1	4. ☐ copy of general power of attorney; reference number, if any:	:
drawings	: 9	5. ☐ statement explaining lack of signature	:
Sub-total number of sheets	: 87	6. ☐ priority document(s) identified in Box No. VI as item(s):	:
sequence listing part of description *(actual number of sheets if filed in paper form, whether or not also filed in computer readable form; see (b) below)*	:	7. ☐ translation of international application into *(language):*	:
		8. ☐ separate indications concerning deposited microorganism or other biological material	:
Total number of sheets	: 87	9. ☐ sequence listing in computer readable form (indicate also type and number of carriers (diskette, CD-ROM, CD-R or other))	
(b) sequence listing part of description filed in **computer readable form**		(i) ☐ copy submitted for the purposes of international search under Rule 13*ter* only (and not as part of the international application)	:
(i) ☐ only (under Section 801(a)(i))		(ii) ☐ *(only where check-box (b)(i) or (b)(ii) is marked in left column)* additional copies including, where applicable, the copy for the purposes of international search under Rule 13*ter*	:
(ii) ☐ in addition to being filed in paper form (under Section 801(a)(ii))			
Type and number of carriers (diskette, CD-ROM, CD-R or other) on which the sequence listing part is contained *(additional copies to be indicated under item 9(ii), in right column):*		(iii) ☐ together with relevant statement as to the identity of the copy or copies with the sequence listing part mentioned in left column	:
		10. ☐ other *(specify):*	:

Figure of the drawings which should accompany the abstract: 3	Language of filing of the international application: English

Box No. X SIGNATURE OF APPLICANT, AGENT OR COMMON REPRESENTATIVE

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).

MASCHIO, Antonio

For receiving Office use only

1. Date of actual receipt of the purported international application:	18 JANUARY 2002 /18-01-02	2. Drawings:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:		☒ received:
4. Date of timely receipt of the required corrections under PCT Article 11(2):		☐ not received:
5. International Searching Authority (if two or more are competent): ISA /	6. ☐ Transmittal of search copy delayed until search fee is paid	

For International Bureau use only

Date of receipt of the record copy by the International Bureau:

See Notes to the request form

GENES

FIELD

The present invention relates to the fields of development, molecular biology and genetics. More particularly, the invention relates to genes which are expressed

5   exclusively in the earliest populations of primordial germ cells (PGCs) and the use of such genes and the products thereof in identification of pluripotent and multipotent cells such as PGCs, pluripotent embryonic stem cells (ES) and pluripotent embryonic germ cells (EG), in cell populations. They are also markers for a change in the sate of cells from being non pluripotent to becoming pluripotent, and in being able to confer this state

10   on a non pluripotent cell.

INTRODUCTION

Post fertilisation, the early mammalian embryo undergoes four rounds of cleavage to form a morula of 16 cells. These cells, following further rounds of division, develop into a blastocyst in which the cells can be divided into two distinct regions; the inner cell

15   mass, which will form the embryo, and the trophectoderm, which will form extra-embryonic tissue, such as the placenta.

The cells that form part of the embryo up until the formation of the blastocyst are totipotent; in other words, each of the cells has the ability to give rise to a complete individual embryo, and to all the extra-embryonic tissues required for its development.

20   After blastocyst formation, the cells of the inner cell mass are no longer totipotent, but are pluripotent, in that they can give rise to a range of different tissues. A known marker for such cells is the expression of the enzyme alkaline phosphatase and *Oct4*.

Primordial germ cells (PGCs) are pluripotent cells that have the ability to differentiate into all three primary germ layers. In mammals, the PGCs migrate from the

25   base of the allantois, through the hindgut epithelium and dorsal mesentery, to colonise the gonadal anlague. The PGC-derived cells have a characteristically low cytoplasm/nucleus ratio, usually with prominent nucleoli. PGCs may be isolated from the embryos by

removing the genital ridge of the embryo, dissociating the PGCs from the gonadal anlague, and collecting the PGCs. The earliest PGC population is reported to consist of a cluster of some 45 (forty-five) alkaline phosphatase positive cells, found at the base of the emerging allantois, 7.25 days post-fertilisation (Ginsburg *et al.*, (1990) Development 110:521-528).

PGCs have many applications in modern biotechnology and molecular biology. They are useful in the production of transgenic animals, where embryonic germ (EG) cells derived from PGCs may be used in much the same manner as embryonic stem (ES) cells (Labosky *et al.*, (1994) Development 120:3197-3204). Moreover, they are useful in the study of foetal development and the provision of pluripotent stem cells for tissue regeneration in the therapy of degenerative diseases and repopulation of damaged tissue following trauma. Above all, PGCs while having some specialised properties, retain an underlying pluripotency, which is lost from the neighbouring cells that surround the founder population of PGCs that acquire a somatic cell fate. PGCs and the surrounding somatic cells share a common ancestry. However, the founder PGCs are few in number and difficult to isolate from embryonic tissue and the surrounding somatic cells, which complicates their study and the development of techniques which make use thereof.

Little is known in the art about the expression of genes in the founder population of PGCs and the relationship between PGC-specific gene expression and the retention of pluripotency in these cells. Certain markers for PGCs are known – for example, the expression of tissue non-specific alkaline phosphatase (TNAP) has been used as a marker for early PGCs (Ginsburg *et al.*, (1990) Development 110:521-528). Oct4 is known to be expressed in PGCs, but not somatic cells (Yoem *et al.*, (1996) Development 122:881-894). Other markers, such as BMP4, are known to be expressed primarily in somatic tissues (Lawson *et al.*, (1999) Genes & Dev. 13:424-436). However, none of these genes is specific for PGCs, since they are also expressed in other tissue types. There is therefore a need in the art for the identification of genes which may be used as markers for PGCs and which may provide an insight into the biology of germ cell development and the nature of the pluripotent state.

SUMMARY

We disclose the sequences of two genes which are expressed specifically in PGCs and other pluripotent cells. The sequence of the genes from mouse is set forth in **SEQ ID NO: 1** (GCR1 or Fragilis) and **SEQ ID NO: 3** (GCR2, or Stella). Corresponding amino acid sequences for mouse GCR1 and GCR2 are set out in **SEQ ID NO: 2** and **SEQ ID NO: 4** respectively. Nucleic acid sequences of rat GCR2 homologues are set out in **SEQ ID NO: 5, SEQ ID NO: 6, SEQ ID NO: 7, SEQ ID NO: 8,** and **SEQ ID NO: 9.**

According to a first aspect of the present invention, we provide a GCR1 polypeptide, or a fragment, homologue, variant or derivative thereof. Preferably, the polypeptide has at least 50%, 60%, 70%, 80%, 90% or 95% homology to a sequence shown in SEQ ID NO: 2.

There is provided, according to a second aspect of the present invention, GCR2 polypeptide, or a fragment, homologue, variant or derivative thereof. Preferably, the polypeptide has at least 50%, 60%, 70%, 80%, 90% or 95% homology to a sequence shown in SEQ ID NO: 4.

We provide, according to a third aspect of the present invention, a nucleic acid encoding a polypeptide according to any preceding claim.

As a fourth aspect of the present invention, there is provided a nucleic acid having at least 90% homology with the sequence set forth in SEQ ID NO: 1, or a fragment, variant or derivative thereof.

We provide, according to a fifth aspect of the present invention, a nucleic acid having at least 75% homology with the sequence set forth in SEQ ID NO: 3, SEQ ID NO: 5, SEQ ID NO: 6, SEQ ID NO: 7, SEQ ID NO: 8 or SEQ ID NO: 9, or a fragment, variant or derivative thereof

The present invention, in a sixth aspect, provides a nucleic acid comprising a sequence of 25 contiguous nucleotides of a nucleic acid according to the third, fourth or fifth aspect of the invention.

In a seventh aspect of the present invention, there is provided a nucleic acid comprising a sequence of 15 contiguous nucleotides of a nucleic acid according to the third, fourth, fifth or sixth aspect of the invention.

According to an eighth aspect of the present invention, we provide a complement of a nucleic acid sequence according to any of the third to seventh aspect of the invention.

Preferably, such a nucleic acid comprises one or more nucleotide substitutions, wherein such substitutions do not alter the coding specificity of said nucleic acid as a result of the degeneracy of the genetic code.

We provide, according to a ninth aspect of the invention, a polypeptide encoded by a nucleic acid according to any preceding aspect of the invention.

Preferably, the polypeptide comprises a sequence shown in SEQ ID NO: 2 or SEQ ID NO: 4.

There is provided, in accordance with a tenth aspect of the present invention, a method for identifying a pluripotent cell, comprising detecting the presence of a polypeptide according to the first, second, ninth or tenth aspect of the invention or the expression of a nucleic acid according to any of the third to eighth aspect of the invention, or a homologue thereof.

Preferably, the method comprises the steps of amplifying nucleic acids from a putative pluripotent cell using 5' and 3' primers specific for GCR1 (Fragilis) and/or GCR2 (Stella), and detecting amplified nucleic acid thus produced. Preferably, the expression of the nucleic acid sequence is detected by *in situ* hybridisation.

The expression of the nucleic acid sequence may be determined by detecting the protein product encoded thereby. Alternatively or in addition, the protein product may be detected by immunostaining.

As an eleventh aspect of the invention, we provide an antibody specific for a polypeptide according to the first, second, ninth or tenth aspect of the invention. preferably, the antibody is capable of specifically binding to an extracellular domain of GCR1.

We provide, according to a twelfth aspect of the invention, there is provided use of such an antibody for the identification and/ or isolation of a pluripotent cell.

We further provide, according to a thirteenth aspect of the invention, a pluripotent cell identified by a method as set out previously.

There is provided, according to a fourteenth aspect of the present invention, a method for isolating a gene specifically expressed in a pluripotent cell, comprising the steps of: (a) providing a population of cells containing a pluripotent cell; (b) isolating one or more pluripotent cells therefrom and providing single-cell pluripotent cell isolates; (c) amplifying the transcribed nucleic acid present in a single pluripotent cell; (d) conducting a subtractive hybridisation screen to identify transcripts present in pluripotent cells but not in somatic cells; and (e) probing a nucleic acid library with one or more transcripts identified in (d) to clone one or more genes which are specifically expressed in pluripotent cells.

In a highly preferred embodiment, the pluripotent cell is selected from the group consisting of: a primordial germ cell (PGC), an embryonic stem cell (ES) and an embryonic germ cell (EG). Preferably, the pluripotent cell comprises a primordial germ cell.

BRIEF DESCRIPTION OF THE FIGURES

Figure 1: Nucleotide and deduced amino acid sequence of Fragilis. Predicted positions of the two transmembrane domains (TM I and TM II) are underlined and indicated by bold letters. The poly(A) signal is underlined.

5   Figure 2: Nucleotide and deduced amino acid sequence of Stella. Three nuclear localization signals are underlined. A potential nuclear export signal is underlined twice, and the hydrophobic residues are indicated in bold. Helical structures in a motif with similarity to SAP domain (a.a.28 to a.a.63) are underlined in red, and the conserved residues are indicated by blue. A splicing factor-like motif is underlined and the
10   conserved residues are indicated in green. Poly(A) signals are also underlined.

Figure 3: Expression of Fragilis in embryonic stem (ES) cells. ES cells are fixed in 4% paraformaldehyde in PBS for 10min. at room temperature and processed for immunohistochemistry as described by Saitou et al., (1998). *J Cell Biol* 141, 397-408. (1998). Fragilis expression is similarly detected in E6.5 proximal epiblast cells, which are
15   germ cell competent cells, and in newly specified germ cells. The expression declines after E8.5 following completion of the specification of germ cells fate.

Figure 4: Expression of Stella in PGCs. PGCs from E12.5 genital ridges are fixed in 4% paraformaldehyde in PBS for 10min. at room temperature and processed for immunohistochemistry as described by Saitou et al., (1998). *J Cell Biol* 141, 397-408.
20   (1998). Stella is detected in PGCs from E 7.25-13.5, as well as in pluripotent ES cells and in EG cells. Stella is also detected in the totipotent oocyte, zygote and in the totipotent and pluripotent blastomeres during preimplantation development and in developing gametes. When EG cells are derived from PGCs (Labosky *et al.*, (1994) Development 120:3197-3204). Fragilis expression is again detected in the pluripotent EG cells as it is in
25   ES cells. Therefore, Fragilis and Stella are also markers for the pluripotent stem cells.

Figure 5. Fragilis expression by whole-mount *in situ* hybridization in E7.2 mouse embryos.

Figure 6. Stella expression by whole mount *in situ* hybridisation in E 7.2 mouse embryos.

Figure 7. Stella expression in PGCs in the process of migration into the gonads in E9.0 embryos.

Figure 8a and 8b. Expression of Fragilis and Stella in single cells detected by PCR analysis of single cell cDNAs. Numbers marked by symbol* in 8b are the PGCs. Note that there are more single cells showing expression of Fragilis compared to those showing expression of Stella. Only cells with the highest levels of Fragilis expression were found to express Stella and acquire the germ cell fate. Cells that express Stella were found not to show expression of Hoxb1. Cells that express lower levels of Fragilis and no Stella become somatic cells and showed expression of Hoxb1. The founder population of PGCs also show high levels of Tnap. Both the founder PGCs and the somatic cells show expression of Oct4, T(Brachyury), and Fgf8.

DETAILED DESCRIPTION

GCR1 (FRAGILIS) AND GCR2 (STELLA)

The disclosure provides generally for GCR1 (Fragilis) and GCR2 (Stella) nucleic acids, polypeptides, as well as fragments, homologues, variants and derivatives thereof.

The names "GCR1" and "Fragilis" should be understood as synonymous with each other, and likewise, "GCR2" and "Stella" should be considered synonyms. Nucleic acid and amino acid sequences of GCR1/Fragilis are set out in SEQ ID NO: 1 and 2, while nucleic acid sequences of GCR2/Stella are set out in SEQ ID NO: 3, 5, 6, 7, 8 and 9, with an amino acid sequence of GCR2/Stella shown in SEQ ID NO: 4.

In preferred embodiments, however, GCR1/ Fragilis should be taken to refer to the nucleic acid sequence shown in SEQ ID NO: 1, or the amino acid sequence shown in SEQ ID NO: 2, as the context requires. Furthermore, in preferred embodiments, GCR2/

Stella should be taken to refer to the nucleic acid sequence shown in SEQ ID NO: 3, or the amino acid sequence shown in SEQ ID NO: 4, as the context requires.

GCR1 and GCR2 are PGC-specific transcripts. GCR1 is upregulated during the process of lineage commitment of PGCs, while GCR2 is upregulated after GCR1, and

5   marks commitment to the PGC fate. The first gene, GCR1 (Germ cell restricted-1, Fragilis), encodes a 137 amino acid protein with a predicted molecular weight of 15.0kD. The best fit model of the EMBL program PredictProtein predicts two transmembrane domains, both N and C terminus ends being located outside. The BLASTP search revealed that Fragilis is a novel member of the interferon-inducible protein family. One

10   prototype member, human 9-27 (identical to Leu-13 antigen), is inducible by interferon in leukocytes and endothelial cells, and is located at the cell surface as a component of a multimeric complex involved in the transduction of antiproliferative and homotypic adhesion signals (Deblandre, 1995). The BLASTN search revealed that the Fragilis sequence was found in ESTs derived from many different tissues both from embryos and

15   adults, indicating that Fragilis may play a common role in different developmental and cell biological contexts. Database searches reveal a sequence match with the rat interferon-inducible protein (sp:INIB RAT, pir:JC1241) with unknown function. The GCR1 sequence appears six times in our screen, indicating high level expression in PGCs.

20   The second gene, GCR2, (Stella) encodes a 150 amino acid protein, of 18kD. It has no sequence homology with any known protein, contains several nuclear localisation consensus sequences and is highly basic pI (pI=9.67, the content of basic residues=23.3%), indicating a possible affinity to DNA. Furthermore a potential nuclear export signal was identified, indicating that Stella may shuttle between the nucleus and

25   the cytoplasm. BLASTN analysis revealed that the Stella sequence was found only in the preimplantation embryo and germ line (newborn ovary, female 12.5 mesonephros and gonad etc.) ESTs indicating its predominant expression in totipotent and pluripotent cells. Interestingly, we found that Stella contains in its N terminus a modular domain which has some sequence similarity with the SAP motif. This motif is a putative DNA-binding

30   domain involved in chromosomal orgainisation. Furthermore, the SMART program revealed the presence of a splicing factor motif-like structure in its C-terminus, These

findings indicate a possible involvement of Stella in chromosomal organisation and RNA processing.

Antibodies may be raised against the GCR1 and/or GCR2 polypeptides. In particular, antibodies may be raised against the extracellular domain of GCR1, which is a

5 transmembrane polypeptide.

Antibodies and nucleic acids disclosed here are useful for the identification of PGCs in cell populations. The methods and compositions described here therefore provide a means to isolate PGCs, useful for example for the study of germ tissue development and the generation of transgenic animals, and PGCs when isolated by a

10 method described here.

Homologues of GCR1 and GCR2 may also be used to identify PGCs and other pluripotent cells, such as ES or EG cells.

The practice of the present invention will employ, unless otherwise indicated, conventional techniques of chemistry, molecular biology, microbiology, recombinant

15 DNA and immunology, which are within the capabilities of a person of ordinary skill in the art. Such techniques are explained in the literature. See, for example, J. Sambrook, E. F. Fritsch, and T. Maniatis, 1989, *Molecular Cloning: A Laboratory Manual*, Second Edition, Books 1-3, Cold Spring Harbor Laboratory Press; Ausubel, F. M. et al. (1995 and periodic supplements; *Current Protocols in Molecular Biology*, ch. 9, 13, and 16, John

20 Wiley & Sons, New York, N.Y.); B. Roe, J. Crabtree, and A. Kahn, 1996, *DNA Isolation and Sequencing: Essential Techniques*, John Wiley & Sons; J. M. Polak and James O'D. McGee, 1990, *In Situ Hybridization: Principles and Practice*; Oxford University Press; M. J. Gait (Editor), 1984, *Oligonucleotide Synthesis: A Practical Approach*, Irl Press; and, D. M. J. Lilley and J. E. Dahlberg, 1992, *Methods of Enzymology: DNA Structure*

25 *Part A: Synthesis and Physical Analysis of DNA* Methods in Enzymology, Academic Press. Each of these general texts is herein incorporated by reference.

POLYPEPTIDES

It will be understood that polypeptide sequences disclosed here are not limited to the particular sequences set forth in SEQ ID NO: 2 and SEQ ID NO: 4, or fragments thereof, or sequences obtained from GCR1 or GCR2 protein, but also include

5   homologous sequences obtained from any source, for example related cellular homologues, homologues from other species and variants or derivatives thereof.

This disclosure therefore encompasses variants, homologues or derivatives of the amino acid sequences set forth in SEQ ID NO: 2 and SEQ ID NO: 4, as well as variants, homologues or derivatives of the amino acid sequences encoded by the nucleotide sequences

10   disclosed here.

Homologues

The polypeptides disclosed include homologous sequences obtained from any source, for example related viral/bacterial proteins, cellular homologues and synthetic peptides, as well as variants or derivatives thereof. Thus polypeptides also include those

15   encoding homologues of GCR1 and/or GCR2 from other species including animals such as mammals (e.g. mice, rats or rabbits), especially primates, more especially humans. More specifically, homologues include human homologues.

In the context of the present document, a homologous sequence or homologue is taken to include an amino acid sequence which is at least 60, 70, 80 or 90% identical,

20   preferably at least 95 or 98% identical at the amino acid level over at least 30, preferably 50, 70, 90 or 100 amino acids with GCR1 or GCR2, for example as shown in the sequence listing herein. In the context of this document, a homologous sequence is taken to include an amino acid sequence which is at least 15, 20, 25, 30, 40, 50, 60, 70, 80 or 90% identical, preferably at least 95 or 98% identical at the amino acid level, preferably

25   over at least 50 or 100, preferably 200, 300, 400 or 500 amino acids with the sequence of GCR1 or GCR2, for example GCR1 (SEQ ID NO: 2) and GCR2 (SEQ ID NO: 4). Although homology can also be considered in terms of similarity (i.e. amino acid residues having similar chemical properties/functions), in the context of the present document it is preferred to express homology in terms of sequence identity.

Homology comparisons can be conducted by eye, or more usually, with the aid of readily available sequence comparison programs. These commercially available computer programs can calculate % homology between two or more sequences.

5 % homology may be calculated over contiguous sequences, i.e. one sequence is aligned with the other sequence and each amino acid in one sequence directly compared with the corresponding amino acid in the other sequence, one residue at a time. This is called an "ungapped" alignment. Typically, such ungapped alignments are performed only over a relatively short number of residues (for example less than 50 contiguous amino acids).

Although this is a very simple and consistent method, it fails to take into
10 consideration that, for example, in an otherwise identical pair of sequences, one insertion or deletion will cause the following amino acid residues to be put out of alignment, thus potentially resulting in a large reduction in % homology when a global alignment is performed. Consequently, most sequence comparison methods are designed to produce optimal alignments that take into consideration possible insertions and deletions without
15 penalising unduly the overall homology score. This is achieved by inserting "gaps" in the sequence alignment to try to maximise local homology.

However, these more complex methods assign "gap penalties" to each gap that occurs in the alignment so that, for the same number of identical amino acids, a sequence alignment with as few gaps as possible - reflecting higher relatedness between the two
20 compared sequences - will achieve a higher score than one with many gaps. "Affine gap costs" are typically used that charge a relatively high cost for the existence of a gap and a smaller penalty for each subsequent residue in the gap. This is the most commonly used gap scoring system. High gap penalties will of course produce optimised alignments with fewer gaps. Most alignment programs allow the gap penalties to be modified. However, it is
25 preferred to use the default values when using such software for sequence comparisons. For example when using the GCG Wisconsin Bestfit package (see below) the default gap penalty for amino acid sequences is -12 for a gap and -4 for each extension.

Calculation of maximum % homology therefore firstly requires the production of an optimal alignment, taking into consideration gap penalties. A suitable computer program for

carrying out such an alignment is the GCG Wisconsin Bestfit package (University of Wisconsin, U.S.A.; Devereux *et al.*, 1984, Nucleic Acids Research 12:387). Examples of other software than can perform sequence comparisons include, but are not limited to, the BLAST package (see Ausubel *et al.*, 1999 *ibid* – Chapter 18), FASTA (Atschul *et al.*, 1990, J. Mol. Biol., 403-410) and the GENEWORKS suite of comparison tools. Both BLAST and FASTA are available for offline and online searching (see Ausubel *et al.*, 1999 *ibid*, pages 7-58 to 7-60). However it is preferred to use the GCG Bestfit program.

Although the final % homology can be measured in terms of identity, the alignment process itself is typically not based on an all-or-nothing pair comparison. Instead, a scaled similarity score matrix is generally used that assigns scores to each pairwise comparison based on chemical similarity or evolutionary distance. An example of such a matrix commonly used is the BLOSUM62 matrix - the default matrix for the BLAST suite of programs. GCG Wisconsin programs generally use either the public default values or a custom symbol comparison table if supplied (see user manual for further details). It is preferred to use the public default values for the GCG package, or in the case of other software, the default matrix, such as BLOSUM62.

Once the software has produced an optimal alignment, it is possible to calculate % homology, preferably % sequence identity. The software typically does this as part of the sequence comparison and generates a numerical result.

Variants and Derivatives

The terms "variant" or "derivative" in relation to the amino acid sequences as described here includes any substitution of, variation of, modification of, replacement of, deletion of or addition of one (or more) amino acids from or to the sequence. Preferably, the resultant amino acid sequence retains substantially the same activity as the unmodified sequence, preferably having at least the same activity as the GCR1 and/or GCR2 polypeptides shown in the sequence listings. Thus, the key feature of the sequences – namely that they are specific for PGCs and other pluripotent cells, such as ES or EG cells, and can serve as a marker for these cells in a cell population – is preferably retained.

Polypeptides having the amino acid sequence shown in the Examples, or fragments or homologues thereof may be modified for use in the methods and compositions described here. Typically, modifications are made that maintain the biological activity of the sequence. Amino acid substitutions may be made, for example

5   from 1, 2 or 3 to 10, 20 or 30 substitutions provided that the modified sequence retains the biological activity of the unmodified sequence. Amino acid substitutions may include the use of non-naturally occurring analogues, for example to increase blood plasma half-life of a therapeutically administered polypeptide.

Natural variants of GCR1 and GCR2 are likely to comprise conservative amino

10   acid substitutions. Conservative substitutions may be defined, for example according to the Table below. Amino acids in the same block in the second column and preferably in the same line in the third column may be substituted for each other:

ALIPHATIC	Non-polar	G A P
		I L V
	Polar - uncharged	C S T M
		N Q
	Polar - charged	D E
		K R
AROMATIC		H F W Y

Fragments

15   Polypeptides disclosed here and useful as markers also include fragments of the above mentioned full length polypeptides and variants thereof, including fragments of the sequences set out in SEQ ID NO:2 and SEQ ID NO: 4.

Polypeptides also include fragments of the full length sequence of any of the GCR1 and/or GCR2 polypeptides. Preferably fragments comprise at least one epitope.

20   Methods of identifying epitopes are well known in the art. Fragments will typically comprise at least 6 amino acids, more preferably at least 10, 20, 30, 50 or 100 amino acids.

Included are fragments comprising, preferably consisting of, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83,

5   84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100, 105, 110, 115, 120, 125, 130, 135, 140, 145 or 150, or more residues from a GCR1 and/or GCR2 amino acid sequence.

Polypeptide fragments of the GCR proteins and allelic and species variants thereof may contain one or more (e.g. 5, 10, 15, or 20) substitutions, deletions or insertions,

10   including conserved substitutions. Where substitutions, deletion and/or insertions occur, for example in different species, preferably less than 50%, 40% or 20% of the amino acid residues depicted in the sequence listings are altered.

GCR1 and/ GCR2, and their fragments, homologues, variants and derivatives, may be made by recombinant means. Howeve,r they may also be made by synthetic

15   means using techniques well known to skilled persons such as solid phase synthesis. The proteins may also be produced as fusion proteins, for example to aid in extraction and purification. Examples of fusion protein partners include glutathione-S-transferase (GST), 6xHis, GAL4 (DNA binding and/or transcriptional activation domains) and β-galactosidase. It may also be convenient to include a proteolytic cleavage site between the

20   fusion protein partner and the protein sequence of interest to allow removal of fusion protein sequences. Preferably the fusion protein will not hinder the function of the protein of interest sequence. Proteins may also be obtained by purification of cell extracts from animal cells.

The GCR1 and/or GCR2 polypeptides, variants, homologues, fragments and

25   derivatives disclosed here may be in a substantially isolated form. It will be understood that such polypeptides may be mixed with carriers or diluents which will not interfere with the intended purpose of the protein and still be regarded as substantially isolated. A GCR1/GCR2 variant, homologue, fragment or derivative may also be in a substantially purified form, in which case it will generally comprise the protein in a preparation in

which more than 90%, e.g. 95%, 98% or 99% of the protein in the preparation is a protein.

The GCR1/GCR2 polypeptides, variants, homologues, fragments and derivatives disclosed here may be labelled with a revealing label. The revealing label may be any suitable label which allows the polypeptide , etc to be detected. Suitable labels include radioisotopes, e.g. ^{125}I, enzymes, antibodies, polynucleotides and linkers such as biotin. Labelled polypeptides may be used in diagnostic procedures such as immunoassays to determine the amount of a polypeptide in a sample. Polypeptides or labelled polypeptides may also be used in serological or cell-mediated immune assays for the detection of immune reactivity to said polypeptides in animals and humans using standard protocols.

GCR1/GCR2 polypeptides, variants, homologues, fragments and derivatives disclosed here, optionally labelled, my also be fixed to a solid phase, for example the surface of an immunoassay well or dipstick. Such labelled and/or immobilised polypeptides may be packaged into kits in a suitable container along with suitable reagents, controls, instructions and the like. Such polypeptides and kits may be used in methods of detection of antibodies to the polypeptides or their allelic or species variants by immunoassay.

Immunoassay methods are well known in the art and will generally comprise: (a) providing a polypeptide comprising an epitope bindable by an antibody against said protein; (b) incubating a biological sample with said polypeptide under conditions which allow for the formation of an antibody-antigen complex; and (c) determining whether antibody-antigen complex comprising said polypeptide is formed.

The GCR1/GCR2 polypeptides, variants, homologues, fragments and derivatives disclosed here may be used in *in vitro* or *in vivo* cell culture systems to study the role of their corresponding genes and homologues thereof in cell function, including their function in disease. For example, truncated or modified polypeptides may be introduced into a cell to disrupt the normal functions which occur in the cell. The polypeptides may be introduced into the cell by *in situ* expression of the polypeptide from a recombinant expression vector (see below). The expression vector optionally carries an inducible promoter to control the expression of the polypeptide.

The use of appropriate host cells, such as insect cells or mammalian cells, is expected to provide for such post-translational modifications (e.g. myristolation, glycosylation, truncation, lapidation and tyrosine, serine or threonine phosphorylation) as may be needed to confer optimal biological activity on recombinant expression products.

5   Such cell culture systems in which the GCR1/GCR2 polypeptides, variants, homologues, fragments and derivatives disclosed here are expressed may be used in assay systems to identify candidate substances which interfere with or enhance the functions of the polypeptides in the cell.

GCR1/GCR2 NUCLEIC ACIDS

10   The methods and compositions described here provide generally for a number of GCR1 and GCR2 nucleic acids, together with fragments, homologues, variants and derivatives thereof. These nucleic acid sequences preferably encode the polypeptide sequences disclosed here, and particularly in the sequence listings. Preferably, the polynucleotides comprise Stella and/or Fragilis nucleic acids, preferably selected from the

15   group consisting of: SEQ ID NO: 1, 3, 5, 6, 7, 8 or 9, fragments, homologues, variants and derivatives thereof.

In particular, we provide for nucleic acids which encode any of the GCR1 and/or GCR2 polypeptides disclosed here. Thus, the terms "GCR nucleic acid", "GCR1 nucleic acid" and "GCR2 nucleic acid" should be construed accordingly. Preferably, however,

20   such nucleic acids comprise any of the sequences set out as SEQ ID NO: 1, 3, 5, 6, 7, 8 or 9 or a sequence encoding any of the polypeptides SEQ ID NO: 2 and 4, and a fragment, homologue, variant or derivative of such a nucleic acid. The above terms therefore preferably should be taken to refer to these sequences.

As used here in this document, the terms "polynucleotide", "nucleotide", and

25   nucleic acid are intended to be synonymous with each other. "Polynucleotide" generally refers to any polyribonucleotide or polydeoxribonucleotide, which may be unmodified RNA or DNA or modified RNA or DNA. "Polynucleotides" include, without limitation single- and double-stranded DNA, DNA that is a mixture of single- and double-stranded regions, single- and double-stranded RNA, and RNA that is mixture of single- and

double-stranded regions, hybrid molecules comprising DNA and RNA that may be single-stranded or, more typically, double-stranded or a mixture of single- and double-stranded regions. In addition, "polynucleotide" refers to triple-stranded regions comprising RNA or DNA or both RNA and DNA. The term polynucleotide also includes DNAs or RNAs containing one or more modified bases and DNAs or RNAs with backbones modified for stability or for other reasons. "Modified" bases include, for example, tritylated bases and unusual bases such as inosine. A variety of modifications has been made to DNA and RNA; thus, "polynucleotide" embraces chemically, enzymatically or metabolically modified forms of polynucleotides as typically found in nature, as well as the chemical forms of DNA and RNA characteristic of viruses and cells. "Polynucleotide" also embraces relatively short polynucleotides, often referred to as oligonucleotides.

It will be understood by a skilled person that numerous different polynucleotides and nucleic acids can encode the same polypeptide as a result of the degeneracy of the genetic code. In addition, it is to be understood that skilled persons may, using routine techniques, make nucleotide substitutions that do not affect the polypeptide sequence encoded by the polynucleotides described here to reflect the codon usage of any particular host organism in which the polypeptides are to be expressed.

Variants, Derivatives and Homologues

The polynucleotides described here may comprise DNA or RNA. They may be single-stranded or double-stranded. They may also be polynucleotides which include within them synthetic or modified nucleotides. A number of different types of modification to oligonucleotides are known in the art. These include methylphosphonate and phosphorothioate backbones, addition of acridine or polylysine chains at the 3' and/or 5' ends of the molecule. For the purposes of the present document, it is to be understood that the polynucleotides described herein may be modified by any method available in the art. Such modifications may be carried out in order to enhance the *in vivo* activity or life span of polynucleotides.

Where the polynucleotide is double-stranded, both strands of the duplex, either individually or in combination, are encompassed by the methods and compositions described here. Where the polynucleotide is single-stranded, it is to be understood that the complementary sequence of that polynucleotide is also included.

5   The terms "variant", "homologue" or "derivative" in relation to a nucleotide sequence include any substitution of, variation of, modification of, replacement of, deletion of or addition of one (or more) nucleotides from or to the sequence providing the resultant nucleotide sequence is specific for pluripotent cells, preferably specific for PGCs, ES cells or EG cells. Most preferably, the resultant nucleotide sequence is specific for PGCs.

10   As indicated above, with respect to sequence identity, a "homologue" has preferably at least 5% identity, at least 10% identity, at least 15% identity, at least 20% identity, at least 25% identity, at least 30% identity, at least 35% identity, at least 40% identity, at least 45% identity, at least 50% identity, at least 55% identity, at least 60% identity, at least 65% identity, at least 70% identity, at least 75% identity, at least 80%
15   identity, at least 85% identity, at least 90% identity, or at least 95% identity to the relevant sequence shown in the sequence listings.

        More preferably there is at least 95% identity, more preferably at least 96% identity, more preferably at least 97% identity, more preferably at least 98% identity, more preferably at least 99% identity. Nucleotide homology comparisons may be
20   conducted as described above. A preferred sequence comparison program is the GCG Wisconsin Bestfit program described above. The default scoring matrix has a match value of 10 for each identical nucleotide and -9 for each mismatch. The default gap creation penalty is -50 and the default gap extension penalty is -3 for each nucleotide.

        Hybridisation

25   We further describe nucleotide sequences that are capable of hybridising selectively to any of the sequences presented herein, or any variant, fragment or derivative thereof, or to the complement of any of the above. Nucleotide sequences are preferably at least 15 nucleotides in length, more preferably at least 20, 30, 40 or 50 nucleotides in length.

The term "hybridisation" as used herein shall include "the process by which a strand of nucleic acid joins with a complementary strand through base pairing" as well as the process of amplification as carried out in polymerase chain reaction technologies.

5   Polynucleotides capable of selectively hybridising to the nucleotide sequences presented herein, or to their complement, will be generally at least 70%, preferably at least 80 or 90% and more preferably at least 95% or 98% homologous to the corresponding nucleotide sequences presented herein over a region of at least 20, preferably at least 25 or 30, for instance at least 40, 60 or 100 or more contiguous nucleotides.

10   The term "selectively hybridisable" means that the polynucleotide used as a probe is used under conditions where a target polynucleotide is found to hybridize to the probe at a level significantly above background. The background hybridization may occur because of other polynucleotides present, for example, in the cDNA or genomic DNA library being screening. In this event, background implies a level of signal generated by interaction between the probe and a non-specific DNA member of the library which is less than 10 fold,

15   preferably less than 100 fold as intense as the specific interaction observed with the target DNA. The intensity of interaction may be measured, for example, by radiolabelling the probe, e.g. with ^{32}P.

Hybridisation conditions are based on the melting temperature (Tm) of the nucleic acid binding complex, as taught in Berger and Kimmel (1987, Guide to Molecular

20   Cloning Techniques, Methods in Enzymology, Vol 152, Academic Press, San Diego CA), and confer a defined "stringency" as explained below.

Maximum stringency typically occurs at about Tm-5°C (5°C below the Tm of the probe); high stringency at about 5°C to 10°C below Tm; intermediate stringency at about 10°C to 20°C below Tm; and low stringency at about 20°C to 25°C below Tm. As will be

25   understood by those of skill in the art, a maximum stringency hybridisation can be used to identify or detect identical polynucleotide sequences while an intermediate (or low) stringency hybridisation can be used to identify or detect similar or related polynucleotide sequences.

In a preferred aspect, we disclose nucleotide sequences that can hybridise to a GCR1/GCR2 nucleic acid, or a fragment, homologue, variant or derivative thereof, under stringent conditions (e.g. 65°C and 0.1xSSC {1xSSC = 0.15 M NaCl, 0.015 M Na$_3$ Citrate pH 7.0}).

5   Where a polynucleotide is double-stranded, both strands of the duplex, either individually or in combination, are encompassed by the present disclosure. Where the polynucleotide is single-stranded, it is to be understood that the complementary sequence of that polynucleotide is also disclosed and encompassed.

          Polynucleotides which are not 100% homologous to the sequences disclosed here but
10   fall within the disclosure can be obtained in a number of ways. Other variants of the sequences described herein may be obtained for example by probing DNA libraries made from a range of individuals, for example individuals from different populations. In addition, other viral/bacterial, or cellular homologues particularly cellular homologues found in mammalian cells (e.g. rat, mouse, bovine and primate cells, including human cells), may be
15   obtained and such homologues and fragments thereof in general will be capable of selectively hybridising to the sequences shown in the sequence listing herein. Such sequences may be obtained by probing cDNA libraries made from or genomic DNA libraries from other animal species, and probing such libraries with probes comprising all or part of SEQ ID NOs: 1 or 3 under conditions of medium to high stringency. Similar
20   considerations apply to obtaining species homologues and allelic variants of GCR1 and GCR2.

          The polynucleotides described here may be used to produce a primer, e.g. a PCR primer, a primer for an alternative amplification reaction, a probe e.g. labelled with a revealing label by conventional means using radioactive or non-radioactive labels, or the
25   polynucleotides may be cloned into vectors. Such primers, probes and other fragments will be at least 15, preferably at least 20, for example at least 25, 30 or 40 nucleotides in length, and are also encompassed by the term polynucleotides as used herein. Preferred fragments are less than 500, 200, 100, 50 or 20 nucleotides in length.

Polynucleotides such as a DNA polynucleotides and probes may be produced recombinantly, synthetically, or by any means available to those of skill in the art. They may also be cloned by standard techniques.

In general, primers will be produced by synthetic means, involving a step wise
5   manufacture of the desired nucleic acid sequence one nucleotide at a time. Techniques for accomplishing this using automated techniques are readily available in the art.

Longer polynucleotides will generally be produced using recombinant means, for example using PCR (polymerase chain reaction) cloning techniques. This will involve making a pair of primers (e.g. of about 15 to 30 nucleotides) flanking a region of the
10   sequence which it is desired to clone, bringing the primers into contact with mRNA or cDNA obtained from an animal or human cell, performing a polymerase chain reaction under conditions which bring about amplification of the desired region, isolating the amplified fragment (e.g. by purifying the reaction mixture on an agarose gel) and recovering the amplified DNA. The primers may be designed to contain suitable restriction enzyme
15   recognition sites so that the amplified DNA can be cloned into a suitable cloning vector

NUCLEOTIDE VECTORS

The polynucleotides can be incorporated into a recombinant replicable vector. The vector may be used to replicate the nucleic acid in a compatible host cell. Thus in a further embodiment, we provide a method of making polynucleotides by introducing a
20   polynucleotide into a replicable vector, introducing the vector into a compatible host cell, and growing the host cell under conditions which bring about replication of the vector. The vector may be recovered from the host cell. Suitable host cells include bacteria such as *E. coli*, yeast, mammalian cell lines and other eukaryotic cell lines, for example insect Sf9 cells.

25   Preferably, a polynucleotide in a vector is operably linked to a control sequence that is capable of providing for the expression of the coding sequence by the host cell, i.e. the vector is an expression vector. The term "operably linked" means that the components described are in a relationship permitting them to function in their intended manner. A

regulatory sequence "operably linked" to a coding sequence is ligated in such a way that expression of the coding sequence is achieved under condition compatible with the control sequences.

The control sequences may be modified, for example by the addition of further
5   transcriptional regulatory elements to make the level of transcription directed by the control sequences more responsive to transcriptional modulators.

Vectors may be transformed or transfected into a suitable host cell as described below to provide for expression of a protein. This process may comprise culturing a host cell transformed with an expression vector as described above under conditions to provide
10   for expression by the vector of a coding sequence encoding the protein, and optionally recovering the expressed protein.

The vectors may be for example, plasmid or virus vectors provided with an origin of replication, optionally a promoter for the expression of the said polynucleotide and optionally a regulator of the promoter. The vectors may contain one or more selectable
15   marker genes, for example an ampicillin resistance gene in the case of a bacterial plasmid or a neomycin resistance gene for a mammalian vector. Vectors may be used, for example, to transfect or transform a host cell.

Control sequences operably linked to sequences encoding the protein include promoters/enhancers and other expression regulation signals. These control sequences
20   may be selected to be compatible with the host cell for which the expression vector is designed to be used in. The term "promoter" is well-known in the art and encompasses nucleic acid regions ranging in size and complexity from minimal promoters to promoters including upstream elements and enhancers.

The promoter is typically selected from promoters which are functional in
25   mammalian cells, although prokaryotic promoters and promoters functional in other eukaryotic cells may be used. The promoter is typically derived from promoter sequences of viral or eukaryotic genes. For example, it may be a promoter derived from the genome of a cell in which expression is to occur. With respect to eukaryotic promoters, they may

be promoters that function in a ubiquitous manner (such as promoters of α-actin, β-actin, tubulin) or, alternatively, a tissue-specific manner (such as promoters of the genes for pyruvate kinase). They may also be promoters that respond to specific stimuli, for example promoters that bind steroid hormone receptors. Viral promoters may also be

5 used, for example the Moloney murine leukaemia virus long terminal repeat (MMLV LTR) promoter, the Rous sarcoma virus (RSV) LTR promoter or the human cytomegalovirus (CMV) IE promoter.

It may also be advantageous for the promoters to be inducible so that the levels of expression of the heterologous gene can be regulated during the life-time of the cell.

10 Inducible means that the levels of expression obtained using the promoter can be regulated.

In addition, any of these promoters may be modified by the addition of further regulatory sequences, for example enhancer sequences. Chimeric promoters may also be used comprising sequence elements from two or more different promoters described

15 above.

HOST CELLS

Vectors and polynucleotides disclosed here may be introduced into host cells for the purpose of replicating the vectors/polynucleotides and/or expressing the proteins. Although the proteins may be produced using prokaryotic cells as host cells, it is

20 preferred to use eukaryotic cells, for example yeast, insect or mammalian cells, in particular mammalian cells.

Vectors/polynucleotides may introduced into suitable host cells using a variety of techniques known in the art, such as transfection, transformation and electroporation. Where vectors/polynucleotides as disclosed here are to be administered to animals,

25 several techniques are known in the art, for example infection with recombinant viral vectors such as retroviruses, herpes simplex viruses and adenoviruses, direct injection of nucleic acids and biolistic transformation.

PROTEIN EXPRESSION AND PURIFICATION

Host cells comprising polynucleotides disclosed here may be used to express proteins. Host cells may be cultured under suitable conditions which allow expression of the proteins. Expression of the proteins described here may be constitutive such that they

5 are continually produced, or inducible, requiring a stimulus to initiate expression. In the case of inducible expression, protein production can be initiated when required by, for example, addition of an inducer substance to the culture medium, for example dexamethasone or IPTG.

Proteins can be extracted from host cells by a variety of techniques known in the

10 art, including enzymatic, chemical and/or osmotic lysis and physical disruption.

RECOMBINANT STELLA AND FRAGILIS PROTEINS

Nucleotide sequences of Stella and Fragilis are cloned into a TRI-system vector (Qiagen). Stella sequence comprising the second codon onwards (i.e., an N terminal fragment of Stella without the first ATG codon) is cloned into a pQE vector using

15 appropriate restriction enzyme sites, and according to the manufacturers instructions. QIAexpress pQE vectors enable high-level expression of 6xHis-tagged proteins in *E. coli*.

A His tag is placed in the N terminal portion of the Stella gene. Recombinant protein is purified by affinity chromatography on a Ni-NTA column, according to manufacturer's instructions. The His tag is cleaved using a suitable protease.

20 Recombinantly expressed Stella and Fragilis protein are found to be biologically active.

ANTIBODIES

Antibodies, as used herein, refers to complete antibodies or antibody fragments capable of binding to a selected target, and including Fv, ScFv, Fab' and F(ab')2,

25 monoclonal and polyclonal antibodies, engineered antibodies including chimeric, CDR-

grafted and humanised antibodies, and artificially selected antibodies produced using phage display or alternative techniques. Small fragments, such as Fv and ScFv, possess advantageous properties for diagnostic and therapeutic applications on account of their small size and consequent superior tissue distribution.

5   The antibodies according described here are especially indicated for the detection of PGCs and other pluripotent cells, such as ES or EG cells. Accordingly, they may be altered antibodies comprising an effector protein such as a label. Especially preferred are labels which allow the imaging of the distribution of the antibody *in vivo* or *in vitro*. Such labels may be radioactive labels or radioopaque labels, such as metal particles, which are

10   readily visualisable within an embryo or a cell mass. Moreover, they may be fluorescent labels or other labels which are visualisable on tissue samples.

Recombinant DNA technology may be used to improve the antibodies as described here. Thus, chimeric antibodies may be constructed in order to decrease the immunogenicity thereof in diagnostic or therapeutic applications. Moreover,

15   immunogenicity may be minimised by humanising the antibodies by CDR grafting [see European Patent Application 0 239 400 (Winter)] and, optionally, framework modification [EP 0 239 400].

Antibodies may be obtained from animal serum, or, in the case of monoclonal antibodies or fragments thereof, produced in cell culture. Recombinant DNA technology

20   may be used to produce the antibodies according to established procedure, in bacterial or preferably mammalian cell culture. The selected cell culture system preferably secretes the antibody product.

Therefore, we disclose a process for the production of an antibody comprising culturing a host, e.g. E. coli or a mammalian cell, which has been transformed with a

25   hybrid vector comprising an expression cassette comprising a promoter operably linked to a first DNA sequence encoding a signal peptide linked in the proper reading frame to a second DNA sequence encoding said antibody protein, and isolating said protein.

Multiplication of hybridoma cells or mammalian host cells in vitro is carried out in suitable culture media, which are the customary standard culture media, for example Dulbecco's Modified Eagle Medium (DMEM) or RPMI 1640 medium, optionally replenished by a mammalian serum, e.g. foetal calf serum, or trace elements and growth sustaining supplements, e.g. feeder cells such as normal mouse peritoneal exudate cells, spleen cells, bone marrow macrophages, 2-aminoethanol, insulin, transferrin, low density lipoprotein, oleic acid, or the like. Multiplication of host cells which are bacterial cells or yeast cells is likewise carried out in suitable culture media known in the art, for example for bacteria in medium LB, NZCYM, NZYM, NZM, Terrific Broth, SOB, SOC, 2 x YT, or M9 Minimal Medium, and for yeast in medium YPD, YEPD, Minimal Medium, or Complete Minimal Dropout Medium.

In vitro production provides relatively pure antibody preparations and allows scale-up to give large amounts of the desired antibodies. Techniques for bacterial cell, yeast or mammalian cell cultivation are known in the art and include homogeneous suspension culture, e.g. in an airlift reactor or in a continuous stirrer reactor, or immobilised or entrapped cell culture, e.g. in hollow fibres, microcapsules, on agarose microbeads or ceramic cartridges.

Large quantities of the desired antibodies can also be obtained by multiplying mammalian cells in vivo. For this purpose, hybridoma cells producing the desired antibodies are injected into histocompatible mammals to cause growth of antibody-producing tumours. Optionally, the animals are primed with a hydrocarbon, especially mineral oils such as pristane (tetramethyl-pentadecane), prior to the injection. After one to three weeks, the antibodies are isolated from the body fluids of those mammals. For example, hybridoma cells obtained by fusion of suitable myeloma cells with antibody-producing spleen cells from Balb/c mice, or transfected cells derived from hybridoma cell line Sp2/0 that produce the desired antibodies are injected intraperitoneally into Balb/c mice optionally pre-treated with pristane, and, after one to two weeks, ascitic fluid is taken from the animals.

The foregoing, and other, techniques are discussed in, for example, Kohler and Milstein, (1975) Nature 256:495-497; US 4,376,110; Harlow and Lane, Antibodies: a

Laboratory Manual, (1988) Cold Spring Harbor, incorporated herein by reference. Techniques for the preparation of recombinant antibody molecules is described in the above references and also in, for example, EP 0623679; EP 0368684 and EP 0436597, which are incorporated herein by reference.

5   The cell culture supernatants are screened for the desired antibodies, preferentially by immunofluorescent staining of PGCs or other pluripotent cells, such as ES or EG cells, by immunoblotting, by an enzyme immunoassay, e.g. a sandwich assay or a dot-assay, or a radioimmunoassay.

    For isolation of the antibodies, the immunoglobulins in the culture supernatants

10 or in the ascitic fluid may be concentrated, e.g. by precipitation with ammonium sulphate, dialysis against hygroscopic material such as polyethylene glycol, filtration through selective membranes, or the like. If necessary and/or desired, the antibodies are purified by the customary chromatography methods, for example gel filtration, ion-exchange chromatography, chromatography over DEAE-cellulose and/or (immuno-) affinity

15 chromatography, e.g. affinity chromatography with GCR1 or GCR2, or fragments thereof, or with Protein-A.

    Hybridoma cells secreting the monoclonal antibodies are also provided. Preferred hybridoma cells are genetically stable, secrete monoclonal antibodies of the desired specificity and can be activated from deep-frozen cultures by thawing and recloning.

20   Also included is a process for the preparation of a hybridoma cell line secreting monoclonal antibodies directed to GCR1 and/or GCR2, characterised in that a suitable mammal, for example a Balb/c mouse, is immunised with a one or more GCR1 or GCR2 polypeptides, or antigenic fragments thereof; antibody-producing cells of the immunised mammal are fused with cells of a suitable myeloma cell line, the hybrid cells obtained in

25 the fusion are cloned, and cell clones secreting the desired antibodies are selected. For example spleen cells of Balb/c mice immunised with GCR1 and/or GCR2 are fused with cells of the myeloma cell line PAI or the myeloma cell line Sp2/0-Ag14, the obtained hybrid cells are screened for secretion of the desired antibodies, and positive hybridoma cells are cloned.

Preferred is a process for the preparation of a hybridoma cell line, characterised in that Balb/c mice are immunised by injecting subcutaneously and/or intraperitoneally between 10 and 10^7 and 10^8 cells expressing GCR1 and/or GCR2 and a suitable adjuvant several times, e.g. four to six times, over several months, e.g. between two and four

5 months, and spleen cells from the immunised mice are taken two to four days after the last injection and fused with cells of the myeloma cell line PAI in the presence of a fusion promoter, preferably polyethylene glycol. Preferably the myeloma cells are fused with a three- to twentyfold excess of spleen cells from the immunised mice in a solution containing about 30 % to about 50 % polyethylene glycol of a molecular weight around

10 4000. After the fusion the cells are expanded in suitable culture media as described hereinbefore, supplemented with a selection medium, for example HAT medium, at regular intervals in order to prevent normal myeloma cells from overgrowing the desired hybridoma cells.

Recombinant DNAs comprising an insert coding for a heavy chain variable

15 domain and/or for a light chain variable domain of antibodies directed to GCR1 and/or GCR2 as described hereinbefore are also disclosed. By definition such DNAs comprise coding single stranded DNAs, double stranded DNAs consisting of said coding DNAs and of complementary DNAs thereto, or these complementary (single stranded) DNAs themselves.

20 Furthermore, DNA encoding a heavy chain variable domain and/or for a light chain variable domain of antibodies directed to GCR1 and/or GCR2 can be enzymatically or chemically synthesised DNA having the authentic DNA sequence coding for a heavy chain variable domain and/or for the light chain variable domain, or a mutant thereof. A mutant of the authentic DNA is a DNA encoding a heavy chain variable domain and/or a

25 light chain variable domain of the above-mentioned antibodies in which one or more amino acids are deleted or exchanged with one or more other amino acids. Preferably said modification(s) are outside the CDRs of the heavy chain variable domain and/or of the light chain variable domain of the antibody. Such a mutant DNA is also intended to be a silent mutant wherein one or more nucleotides are replaced by other nucleotides with the

30 new codons coding for the same amino acid(s). Such a mutant sequence is also a degenerated sequence. Degenerated sequences are degenerated within the meaning of the

genetic code in that an unlimited number of nucleotides are replaced by other nucleotides without resulting in a change of the amino acid sequence originally encoded. Such degenerated sequences may be useful due to their different restriction sites and/or frequency of particular codons which are preferred by the specific host, particularly *E. coli*, to obtain an optimal expression of the heavy chain murine variable domain and/or a light chain murine variable domain.

The term mutant is intended to include a DNA mutant obtained by in vitro mutagenesis of the authentic DNA according to methods known in the art.

For the assembly of complete tetrameric immunoglobulin molecules and the expression of chimeric antibodies, the recombinant DNA inserts coding for heavy and light chain variable domains are fused with the corresponding DNAs coding for heavy and light chain constant domains, then transferred into appropriate host cells, for example after incorporation into hybrid vectors.

Also disclosed are recombinant DNAs comprising an insert coding for a heavy chain murine variable domain of an antibody directed to GCR1 and/or GCR2 fused to a human constant domain g, for example γ1, γ2, γ3 or γ4, preferably γ1 or γ4. Likewise the invention concerns recombinant DNAs comprising an insert coding for a light chain murine variable domain of an antibody directed to GCR1 and/or GCR2 fused to a human constant domain κ or λ, preferably κ.

In another embodiment, we disclose recombinant DNAs coding for a recombinant polypeptide wherein the heavy chain variable domain and the light chain variable domain are linked by way of a spacer group, optionally comprising a signal sequence facilitating the processing of the antibody in the host cell and/or a DNA coding for a peptide facilitating the purification of the antibody and/or a cleavage site and/or a peptide spacer and/or an effector molecule.

The DNA coding for an effector molecule is intended to be a DNA coding for the effector molecules useful in diagnostic or therapeutic applications. Thus, effector molecules which are toxins or enzymes, especially enzymes capable of catalysing the

activation of prodrugs, are particularly indicated. The DNA encoding such an effector molecule has the sequence of a naturally occurring enzyme or toxin encoding DNA, or a mutant thereof, and can be prepared by methods well known in the art.

ANTI-PEPTIDE STELLA AND FRAGILIS ANTIBODIES

5   Anti-peptide antibodies are produced against Stella and Fragilis peptide sequences. The sequences chosen are as follow:

GCR1 (Fragilis): ASGGQPPNYERIKEEYE and RDRKMVGDVTGAQAYA

GCR2 (Stella): MEEPSEKVDPMKDPET and CHYQRWDPSENAKIGKN

Antibodies are produced by injection into rabbits, and other conventional means,
10   as described in for example, Harlow and Lane (supra).

Antibodies are checked by Elisa assay and by Western blotting, and used for immunostaining as described in the Examples.

DETECTION OF PLURIPOTENT CELLS IN CELL POPULATIONS

Polynucleotide probes or antibodies as described here may be used for the
15   detection of pluripotent cells such as primordial germ cells (PGCs), stem cells such as embryonic stem (ES) and embryonic germ (EG) cells in cell populations. As used herein, a "cell population" is any collection of cells which may contain one or more PGCs, ES or EG cells. Preferably, the collection of cells does not consist solely of PGCs, but comprises at least one other cell type.

20   Cell populations comprise embryos and embryo tissue, but also adult tissues and tissues grown in culture and cell preparations derived from any of the foregoing.

Polynucleotides as described here may be used for detection of GCR1 and GCR2 transcripts in PGCs or other pluripotent cells, such as ES or EG cells, by nucleic acid

hybridisation techniques. Such techniques include PCR, in which primers are hybridised to GCR1 and/or GCR2 transcripts and used to amplify the transcripts, to provide a detectable signal; and hybridisation of labelled probes, in which probes specific for an unique sequence in the GCR1 and/or GCR2 transcript are used to detect the transcript in the target cells.

As noted hereinbefore, probes may be labelled with radioactive, radioopaque, fluorescent or other labels, as is known in the art.

The antibodies may also be used to detect GCR1 and/or GCR2. GRC1, in particular, possesses an extracellular domain which may be targeted by an anti-GCR1 antibody and detected at the cell surface. Alternatively, intracellular scFv may be used to detect GCR1 and/or GCR2 within the cell.

Particularly indicated are immunostaining and FACS techniques. Suitable fluorophores are known in the art, and include chemical fluorophores and fluorescent polypeptides, such as GFP and mutants thereof (see WO 97/28261). Chemical fluorophores may be attached to immunoglobulin molecules by incorporating binding sites therefor into the immunoglobulin molecule during the synthesis thereof.

Preferably, the fluorophore is a fluorescent protein, which is advantageously GFP or a mutant thereof. GFP and its mutants may be synthesised together with the immunoglobulin or target molecule by expression therewith as a fusion polypeptide, according to methods well known in the art. For example, a transcription unit may be constructed as an in-frame fusion of the desired GFP and the immunoglobulin or target, and inserted into a vector as described above, using conventional PCR cloning and ligation techniques.

Antibodies may be labelled with any label capable of generating a signal. The signal may be any detectable signal, such as the induction of the expression of a detectable gene product. Examples of detectable gene products include bioluminescent polypeptides, such as luciferase and GFP, polypeptides detectable by specific assays, such as β-galactosidase and CAT, and polypeptides which modulate the growth characteristics

of the host cell, such as enzymes required for metabolism such as HIS3, or antibiotic resistance genes such as G418. In a preferred aspect, the signal is detectable at the cell surface. For example, the signal may be a luminescent or fluorescent signal, which is detectable from outside the cell and allows cell sorting by FACS or other optical sorting techniques.

Preferred is the use of optical immunosensor technology, based on optical detection of fluorescently-labelled antibodies. Immunosensors are biochemical detectors comprising an antigen or antibody species coupled to a signal transducer which detects the binding of the complementary species (Rabbany *et al.*, 1994 *Crit Rev Biomed Eng* **22**:307-346; Morgan *et al.*, 1996 *Clin Chem* **42**:193-209). Examples of such complementary species include the antigen Zif 268 and the anti-Zif 268 antibody. Immunosensors produce a quantitative measure of the amount of antibody, antigen or hapten present in a complex sample such as serum or whole blood (Robinson 1991 *Biosens Bioelectron* **6**:183-191). The sensitivity of immunosensors makes them ideal for situations requiring speed and accuracy (Rabbany *et al.*, 1994 *Crit Rev Biomed Eng* **22**:307-346).

Detection techniques employed by immunosensors include electrochemical, piezoelectric or optical detection of the immunointeraction (Ghindilis *et al.*, 1998 *Biosens Bioelectron* **1**:113-131). An indirect immunosensor uses a separate labelled species that is detected after binding by, for example, fluorescence or luminescence (Morgan *et al.*, 1996 *Clin Chem* **42**:193-209). Direct immunosensors detect the binding by a change in potential difference, current, resistance, mass, heat or optical properties (Morgan *et al.*, 1996 *Clin Chem* **42**:193-209). Indirect immunosensors may encounter fewer problems due to non-specific binding (Attridge *et al.*, 1991 *Biosens Bioelecton* **6**:201-214; Morgan *et al.*, 1996 *Clin Chem* **42**:193-209).

FURTHER ASPECTS OF THE INVENTION

We provide a nucleic acid molecule which is at least 90% homologous to SEQ ID NO: 1 and a nucleic acid molecule which is at least 75% homologous to SEQ ID NO: No. 3.

We disclose polynucleotides which comprise a contiguous stretch of nucleotides from SEQ ID NO: 1 or SEQ ID NO: 3, or any of SEQ ID NOs: 5 to 9, or of a sequence at least 90% homologous thereto. Advantageously, this stretch of contiguous nucleotides is 50 nucleotides in length, preferably 40, 35, 30, 25, 20, 15 or 10 nucleotides in length.

5   The genes GCR1 and GCR2 encode novel polypeptides, the sequences of which are set forth in SEQ ID NO: 2 and SEQ ID NO: 4. We therefore disclose polypeptides encoded by the nucleic acids described here. Preferably, the polypeptides have the sequences set forth in SEQ ID NO: 2 and SEQ ID NO: 4.

Moreover, we provide a method by which genes specifically expressed in PGCs or

10   other pluripotent cells, such as ES or EG cells, may be isolated, comprising the steps of: (a) providing a population of cells containing PGCs or other pluripotent cells, such as ES or EG cells; (b) isolating one or more PGCs or other pluripotent cells, such as ES or EG cells, therefrom and providing single-cell isolates; (c) amplifying the transcribed nucleic acid present in a single cell; (d) conducting a subtractive hybridisation screen to identify

15   transcripts present in the PGCs or other pluripotent cells, such as ES or EG cells, but not in somatic cells; and (e) probing a nucleic acid library with one or more transcripts identified in d) to clone one or more genes which are specifically expressed.

Further aspects of the invention are now set out in the following numbered paragraphs; it is to be understood that the invention encompasses these aspects:

20   Paragraph 1.   A nucleic acid having at least 90% homology with the sequence set forth in SEQ. ID. No. 1.

Paragraph 2.   A nucleic acid having at least 75% homology with the sequence set forth in SEQ. ID. No. 3.

Paragraph 3.   A nucleic acid comprising a sequence of 25 contiguous nucleotides

25   of the nucleic acid of Paragraph 1 or Paragraph 2.

Paragraph 4. A nucleic acid comprising a sequence of 15 contiguous nucleotides of the nucleic acid of Paragraph 1 or Paragraph 2.

Paragraph 5. The complement of a nucleic acid sequence according to any preceding Paragraph.

5 Paragraph 6. A nucleic acid according to any one of Paragraphs 1 to 5, comprising one or more nucleotide substitutions, wherein such substitutions do not alter the coding specificity of said nucleic acid as a result of the degeneracy of the genetic code.

Paragraph 7. A polypeptide encoded by a nucleic acid according to any

10 preceding Paragraph.

Paragraph 8. A method for identifying a primordial germ cell in a population of cells, comprising detecting the expression of a nucleic acid sequence according to Paragraph 1 or Paragraph 2, or a homologue thereof.

Paragraph 9. A method according to Paragraph 8, comprising the steps of

15 amplifying nucleic acids from putative PGCs using 5' and 3' primers specific for GCR1 and/or GCR2, and detecting amplified nucleic acid thus produced.

Paragraph 10. A method according to Paragraph 8, wherein the expression of the nucleic acid sequence is detected by *in situ* hybridisation.

Paragraph 11. A method according to Paragraph 8, wherein the expression of the

20 nucleic acid sequence is determined by detecting the protein product encoded thereby.

Paragraph 12. A method according to Paragraph 11, wherein the protein product is detected by immunostaining.

Paragraph 13. An antibody specific for a polypeptide according to Paragraph 7.

Paragraph 14. An antibody according to Paragraph 13, specific for the extracellular domain of GCR1.

Paragraph 15. Use of an antibody according to Paragraph 13 or Paragraph 14 for the identification of a PGC in a population of cells.

5   Paragraph 16. A PGC when identified by a method according to any one of Paragraphs 8 to 12.

Paragraph 17. A method for isolating a gene specifically expressed in PGCs, comprising the steps of: a) providing a population of cells containing PGCs; b) isolating one or more PGCs therefrom and providing single-cell PGC isolates; c) amplifying the

10   transcribed nucleic acid present in a single PGC; d) conducting a subtractive hybridisation screen to identify transcripts present in PGCs but not in somatic cells; and e) probing a nucleic acid library with one or more transcripts identified in d) to clone one or more genes which are specifically expressed in PGCs.

EXAMPLES

15   **Example 1. Identification of Genes Specific to the Earliest Population of Primordial Germ Cells (PGCs) by Single Cell cDNA Differential Screening**

A method for single cell analysis is developed to identify genes that are involved in the specification of the germ cell lineage, which results in the establishment of a founder population of Primordial Germ Cells (PGCs). It is determined that the lineage

20   specification of PGCs accompanies the expression of a unique set of genes, which are not expressed in somatic cells.

The method for the identification of the genes is mainly based on the differential screening of the libraries made from single cells from day 7.25 mouse embryonic fragments that contain PGCs. The single cell cDNA differential screen was originally

25   described by Brady and Iscove (1993), and subsequently modified by Cathaline Dulac and Richard Axel which resulted in the successful identification of the pheromone

receptor genes from rat (Dulac, C. and Axel, 1995). The method of Axel's group is employed, with slight modifications as described.

Construction of single cell cDNAs from embryonic fragment bearing the earliest population of PGCs

5   In the mouse, the earliest population of the PGCs is reported to consist of alkaline phosphatase positive cluster of some 40 cells, at the base of the emerging allantois at day 7.25 of gestation (Ginsburg, M., Snow, M.H.L., and McLaren, A. (1990)). The precise location of the PGC cluster in the inbred 129Sv and C57BL/6 strain is determined by microscopy using both whole-mount alkaline phosphatase staining and semi-thin sections

10   stained by methylene blue. The earliest stage at which a cluster of PGCs can be detected is at the Late Streak stage (Downs, K.M., and Davies, T. (1993)), when a distinctively stained population of cells is found just beneath an epithelial lining from which the allantoic bud appears. This region is at the border between the extraembryonic and embryonic tissues just posterior to and above the most proximal part of the primitive

15   streak. The cluster persists at this position at least until Early/Mid Bud stage. In the inbred 129Sv strain, the PGC cluster is found to contain a slightly larger number of the cells, which are more tightly packaged than in the C57BL/6 strain. The 129Sv strain is used for subsequent experiments, as a better recovery of the earliest PGCs is obtained.

         129Sv embryos are isolated at E7.5 in DMEM plus 10% FCS buffered with

20   25mM HEPES at room temperature and the developmental stage of each embryo is determined under a dissection microscope. The precise developmental stage can differ substantially even amongst embryos within the same litter. Embryos that are at the no bud or early bud (allantoic) stage are chosen for further dissection, which in part is dictated by the ease of identification of the region containing PGCs as seen under the dissection

25   microscope. The fragment that is expected to contain the PGC cluster is cut out very precisely by means of solid glass needles. This region is dissociated it into single cells using 0.25% trypsin-1mM EGTA/PBS treatment at 37°C for 10 min, followed by gentle pipetting with a mouth pipette. The dissected fragment usually contained between 250-300 cells. The procedure for cell dispersal with this gentle procedure left the visceral

30   endoderm layer remained as an intact cellular sheet.

We picked single cells randomly from the cell suspension by a mouth pipette and put individual single cells (but avoiding generating air bubbles), into a thin-walled PCR tube containing 4μl of ice-cold cell lysis buffer (50mM Tris-HCl pH8.3, 75mM KCl, 3mM $MgCl_2$, 0.5% NP-40, containing 80ng/ml pd(T)24, 5μg/ml prime RNase inhibitor,

5   324U/ml RNA guard, and 10mM each of dATP, dCTP, dGTP, and dTTP). The volume of medium carried with the single cell is less than 0.5μl. The tube is briefly centrifuged to ensure that the cell is indeed in the lysis buffer. During each separate experiment, we picked a total of 19 single cells, and left one tube without a cell, to serve as a negative control for the PCR amplification procedure. All the cells that are collected in tubes are

10   kept on ice before starting the subsequent procedure.

The cells are lysed by incubating the tubes at 65°C for 1min, and then kept at room temperature for 1-2 min to allow the oligo dT to anneal the to RNA. First-strand cDNA synthesis is initiated by adding 50U of Moloney murine leukaemia virus (MMLV) and 0.5U of avian myeloblastosis virus (AMV) reverse transcriptase followed by

15   incubation for 15min at 37°C. The reverse transcriptases are inactivated for 10min at 65°C. This reverse transcription reaction is restricted to 15 min, which allows the synthesis of relatively uniform size cDNAs of between 500 base -1000 bases in length from the C termini. This enables the subsequent PCR amplification to be fairly representative.

20   Next, in order to add the poly A tail to the 5 prime end of the synthesised first-strand cDNA, 4.5μl of 2X tailing buffer (200mM potassium cacodylate pH7.2, 4mM $CoCl_2$, 0.4mM DTT, 200mM dATP containing 10U of terminal transferase) is added to the reaction followed by incubation for 15min at 37 °C. The samples are heat inactivated for 10 min at 65°C. The reaction now contained synthesised cDNAs bearing poly T tail at

25   their C termini and poly A stretch at their N termini, ready for the amplification by the PCR using the specific primer.

The contents of each tube is brought to 100μl with a solution made of 10mM Tris-HCl pH8.3, 50mM KCl, 2.5mM $MgCl_2$, 100μg/ml bovine serum albumin, 0.05% Triton-X 100, 1mM of dATP, dCTP, dGTP, dTTP, 10U of Taq polymerase, and 5μg of the AL1

primer. The AL1 sequence is ATT GGA TCC AGG CCG CTC TGG ACA AAA TAT GAA TCC (T)$_{24}$. The PCR amplification is performed according to the following schedule: 94°C for 1 min, 42°C for 2 min, and 72°C for 6 min with 10 s extension per cycle for 25 cycles. Five additional units of Taq polymerase are added before performing

5   25 more cycles with the same programme but without the extension time. Each tube at this point contains amplified cDNA products derived from a single cell. The protein contents of the solution are extracted by phenol/chloroform treatment, and the amplified cDNAs are precipitated by ethanol and eventually suspended in 100μl of TE pH8.0. 5μl of the cDNA solution is run on a 1.5% agarose gel to check the success of the

10   amplification. Most of the samples show a very intense 'smeared' band ranging mainly between 500bp to 1200bp, indicating the efficient amplification of the single cell cDNA. Only the successfully amplified samples are used for the subsequent 'cell typing' analysis.

Example 2. Identification of PGCs by Examination of the Expression of Marker
15   **Genes**

The embryonic fragment which is excised theoretically contains three major components: the allantoic mesoderm, PGCs, and extraembryonic mesoderm surrounding PGCs. In order to identify the single cell cDNA of PGC origin amongst these samples, positive and negative selection of the constructed cDNAs is performed, by examining the

20   expression of four marker genes (BMP4, TNAP, Hoxb1, and Oct4), which are known to be either expressed or repressed in various cell types in this region.

At the No/Early Bud stage, BMP4 is reported to be expressed in the emerging allantois and mesodermal components of the developing amnion, chorion, and visceral yolk sac (Lawson, K.A., Dunn, N.R., Roelen, B.A.J., Zeinstra, L.M., Davis, A.M.,

25   Wright, C.V.E., Korving, J.P.W.F.M., and Hogan, B.L.M. (1999)). The boundary of BMP4 expression is very sharp, and the expression is completely excluded in the mesodermal region beneath the epithelial lining continuous from the amnionic mesoderm where the putative PGCs are determined. Therefore, BMP4 is used as a negative marker for the selection. Primer pairs are designed for amplifying the C terminal portion of

30   BMP4 (5': GCC ATA CCT TGA CCC GCA GAA G, 3': AAA TGG CAC TCA GTT

CAG TGG G). The PCR amplification is performed using 0.5μl of the cDNA solution as a template according to the following schedule: 95°C for 1 min, 55°C for 1 min, and 72°C for 1 min for 20 cycles. Among 83 samples tested, 57 samples show the expected size of bands, indicating expression of BMP4 these single cells. These samples are considered to be of allantoic mesodermal origin, and therefore excluded from amongst the candidates representing cells of PGC origin.

The expression of tissue non-specific alkaline phosphatase (TNAP), which has long been used as an early marker for PGCs (Ginsburg, M., Snow, M.H.L., and McLaren, A. (1990)), is then examined. Primer pairs are designed (5': CCC AAA GCA CCT TAT TTT TCT ACC, 3': TTG GCG AGT CTC TGC AAT TGG) and the same PCR reaction as above is performed. Amongst the 26 samples, 22 samples are judged to be positive for TNAP. From the alkaline phosphatase staining of the sectioned embryos, it is known that the somatic cells surrounding PGCs also express some amount of TNAP, although the level of expression is slightly lower than that in PGCs. Therefore, amongst these 22 positive samples there should be still be cells destined to become somatic cells as well as PGCs.

One of the genes known to be expressed in the totipotent PGCs but not in somatic cells is Oct4 (Yoem, Y.II., Fuhrmann, G., Ovitt, C.E., Brehm, A., Ohbo, K., Gross, M., Hubner, K., and Scholer, H.R. (1996)). To examine the possibility that Oct4 can be used as a marker to distinguish PGCs from somatic cells at this stage, Oct4 expression is checked in the 22 samples by PCR (5': CAC TCT ACT CAG TCC CTT TTC, 3': TGT GTC CCA GTC TTT ATT TAA G). All the 22 samples express Oct4 at comparable levels, indicating that the somatic cells at this stage are still actively transcribing Oct4 RNA.

The amount of expression of TNAP is quantitated in 22 samples by Southern blot analysis (reverse northern blot analysis). Given the fairly representative amplification of the single cell method, confirmed by amplifying single ES cell cDNA, Southern blot analysis allows semi-quantitative measurement of the amount of the genes expressed in the original single cells, although it does not serve as a perfect indicator of cell identity. However, as a result of this TNAP analysis, 10 samples out of 22 show relatively stronger

bands at an equivalent level, while the remaining 12 samples exhibit weaker signals. These results indicate that these 22 samples can be divided at least into two groups, one with stronger TNAP expression (therefore from putative PGCs) and the other with weaker TNAP.

5   The possibility that somatic cells surrounding PGCs start to express Hoxb1, while PGCs do not (personal communication from Dr. Kirstie Lawson) is also examined. Primer pairs are designed (5': AAC TCA TCA GAG GTC GAA GGA, 3': CGG TGC TAT TGT AAG GTC TGC) and the same PCR reaction as above is performed. Among the 22 samples tested, 12 are positive, and more importantly, these 12 samples perfectly

10   match the ones which show weaker TNAP signals, by Southern blot analysis.

       Taking all these results into consideration, it is concluded that 10 samples out of 83, which are Oct4 (+), TNAP (++), BMP4 (-), and Hoxb1(-),are of PGC origin. This ratio (10/83) is reasonable, considering the number of the founding population of PGCs as 40 and the number of cells in the fragment as 250-300.

15   **Example 3. Differential Screening of Single Cell cDNA Libraries**

       As the efficiency of the amplification of cDNA differs in each tube, it is very important to select the samples with the most efficiently amplified cDNA for the construction of libraries. The amplification of six different genes (ribosomal protein S12, intermediate filament protein vimentin, β tubulin-5, α actin, Oct4, E-cadherin) is

20   examined in the 10 PGC candidate samples, by Southern blot analysis. Judging from the overall profile of the amplification of all these six genes, three cDNA preparations are selected for the construction of libraries.

       To obtain the maximum amount of double strand cDNA, an extension step is performed with 5µl of cell cDNA in 100µl of the PCR buffer described as above

25   (including 1µl of Amplitaq) according to the following schedule: 94°C for 5min, 42°C for 5min, 72°C for 30min. The solution is extracted by phenol/chloroform treatment, and the amplified cDNAs are precipitated by ethanol, suspended in TE, and completely digested with EcoRI. The PCR primer and excess amount of dNTPs are removed by QIAGEN

PCR Purification Kit, and all the purified cDNAs are run on a 2% low melting agarose gel. cDNAs above 500bp are cut and purified by QIAGEN Gel Purification Kit. The purified cDNAs are precipitated by ethanol and suspended in TE and ligated into λ ZAP II vector arms. The ligated vector is packaged, titered and the ratio of the successfully

5   ligated clones is monitored by amplifying the inserts with T3 and T7 primers from 20 plaques. More than 95% of the phage are found to contain inserts.

The representation of the three genes, ribosomal protein S12, β tubulin-5, Oct4, is quantitated by screening 5000 plaques, and the library of the best quality among the three (S12 0.62%, β tubulin 0.4%, Oct4 0.5%) is used for the differential screening. As a

10   comparison partner with the PGC probe, one of the most efficiently amplified surrounding somatic cell cDNA (Oct4 (+), TNAP(+/-), BMP(-), and Hoxb1(+)) is selected by the similar Southern blot analysis.

The library is plated at a density of 1000 plaques per 15cm dish to obtain large plaques (2mm diameter) and two duplicate lifts are taken using Hybond N+ filters from

15   Amersham. The filters are prehybridized at 65°C in 0.5M sodium phosphate buffer (pH7.3) containing 1% bovine serum albumin and 4% SDS. We prepared the cell cDNA probes by reamplifying for 10 cycles 1μl of the original cell cDNA into 50μl of total reaction with the AL1 primer, in the absence of cold dCTP and with 100μCi of newly received ^{32}PdCTP, followed by the purification using Amersham Nick^{TM} Spin Column.

20   The filters are hybridised for at least 16 hrs with 1.0×10^7cpm/ml (The first filter is hybridised with somatic cell probe and the second filter is hybridised with the PGC probe). After the hybridisation, the filters are washed three times at 65°C in 0.5X SSC, 0.5% SDS and exposed to X ray films until the appropriate signal is obtained (usually one to two days).

25   The positive plaques in the two duplicate filters are compared very carefully. Among 5000 plaques screened, 280 are picked as candidates representing the differentially expressed genes. The inserts of all the 280 plaques are amplified with T3 and T7 primers, run on 1.5% gels, and double sandwich Southern blotted. Each membrane is hybridised with the PGC and somatic cell probe, respectively, using the

30   same conditions as the screening. 38 clones amongst the 280 are selected as differentially

expressed genes. These clones are next hybridised with the second PGC and somatic cell cDNA probes, which resulted in 20 clones out of 38 to be common in both PGC cDNAs but they are either not included or less abundant in both somatic cell cDNAs. The sequences of all the 20 clones are determined.

5   *Genes highly specific to the earliest population of PGCs*

The 20 clones represent 11 different genes (two clones appear two times, one clone appears three times, and one clone appears 6 times). To further stringently check the specificity of expression, primer pairs are designed for these 11 clones and their expression checked in 10 different single PGC-candidate cDNAs and 10 different single

10   somatic cell cDNAs by PCR. Two of them show highly specific expression to PGC cDNAs.

The first gene, GCR1 (Germ cell restricted-1, Fragilis), encodes a 137 amino acid protein with a predicted molecular weight of 15.0kD. Nucleotide and amino acid sequences of mouse Fragilis are shown in **Figure 1**.

15   The best fit model of the EMBL program PredictProtein predicts two transmembrane domains, both N and C terminus ends being located outside. The BLASP search revealed that Fragilis is a novel member of the interferon-inducible protein family. One prototype member, human 9-27 (identical to Leu-13 antigen), is inducible by interferon in leukocytes and endothelial cells, and is located at the cell surface as a

20   component of a multimeric complex involved in the transduction of antiproliferative and homotypic adhesion signals (Deblandre, 1995). The BLASTN search revealed that the Fragilis sequence was found in ESTs derived from many different tissues both from embryos and adults, indicating that Fragilis may play a common role in different developmental and cell biological contexts. Database searches reveal a sequence match

25   with the rat interferon-inducible protein (sp:INIB RAT, pir:JC1241) with unknown function. The GCR1 sequence appears six times in our screen, indicating high level expression in PGCs.

The second gene, GCR2, (Stella) encodes a 150 amino acid protein, of 18kD. Nucleotide and amino acid sequences of mouse Fragilis are shown in **Figure 2**.

It has no sequence homology with any known protein, contains several nuclear localisation consensus sequences and is highly basic pI (pI=9.67, the content of basic residues=23.3%), indicating a possible affinity to DNA. Furthermore a potential nuclear export signal was identified, indicating that Stella may shuttle between the nucleus and

5   the cytoplasm. BLASTN analysis revealed that the Stella sequence was found only in the preimplantation embryo and germ line (newborn ovary, female 12.5 mesonephros and gonad etc.) ESTs indicating its predominant expression in totipotent and pluripotent cells. Interestingly, we found that Stella contains in its N terminus a modular domain which has some sequence similarity with the SAP motif. This motif is a putative DNA-binding

10   domain involved in chromosomal orgainisation. Furthermore, the SMART program revealed the presence of a splicing factor motif-like structure in its C-terminus, These findings indicate a possible involvement of Stella in chromosomal orgainistion and RNA processing.

Example 4. Identification of PGCs by Screening for GCR1 and GCR2 Expression

15   Although PGCs are identified in Example 2 by analysis of BMP4, TNAP, Hoxb1, and Oct4, no single one of these genes can be taken as a marker for the PGC state. However, both GCR1 and GCR2 may be used as such.

The expression of GCR1 is examined. Primer pairs are designed (5': CTACTCCGTGAAGTCTAGG, 3': AATGAGTGTTACACCTGCGTG) and the same

20   PCR reaction as above is performed. GCR1 expression was detected in germ cell competent cells. The definitive PGCs were recruited from amongst this group of cells showing expression of GCR1.

The boundary of GCR2 expression in particular is well-defined, and the expression is substantially limited to PGCs. Therefore, GCR2 is used as a positive marker

25   for the selection of PGCs. Primer pairs are designed for amplifying the C terminal portion of GCR2 (5': GCCATTCAGATGTCTCTGCAC, 3': CTCACAGCTTGAGGCTTCTAA). The PCR amplification is performed using 0.5μl of the cDNA solution obtained from PGCs in Example 1 as a template according to the following schedule: 95°C for 1 min, 55°C for 1 min, and 72°C for 1 min for 20 cycles.

Among 83 samples tested, only those taken from PGCs show expression of GCR2. Hence, GCR2 is a positive marker for the PGC fate.

Antibodies against GCR1 and GCR2 can be similarly used to detect pluripotent cells. Preferably, antibodies against GCR1 are used to detect germ cell competent cells, and antibodies against GCR2 are used to detect PGCs.

Accordingly, both GCR1 and GCR2 are positive markers for the PGC fate which can be used to positively identify PGC.

Identification of PGC by ISH

The *in vivo* expression of the two genes is examined by *in situ* hybridisation. The expression of GCR1 starts very weakly in the entire epiblast at E6.0-E6.5 (PreStreak stage) and becomes strong in the few cell layers of the proximal rim of the epiblast. BMP4 that is expressed in the extraembryonic ectoderm is one signalling molecule that is important for the induction of germ cell competence and expression of GCR1. Other signals, such as interferons are likely to be involved in the induction of GCR1. The expression becomes more intense at the proximo-posterior end of the developing primitive streak at the Early/Mid Streak stage and becomes very strong at this position from Late Streak stage onward. The expression persists until Early Head Fold stage and eventually disappears gradually. No expression is detected in the migrating PGCs at E8.5.

The expression of GCR2 starts at the proximo-posterior end of the developing primitive streak at Mid/Late Streak stage and becomes gradually strong at the same position from the later stage onward. The expression is specific and individual single cells stained in a dotted manner can be seen in the region where PGCs are considered to start differentiating as a cluster of cells. At Late Bud/Early Head Fold stage, some cells considered to be migrating from the initial cluster are stained as well as cells in the cluster. At E8.5 and E9.5, a group of cells considered to be the migrating PGCs are very specifically stained.

From these results, it is concluded that GCR1 is a gene which is upregulated during the process of lineage specification and germ cell competence, and subsequently of PGCs, when GCR2 is turned on after GCR1 to fix the PGC fate.

Accordingly, expression of GCR1 may be detected in a method of detecting lineage specification, and/or pluripotency, such as germ cell competence. Similarly, expression of GCR2 may be detected to detect commitment to cell fate, for example, commitment to fate as a primordial germ cell.

Example 5. Expression of Fragilis and Stella During Germ Line Development

Antibodies against Stella and Fragilis are used to detect expression of these genes in early embryos. It is found that each of these genes is expressed in primordial germ cells. In particular, we find that Fragilis is the first gene to mark PGC competent cells at the time of germ cell allocation. Stella is expressed only in the lineage-restricted founder PGCs and thereafter in the germ cell lineage.

Figure 3 shows expression of Fragilis in embryonic stem (ES) cells.

Fragilis is expressed in pluripotent ES and EG cells. During the derivation of EG cells from PGCs, it is found that Fragilis expression re-appears on EG cells. Late PGCs are negative for Fragilis after specification of these cells is completed.

Figure 5 shows expression of Fragilis as detected by whole-mount *in situ* hybridization in E7.2 mouse embryos.

There is strong Fragilis expression at the base of incipient allantois where the founder PGC population differentiates in the E7.25 embryos. Fragilis expression persisted until E7.5, but it was not detected in migrating PGCs at E8.5. Fragilis is first detected in germ cell competent proximal epiblast cells. Fragilis expression can be induced in the epiblast cells when combined with the tissues extraembryonic ectoderm tissues, which is the source of BMP4. In the BMP4 mutant mice, there is no expression of Fragilis, consistent with the absence of PGCs in these embryos (Lawson et al., 1999).

Figure 4 shows expression of Stella in PGCs.

Stella expression which is strong in PGCs is downregulated in EG cells. There is also low level expression of Stella in ES cells. Stella and Fragilis are detectable in ES and EG cells by Northern blot analysis. Stella is first detected at E7.0 in single cells within the

5   distinctive cluster of lineage-restricted PGCs, and thereafter in migrating PGCs and subsequently when they enter the gonads. **Figure 7** shows Stella expression in PGCs in the process of migration into the gonads in E9.0 embryos. Stella is the only gene so far known to be a definitive marker for the founder population of PGCs.

Figure 6 shows expression of Stella as detected by whole-mount *in situ*
10   hybridization in E7.2 mouse embryos.

Figure 8. Expression of Fragilis and Stella in single cells detected by PCR analysis of single cell cDNAs. Note that there are more single cells showing expression of Fragilis compared to those showing expression of Stella. Only cells with the highest levels of Fragilis expression are found to express Stella and acquire the germ cell fate.

15   Cells that express Stella were found not to show expression of Hoxb1. Cells that express lower levels of Fragilis and no Stella become somatic cells and show expression of Hoxb1. The founder population of PGCs also show high levels of Tnap. Both the founder PGCs and the somatic cells show expression of Oct4, T(Brachyury), and Fgf8.

Example 6. Expression of Fragilis and Stella in Individual Cells

20   Intracellular localisation of Stella and Fragilis is also determined. Fragilis localised to a single cytoplasmic spot at the Golgi apparatus, as well as in the plasma membrane. Stella comprises a putative nuclear localisation signal and nuclear export signal, and is localised in both the cytoplasm and nucleus.

Fragilis is observed in the Golgi apparatus as well as in the plasma membrane of
25   PGCs. The cell surface localization of Fragilis is expected as a member of the interferon inducible gene family [Deblandre, 1995]. Expression of Fragilis in the proximal rim of the epiblast marks the onset of germ cell competence. *Fragilis* has an IFN response

element upstream of its exon 1, so it is very likely to be induced by IFN after initial priming by BMP4 of the proximal epiblast cells. These IFN inducible proteins can from a multimeric complex with other proteins such as TAPA1, which is capable of transduction of antiproliferative signals, which may be why the cell cycle time in founder PGCs

5 increases from 6 to 16hr, while the somatic cells continue to divide rapidly.

Stella, which has the putative nuclear localization signal and a nuclear export signal, was observed in both the cytoplasm and the nucleus. The onset of *Stella* is followed by the loss of *Fragilis* expression by E8.5. Therefore, *Fragilis* expresiion marks the onset of germ cell competence and *Stella* expression marks the end of this

10 specification process. Expression of *Stella* in the founder PGCs marks an escape from the somatic cell fate and consistent with their pluripotent state. These studies indicate that specific set of genes are required to impose a germ line fate on cells that may otherwise become somatic cells. Stella, with its potential to shuttle between the nucleus and cytoplasm, could have a role in transcriptional and translational regulation, since many

15 organisms possess elaborate transcriptional mechanisms to prevent germ cells from becoming somatic cells. Expression of Stella in the oocyte and preimplantation embryos indicates that it has a wider role in totipotency and pluripotency.

Example 7. The Link Between Fragilis and Stella

Only some of the cells that express Fragilis, ended up showing expression of

20 Stella. Only those cells with the higest levels of Fragilis expression become PGCs and began to express Stella. Furthermore, Stella positive PGCs never show expression of Hoxb1. More importantly, only somatic cells with lower levels of Fragilis expression, show Hoxb1 expression. Furthermore, only the somatic cells show expression of two other homeobox-containing genes, Lim1 and Evx-1. Therefore lack of expression of

25 Hoxb1, Evx-1 and Lim1, appears to be important for the specification of germ cell fate.

Fig 8a and 8b show expression of various genes in single cell PGCs and somatic cells by PCR analysis.

Our experiments also show that Oct4 is not a definitive marker of PGC, Previously, Oct4 expression is demonstrated in totipiotent and pluripotent cells [Nichols, 199, Pesce, 1998; Yeom, 1996]. However, we find that Oct4 is expressed to the same extent in all PGCs and somatic cells. We do however find expression of T (Brachyuri)

5   and Fgf 8 in PGCs indicating that PGCs are recruited from amongst embryonic cells that are initially destined to become mesodermal cells.

Example 8 PGC Specification

The founder PGCs and their somatic neighbours share common origin from the proximal epiblast cells. By analysing the founder PGC and the somatic neighbour, a

10   systematic screen for critical genes for the specification of germ cell fate has been established. Fragilis is an interferon (IFN) inducible gene that can promote germ cell competence and homotypic association to demarcate putative germ cells from their somatic neighbours, and such an example may apply to other situation during development. Expression of Stella occurs in cells with high expression of Fragilis.

15   Fragilis is no longer required once germ cell specification is complete, but Stella expression continues in the germ cell lineage. Stella may also be important throughout in the totipotent/pluripotent cells since it is also expressed in oocytes and early preimplantion development embryos.

Example 9 Germ Line and Pluripotent Stem Cells

20   PGCs can be used to derive pluripotent embryonic germ (EG) cells. However, unlike EG cells, PGCs do not participate in development if introduced into blastocysts. They either cannot respond to signalling molecules, or that they are transcriptionally repressed. PGCs once specified do not express Fragilis on their cell surface. However, EG cells clearly show expression of Fragilis on their cell surface as do ES cells. Both EG and

25   ES cells express Stella as judged by Northern analysis, although Stella is expressed at a lower level in ES and EG cells than in PGCs. Fragilis and Stella therefore have a role in pluripotent stem cells. These genes are therefore markers of these pluripotent stem cells, where they may also have a role in conferring pluripotency on these stem cells.

P10490GB

49

REFERENCES

Brady, G. and Iscove, N.N. (1993). Construction of cDNA libraries from single cells. *Methods Enzymol.* 225, 611-623.

Dulac, C. and Axel, R. (1995). A novel family of genes encoding putative pheromone receptors in mammals. *Cell* 83, 195-206.

Ginsburg, M., Snow, M.H.L., and McLaren, A. (1990). Primordial germ cells in the mouse embryo during gastrulation. *Development* 110, 521-528.

Downs, K.M., and Davies, T. (1993). Staging of gastrulating mouse embryos by morphological landmarks in the dissecting microscope. *Development* 118, 1255-1266.

Lawson, K.A., Dunn, N.R., Roelen, B.A.J., Zeinstra, L.M., Davis, A.M., Wright, C.V.E., Korving, J.P.W.F.M., and Hogan, B.L.M. (1999). Bmp4 is required for the generation of primordial germ cells in the mouse embryo. *Genes&Dev.* 13, 424-436.

Yoem, Y.II., Fuhrmann, G., Ovitt, C.E., Brehm, A., Ohbo, K., Gross, M., Hubner, K., and Scholer, H.R. (1996). Germline regulatory element of Oct-4 specific for the totipotent cycle of embryonal cells. *Development* 1996, 881-894.

1.   Weismann, A. Das Keimplasma. Eine theorie der Vereburg. *Jenna. Gustav Fischer* (1892).

2.   Eddy, E. M. Germ plasm and the differentiation of the germ cell line. *Int Rev Cytol* **43**, 229-80 (1975).

3.   Seydoux, G. & Strome, S. Launching the germline in Caenorhabditis elegans: regulation of gene expression in early germ cells. *Development* **126**, 3275-83. (1999).

4.   Wylie, C. Germ cells. *Cell* **96**, 165-74. (1999).

5.   Lawson, K. A. et al. Bmp4 is required for the generation of primordial germ cells in the mouse embryo. *Genes Dev* **13**, 424-36. (1999).

6.   Lawson, K. A. & Hage, W. J. Clonal analysis of the origin of primordial germ cells in the mouse. *Ciba Found Symp* **182**, 68-84 (1994).

5   7.   Tam, P. P. & Zhou, S. X. The allocation of epiblast cells to ectodermal and germ-line lineages is influenced by the position of the cells in the gastrulating mouse embryo. *Dev Biol* **178**, 124-32. (1996).

8.   Yoshimizu, T., Obinata, M. & Matsui, Y. Stage-specific tissue and cell interactions play key roles in mouse germ cell specification. *Development* **128**, 481-90.
10   (2001).

9.   McLaren, A. Signaling for germ cells. *Genes Dev* **13**, 373-6. (1999).

10.   Ying, Y., Liu, X. M., Marble, A., Lawson, K. A. & Zhao, G. Q. Requirement of Bmp8b for the generation of primordial germ cells in the mouse. *Mol Endocrinol* **14**, 1053-63. (2000).

15   11.   Ying, Y., Qi, X. & Zhao, G. Q. Induction of primordial germ cells from murine epiblasts by synergistic action of BMP4 and BMP8B signaling pathways. *Proc Natl Acad Sci U S A* **98**, 7858-7862. (2001).

12.   Ying, Y. & Zhao, G. Q. Cooperation of endoderm-derived BMP2 and extraembryonic ectoderm- derived BMP4 in primordial germ cell generation in the
20   mouse. *Dev Biol* **232**, 484-92. (2001).

13.   Chiquoine, A. D. The identification, origin and migration of the primordial germ cells in the mouse embryo. *Anat Rec* **118**, 135-146 (1954).

14.   Ginsburg, M., Snow, M. H. & McLaren, A. Primordial germ cells in the mouse embryo during gastrulation. *Development* **110**, 521-8. (1990).

15. MacGregor, G. R., Zambrowicz, B. P. & Soriano, P. Tissue non-specific alkaline phosphatase is expressed in both embryonic and extraembryonic lineages during mouse embryogenesis but is not required for migration of primordial germ cells. *Development* **121**, 1487-96. (1995).

16. Nichols, J. et al. Formation of pluripotent stem cells in the mammalian embryo depends on the POU transcription factor Oct4. *Cell* **95**, 379-91. (1998).

17. Pesce, M., Gross, M. K. & Scholer, H. R. In line with our ancestors: Oct-4 and the mammalian germ. *Bioessays* **20**, 722-32. (1998).

18. Yeom, Y. I. et al. Germline regulatory element of Oct-4 specific for the totipotent cycle of embryonal cells. *Development* **122**, 881-94. (1996).

19. Downs, K. M. & Davies, T. Staging of gastrulating mouse embryos by morphological landmarks in the dissecting microscope. *Development* **118**, 1255-66. (1993).

20. Brady, G. & Iscove, N. N. Construction of cDNA libraries from single cells. *Methods Enzymol* **225**, 611-23 (1993).

21. Dulac, C. & Axel, R. A novel family of genes encoding putative pheromone receptors in mammals. *Cell* **83**, 195-206. (1995).

22. Frohman, M. A., Boyle, M. & Martin, G. R. Isolation of the mouse Hox-2.9 gene; analysis of embryonic expression suggests that positional information along the anterior-posterior axis is specified by mesoderm. *Development* **110**, 589-607. (1990).

23. Deblandre, G. A. et al. Expression cloning of an interferon-inducible 17-kDa membrane protein implicated in the control of cell growth. *J Biol Chem* **270**, 23860-6. (1995).

24. Friedman, R. L., Manly, S. P., McMahon, M., Kerr, I. M. & Stark, G. R. Transcriptional and posttranscriptional regulation of interferon- induced gene expression in human cells. *Cell* **38**, 745-55. (1984).

25. Evans, S. S., Collea, R. P., Leasure, J. A. & Lee, D. B. IFN-alpha induces homotypic adhesion and Leu-13 expression in human B lymphoid cells. *J Immunol* **150**, 736-47. (1993).

26. Evans, S. S., Lee, D. B., Han, T., Tomasi, T. B. & Evans, R. L. Monoclonal antibody to the interferon-inducible protein Leu-13 triggers aggregation and inhibits proliferation of leukemic B cells. *Blood* **76**, 2583-93. (1990).

27. Aravind, L. & Koonin, E. V. SAP - a putative DNA-binding motif involved in chromosomal organization. *Trends Biochem Sci* **25**, 112-4. (2000).

28. Gurdon, J. B., Lemaire, P. & Kato, K. Community effects and related phenomena in development. *Cell* **75**, 831-4. (1993).

29. Reid, L. E. et al. A single DNA response element can confer inducibility by both alpha- and gamma-interferons. *Proc Natl Acad Sci U S A* **86**, 840-4. (1989).

30. Kita, M. et al. [Expression of cytokines and interferon-related genes in the mouse embryo]. *C R Seances Soc Biol Fil* **188**, 593-600 (1994).

31. Gomperts, M., Garcia-Castro, M., Wylie, C. & Heasman, J. Interactions between primordial germ cells play a role in their migration in mouse embryos. *Development* **120**, 135-41. (1994).

32. Herrmann, B. G., Labeit, S., Poustka, A., King, T. R. & Lehrach, H. Cloning of the T gene required in mesoderm formation in the mouse. *Nature* **343**, 617-22. (1990).

33.   Herrmann, B. G. Expression pattern of the Brachyury gene in whole-mount TWis/TWis mutant embryos. *Development* **113,** 913-17

34.   Crossley, P. H. & Martin, G. R. The mouse Fgf8 gene encodes a family of polypeptides and is expressed in regions that direct outgrowth and patterning in the developing embryo. *Development* **121**, 439-51. (1995).

35.   Barnes, J. D., Crosby, J. L., Jones, C. M., Wright, C. V. & Hogan, B. L. Embryonic expression of Lim-1, the mouse homolog of Xenopus Xlim-1, suggests a role in lateral mesoderm differentiation and neurogenesis. *Dev Biol* **161**, 168-78. (1994).

36.   Fujii, T. et al. Expression patterns of the murine LIM class homeobox gene lim1 in the developing brain and excretory system. *Dev Dyn* **199**, 73-83. (1994).

37.   Bastian, H. & Gruss, P. A murine even-skipped homologue, Evx 1, is expressed during early embryogenesis and neurogenesis in a biphasic manner. *Embo J* **9**, 1839-52. (1990).

38.   Rogers, M. B., Hosler, B. A. & Gudas, L. J. Specific expression of a retinoic acid-regulated, zinc-finger gene, Rex- 1, in preimplantation embryos, trophoblast and spermatocytes. *Development* **113**, 815-24. (1991).

39.   Sutton, J. et al. Genesis, a winged helix transcriptional repressor with expression restricted to embryonic stem cells. *J Biol Chem* **271**, 23126-33. (1996).

40.   Cox, D. N. et al. A novel class of evolutionarily conserved genes defined by piwi are essential for stem cell self-renewal. *Genes Dev* **12**, 3715-27. (1998).

41.   Fujiwara, Y. et al. Isolation of a DEAD-family protein gene that encodes a murine homolog of Drosophila vasa and its specific expression in germ cell lineage. *Proc Natl Acad Sci U S A* **91**, 12258-62. (1994).

42. Dixon, K. E. Evolutionary aspects of primordial germ cell formation. *Ciba Found Symp* **182**, 92-110 (1994).

43. Mahowald, A. P. Assembly of the Drosophila germ plasm. *Int Rev Cytol* **203**, 187-213 (2001).

5 44. Nieuwkoop, P. D. & Satasurya, L. A. Primordial germ cells in the chordates. *Cambridge University Press, Cambridge, UK* (1979).

45. Johnson, A. D., Bachvarova, R. F., Drum, M. & Masi, T. Expression of axolotl dazl rna, a marker of germ plasm: widespread maternal rna and onset of expression in germ cells approaching the gonad. *Dev Biol* **234**, 402-15. (2001).

10 46. Johnson, A. D., Bachvarova, R. F., Masi, T. & Drum, M. Expression of *Vasa* and *Daz-like* genes demonstrate that Axolotl primordial germ cells (PGCs) are not predetermined. *Germ cells* **Cold Spring harbor laboratory**, 61 (2000).

47. Toyooka, Y. et al. Expression and intracellular localization of mouse Vasa-homologue protein during germ cell development. *Mech Dev* **93**, 139-49. (2000).

15 48. Saitou, M. et al. Occludin-deficient embryonic stem cells can differentiate into polarized epithelial cells bearing tight junctions. *J Cell Biol* **141**, 397-408. (1998).

49. Henrique, D. et al. Expression of a Delta homologue in prospective neurons in the chick. *Nature* **375**, 787-90. (1995).

50. Wilkinson, D. G. & Nieto, M. A. Detection of messenger RNA by in situ
20 hybridization to tissue sections and whole mounts. *Methods Enzymol* **225**, 361-73 (1993).

51. Winnier, G., Blessing, M., Labosky, P. A. & Hogan, B. L. Bone morphogenetic protein-4 is required for mesoderm formation and patterning in the mouse. *Genes Dev* **9**, 2105-16. (1995).

Each of the applications and patents mentioned in this document, and each document cited or referenced in each of the above applications and patents, including during the prosecution of each of the applications and patents ("application cited documents") and any manufacturer's instructions or catalogues for any products cited or

5   mentioned in each of the applications and patents and in any of the application cited documents, are hereby incorporated herein by reference. Furthermore, all documents cited in this text, and all documents cited or referenced in documents cited in this text, and any manufacturer's instructions or catalogues for any products cited or mentioned in this text, are hereby incorporated herein by reference.

10   Various modifications and variations of the described methods and system of the invention will be apparent to those skilled in the art without departing from the scope and spirit of the invention. Although the invention has been described in connection with specific preferred embodiments, it should be understood that the invention as claimed should not be unduly limited to such specific embodiments. Indeed, various modifications

15   of the described modes for carrying out the invention which are obvious to those skilled in molecular biology or related fields are intended to be within the scope of the claims.

SEQUENCE LISTING

SEQ ID NO: 1 (MOUSE GCR1/FRAGILIS NUCLEIC ACID)

Mouse GCR1 (Fragilis) full length nucleotide sequence

GCCGCAGAAAGGGCAGACCCGCAGCGCGCTCCATCCTTTGCCCTCCAGTGCTGCCTTTGCTCCGC
ACCATGAACCACACTTCTCAAGCCTTCATCACCGCTGCCAGTGGAGGACAGCCCCCAAACTACGA
AAGAATCAAGGAAGAATATGAGGTGGCTGAGATGGGGGCACCGCACGGATCGGCTTCTGTCAGAA
CTACTGTGATCAACATGCCCAGAGAGGTGTCGGTGCCTGACCATGTGGTCTGGTCCCTGTTCAAT
ACACTCTTCATGAACTTCTGCTGCCTGGGCTTCATAGCCTATGCCTACTCCGTGAAGTCTAGGGA
TCGGAAGATGGTGGGTGATGTGACTGGAGCCCAGGCCTACGCCTCCACTGCTAAGTGCCTGAACA
TCAGCACCTTGGTCCTCAGCATCCTGATGGTTGTTATCACCATTGTTAGTGTCATCATCATTGTT
CTTAACGCTCAAAACCTTCACACTTAATAGAGGATTCCGACTTCCGGTCCTGAAGTGCTTCACCC
TCCGCAGCTGCGTCCCTCCTTGCCCCTCCCTACACGCAGGTGTAACACTCATTTATCTATCCACA
GTGGATTCAATAAAGTGCACTTGATAACCACC

SEQ ID NO: 2 (MOUSE GCR1/FRAGILIS AMINO ACID)

Mouse GCR1 (Fragilis) amino acid sequence

MNHTSQAFITAASGGQPPNYERIKEEYEVAEMGAPHGSASVRTTVINMPREVSVPDHVVWSLFNT
LFMNFCCLGFIAYAYSVKSRDRKMVGDVTGAQAYASTAKCLNISTLVLSILMVVITIVSVIIIVL
NAQNLHT

SEQ ID NO: 3 (MOUSE GCR2/STELLA NUCLEIC ACID)

Mouse GCR2 (Stella) full length nucleotide sequence

GGATCACAGACTGACTGCTAATTGGGTCTTGGTTTTAGGTCTTTTCAAAGACTAAGCAATCTTGT
TCCGAGCTAGCTTTTGAGGCTTCTGCCCATCGCATCGCCATGGAGGAACCATCAGAGAAAGTCGA
CCCAATGAAGGACCCTGAAACTCCTCAGAAGAAAGATGAAGAGGACGCTTTGGATGATACAGACG
TCCTACAACCAGAAACACTAGTAAAGGTCATGAAAAAGCTAACCCTAAACCCCGGTGTCAAGCGG
TCCGCACGCCGGCGCAGTCTACGGAACCGCATTGCAGCCGTACCTGTGGAGAACAAGAGTGAAAA
AATCCGGAGGGAAGTTCAAAGCGCCTTTCCCAAGAGAAGGGTCCGCACTTTGTTGTCGGTGCTGA
AAGACCCTATAGCAAAGATGAGAAGACTTGTTCGGATTGAGCAGAGACAAAAAAGGCTCGAAGGA
AATGAGTTTGAACGGGACAGTGAGCCATTCAGATGTCTCTGCACTTTCTGCCATTATCAAAGATG
GGATCCCTCTGAGAATGCGAAAATCGGGAAGAATTAGGAGCTTACATTGTACGCTGCCCTGGCTG
TCGACGATGCCGCACAGCAGATGTGAAAGCTATTTTTTGTTTAAGATTAAACTTTTTCTGGTGCT
GGGAAATCTTAACTTGTTAACCTTTAAATTGTAGATAGGATGCACAACGATCCAGATTTATGTGA
AGTTTAGAAGCCTCAAGCTGTGAGGCCCAGGGCTGAGGAATAAAGTAAATAGAATTTGGAGTATG
TACGTTCTAATTTCCAGAAATTTGTAATAAAGCATTTTTGTT

SEQ ID NO: 4 (MOUSE GCR2/STELLA AMINO ACID)

Mouse GCR2 (Stella) amino acid sequence

MEEPSEKVDPMKDPETPQKKDEEDALDDTDVLQPETLVKVMKKLTLNPGVKRSARRRSLRNRIAA
VPVENKSEKIRREVQSAFPKRRVRTLLSVLKDPIAKMRRLVRIEQRQKRLEGNEFERDSEPFRCL
CTFCHYQRWDPSENAKIGKN

SEQ ID NO: 5 (RAT GCR2 HOMOLOGUE NUCLEIC ACID)

5   Rat GCR2 (Stella) homologue genomic sequence; similar intron-exon structure as

mouse-Stella. AC094826 contig No.5 (22671 - 27595: contig of 4925 bp in length)

```
CCCCCCCCCCCCCCCCCCCCCTCCCCCCCCCCCCACCTCCGACGTATGATGGCTCCTAGACGCA
ACACGAAGCGGACTCCCCGCATCATTCACGTAGACCCGCCTTCTGCTTTCCTGTCGGGGTTTTG
GGAAGCCCGGCGGCCCTCTCTTCTCACCTTGCTCCACTAGCACGCGGCTGTTTTCACTGAGCCCA
GCACTGGCTAAGTGGAGCACCAGGAGTTTCAGGCTATCCTTCAGAGGGCAAGGTGTAGTCCATGG
TGGGCTACAGGAGACCCTCTCTCTCCGTGAGTACAGAGAGGCAAACCCAAGCCAGACAGGGGTGA
TGATTAGGAACATACCTTCGTCGGGGAGAAAATACCGGTTCATATAGGAATAAGAGGAACCAGGA
GGTAGTTAAGGCTGTGGTGTCTGGTTGCGGGTTTTTGACTCTCAACAACCACGTTCAGAACGTG
CTGAGTTTTTATGATGGTGTAGAATTTCCTTATCAGCAATTGGTCTCCGCGGTGTTTCTTTTTCT
TTTTTAATTTTTTAAGTATAATTTGGTGTTTGAAGCAACTGTACTTGGACTAGAACTCCCTGTGT
AATCCAGAATGGAATCCCAAATCCTAGGATTAAAGGTTTTAGTGGGCTGCAGTGTTGGGTGGGGG
TTGTTTTGATTACGTTGTAGCCCAGGCTGGGCTCAATCTCAATCCTCCTGCCTCTGCCTTCTAAA
CGCTAGGATTAAAAGTGCTGCGCCATGATCCTGCTGTAGCTTTATTTTTATTTATTTATTTATTT
ATTTTGGCTCTTTTTTTTTGGAGCTGGGGACCGAACCGAGGGCCTTGTGCTTCCTAGGCAAGCGC
TCTACCACTGAGCTAAATCCCCAACCCCAGTGTAGCTTTATTTTTAAGAACAGGAGTCTTGTTTC
TCAAAACAGTTTCTCTGTAGCCCTGGTTGTCCTGGAACTCCGTAAACCAGGCTGGTTTGGGACTC
TGCCTTTAAAACACTGGGACTAAAGGCGGTACCACCTCCGTGGGCTACACCGGAATCTTTTAAGC
TTCATTTGAACCGGGGCTTTTTCTTTTTCTCACCCACTTTCTGGAAGCGATTTTCCTGCTAAATT
TCCATTCCTGGTAAATGACTCTGAGGGGAAATAGGAACCCAGAATAGATTGAGCCGGGGGCTACC
TGGGACCCCGCACTCCCCACCCCCCAGCCGCTGTTGAAGCTCTTTGCCTGAGGGGCCTCCGGGTT
TGATACCTCCTAGCACTCCGGGCTGAGGGCGTGGCTCGGGAGGAGCCATTCCTTTGGAGAGGAAA
ACAACTGCTGGCCTTGAATCTGCCCTAATACCTGACAGTTACATGGGACCTCCTTATTTCCACAG
GATTCTTTAGTCTTTGTTTGGGAGATTTTCAAATCTTGAGACTGCTCAACCCTTCCTGGCCTAAC
ACTCACAAGGCCAGGCTAGACCCAAATTCTGTCAACCCCTTCTGTGTCCAAAACGGTGGGTGGCT
AGCTGGCTCACCCTTGGTGTCACTTTGCTTTAACATTCGGAAAAGTTGTGGTAAGTTTCCTGTAT
AAAATAGGACCATCTACTGGGTGTGGTCCCATGTAAAGCAAGGTTGGTTTCCCAAAATACCCTGT
TTACATAGATGTCCGGAAGCATTGGAGCAGGTCAATTAGATTTAGGTGGAAACAGCCTGTTTTTG
GAAAGCTTTCCAGGGCGGAAAATGAACCCAGAGGCACTATTGGGCAAGCCCTCCGGCTAAGCAAC
ACAATTGGCTGCAGGGGTCTCTGGAAGAGGTGTGAGACAAGAGAGAATATGCAGGTTTCAGGACC
TCTGAACTAGAGTTAGGCTGCTGTAACATTGTAACATTGCTGTAAGCAGAACAGCCCATGGTAAG
AAGCTCAGTGGATCTCTACAAACACTAGGATATCTGCTCAGGGTTTATGACCAGGCCCTGTGCAT
ATGGTTTGCTTCTTGTTGGCCCCTCTCTTGAAGAGGGGTGATTATCTGTTACCCACTTCCTTGTT
TCTCTGGGGTATTACCTTGCAAAATGCAAATGATATACTTCACTAATGTCTCCATCTTCTGTTT
CAGAAATCCTACAACCAGAAACACTAGTAAAGGTCATGAAAAGCTAACCCTGAACCCCAGTGCC
AAGCCGACAAAATATCATCGTCGTCAAAGGGTTCGTCTCCAGGTTAAGAGCCAGCCTGTGGAGAA
CAGAAGTGAAAGAATCATGAGGGAAGTTCAAAGCGCCTTTCCCAGGAGAAGGGTCCGCACTCTGT
TGTCCGTGCTGAAAGACCCCATAGCAAGGATGAGAAGATTTGTTCGGGTGAGTTGCGTTTGTGGG
CGGGGCATAGATCTAAGAGCAACTCTAGCCTCAGGAATGGCACCTAGGTTAAACAGGGAATGTAG
ACAAGGATAGTGACTACCTGTGATTCCCAGCTCAAGAAACAAGCTCCAAGGCTATCCTCTACTG
CGCAGTCTGAAGCTGGCCAGAGCTATATGCAAATTGATAAGTCAGTATAACATTTATTTTTGGAT
TTTCAGACTCCCTCCCCATAGTCCAAACTGGCCCTCCAGTTCAGTCCACGGTCCTGCTTCTTCCC
CGGTGCTAGGCTTTTGAGTGATAAGGCTGACTTAGACTGGATCTCAGAGCTGAAGTGGACCTGTT
AGTCTTTGTAGACCAGGCTGGGGTGGTTTCTGCTTTCTCAGCGCCTAGCTCACATAGTAGGCATT
```

```
   TTAACTTTGTCTTAATAGTAATTTGAGTAATTTTGTTTTTCTCTTGAAGATTGAGCAGAGACAAA
   GACAGCTTGAAGGAAATGAGGTAAATGCATATGGATGGGTAGGGTGTCTATGGATGGGTAGGGTG
   TCTTGTTTTTACTGTTTCCTTAGACAAGGAGTGTGTATGTGGAGAGTTACCTTCTCAACACAGGG
   AATCTGGTTATTAAAGCAGTACTTTAAAAATAAATAAAATAAATAAAATAAAAATAAAGCAGTAG
5  AAGGGGATTTACATTTCTTTTGAGTTGCAATATCCTGATTAACATTTTTCTTTCAGAGACGAGAT
   GAGCCATTCAGATGTCTCTGCACTTTCTGCCATTATCAGAGATGGGATCCTTCTGAGAATGCTAA
   AATCGGGCAGAACCAGAAGAATTAGGGCAGTTTGAATTGTACACCGTCCTTGCCGTTAACGGTGC
   CATGCAGCAGATGTGAAAGCTGTTTTTTTGTTTAAGATTAAACTTTTCTTGGTGCTGGGGAAATC
   TCTTCTAATTGCTAACCTTTAAATTATATAGGATGTGTGACATTTGGATTCATGGGAATGACAGA
10 TTTACCCAAGAATTGAGCATGAGTCAAAGCCTGGTAGTTTGATTTAGAAGGTAATTGGAATAAAT
   CTTTTTATTTTAGATTTTCTAGTTTGCAGAGAAATTTGTAATAAAGGCAAATTTGTTATCTTTAA
   TAAATACAGAACAGATTAGAATGAGCCATTGGAGATGGGGGACTCGTTTTTACAGGTGCATGTG
   TGGGTGTGTGATGTTCAGAGTTCAATGTGTGCTACCCTGTATTTCTGCTTGAGGCAAGGTCTCCA
   TGAGGCCTAGCTGGTCTAACTCCTGGTCCTGCCTTTTGTTTTCCCCTGAGTTTTGACACCATAGG
15 CTTGTCGGCAAGATCTGGAAGAGGCTTGATGTTTGTGTTTGTGCTGTGTAATAAACAATTGGTTG
   ACATATTCCTAAAGTGTGGCACTGTATTGACCTGTCTGTCTCATGAGGAAGTTAATGACCGGAGC
   ATAATTGTATGCTTTATTTCCTGAGAGAAGTGTCAGGAAAGGAGGAGTTAGGAAGAAAGCCCCAG
   GCTGGGGTTAAGAGCACTGGCTGCTTTTCCAGAGGTCCTGAGTTCAATTCCCAGCAATCACCTGG
   TGGCTCCCGAACATCTGTAACAGGATCCAATGCCCTCTTTTGGTGTGTCTAAGAACTCCCTAGGC
20 ATGCAGAGGATTTTTGTTTTTGTTTTTTTTTTTTTTTTTTTTTTTTTTCGTTTTTTTCAGAGCTGG
   GGAACCGAACCCAGGGCCTTGCGCTTGCTAAGCAAGCGCTCTACCACTGAGCTAAATCCCCAACC
   CCTACAATGGCCTTTTTCTACCTGCTTTTGAATTATCAATAAAGACTGGGGCAAAAGAAAGGCT
   GGAGTGAATGAGAGAGAACATGTGAAGAGTAAATGAGAGAGAGCATGAGGGAATGAATGAGAGAG
   TGAATGTGAGAACGAATGTGAGAGCGAGTGAGAGAACATGAGAAGAACACGTTAAGAGTGAGTGA
25 AGAGAGAATGTGAGGTGTGTATGAAGATTGTGTGTGGGGTTGGGGATTTAGCTCAGTGGTAGAGT
   GCTTGCCTAGGAAGCACAAGGCCCTGGGTTCGGTCCCCAGCTCCAAAAAAAAGACCCAAAAAAAA
   AAAAAAAAAAAAGATTGTGTGTGTGTGTGAAAGGAGAGTGCATGTGGTGTGTGTGAGATATGTG
   CAAGGTGTGTATCAAGAGTGTGTGTGAGAGTGAAAGGGTAATGAACAGAGGTGTGCATGAGCGTG
   GGAGTTTGAGAAAAGAAAACAGCAATAAAAAAAAAAGCAGAGTGCACGAGAGAATGCAGAGTGTG
30 TGCAACCTCAAGCTGAGACAGAGACAGAGAGAAAGAGAGAGAGAGAGACTTTAAGCCTTGA
   AATTACCTGTCAGTTTGTACCCAAATAGTAGTCTGTGTATATTTATTTTGAGCCTTCCAGATCCC
   TGCTTCCAGTGGAGAACTCTGATTCTATGTTGAGGCTGGACCCTGGCAATAGTGGGCTTCTTGAA
   AAATAGTCAAAGGAAACAGTGCTACACCATGGACTTAAGCCTTTAGACTCAGTTCTGGCTTCAAG
   AGCAGCTGTCAGAAAATAAGTGATGAACTACTTGCAGTCGAACTCGAATC
35
```

SEQ ID NO: 6 (Rat GCR2 Homologue Nucleic Acid)

Rat GCR2 (Stella) homologue genomic sequence; different intron-exon structure from mouse-Stella (fused exons). AC097234 (131006 132449: contig of 1444 bp in length)

```
40 CCAGGATTCAGACGAGCTAGGCCTCATGCATGGAGACCTTGCCTCAAGCAGAAATAAACAGGGTA
   GCACACATTGAACTCTGAACATCACGAGTGTGCACACACCCACACATGCATCTGTAAAAAACGAG
   TCCCCATCTCCAATGGCTCGTTCTAATCTGTTCTGTGTATTTATTAAAGATAACAAATTTGCCTC
   TATTACAAATTTCTCTGCAAACTAGAAAATCTAAAATAAAGATCTATTCCAATTACCTTCTAAA
   TCAAACTACCGGGCTTTGACTCATGCTCAATTCTTGGGTAAATCTGTCATTCCATGAATCCAAA
45 TGTCACACATCCTATATAATTTAAAGGTTAGCAAGTAGAGATTTCCCCAGCACCAAGAAAGTTT
   AATCTTAAACAAAAAACAGCTTTCACATCTGCTGCATGGCACCGTTAACGGCAAGGACAGTGTA
   TGATTCAAACTGCCCTAATTCTTCTGGTTCTGCCCAATTTTAGCATTCTCAGAAGGATCCCATCT
   CTGATAATGGCAGAAAGTACAGAGACATCTGAATGGCTCAACTCTTCTCTCATTTCCTTCAAGCT
   GTCTTTGTCTCTGCTCAATCCGAACAAATCTTCTCATCCTTGCTATGGGGTCTTTCAGCACCGAC
```

```
AACAGTGTGCGGACCCTTCTCTTGGGAAAGGCGCTTTGAACTCCCCTCATGATTCTTTCACTTCT
GTTCTCCACAGGCTGGCTCTTAATCTGGAGACGAACCCTTTGACGAAGATGATATTTTGGCCGAT
TGAGATAGAATATCAAAACAACATTTAACATTTAAATAACTTAACGATATACACACCTTTTTTTT
TTCCACCTCCCCACACAGACAAAAACAACCCTATTTTTTCTTTACAACCCCGCCTAAGCAAGCG
```
5
```
AAGCATTAGTAACTGACCAATCATAGAAAGGAAACACCACCAGACCACATCAAATAAAATAAAAT
CACCGCCCAACCCCACCCCTATAAAAAACCCGCCGACCACACCACATATACTCCCCCCCCCCGC
ACCATCACTACATCACCCTCTCCACCCATTCCCACCTCCCCCCCCCAACATTAACCCCACCCCATC
ACGGAAACCCCCAACACCAACAAATAAATTAGACACATCGCATTACATAAATTGACACAAGACCC
ACCCCAAAAGAGCAGCAAAGATTAGAGCCACATCCTCGGCCCAACACAATACACTCAACCTGCAT
```
10
```
AGTATCTATCTCCACCCCAACCTAGAAACAAAAATCTAATCAGCACCAGGCACCCAAGTATCACG
CACACTCAAAAACATACCCACCAATTAAACACGCCCCACCCACCCAACAACCCACCCGCCTGACA
ACACACTTCGGAACTACCCTCAACATCACCAAAGCAATCGCAAGTTACGATGACTCCAACCACC
TCACTCTCTCATTG
```

SEQ ID NO: 7 (RAT GCR2 HOMOLOGUE NUCLEIC ACID)

15   Rat GCR2 (Stella) homologue genomic sequence; different intron-exon structure

from mouse-Stella (fused exons). AC093991 (1 - 7657: contig of 7657 bp in length)

```
ACTGCAAGTAGTTCATCATTTACAGATCAAAAGAAAGAAGAATAAAAAAACAAGGTGTCATGATC
CCTCCAAAAGAGTGGAACACTTCAACTGCCAGATCCAAGATACTGAAATGGGTAGCATGCTGGAG
AAAGAATTCAAAAGTTAGGTAGAGAATCTGGTTGAGCAGAGCACTTGCTTTTCTTCCAGAGGATC
```
20
```
TGAGTTCAAGTCCCAGGACCTATATCACAGTTTTCTGTAACTCTAGCTCCAGAGGGTCTGACACT
TCTGTTCACTGTGGGCACCTGCATTCACAGACAAACATAAAGTAGTTCATCACCCTTTTCACAGA
AAACCCACAGCATGTGAGGAAATCCGGGTCTCTGCGCAATGCCCCCACAGCAGAAGGGGGGAGCT
GGAGAGATGGTTCATCTGTTAGCCCATTTATTGCTCTTGAAGAGAACCCAGGGTCATCCATAGCA
CCCATAGCAGCTCACAACCATCTCCAGTTCCAGGAGATCCAATGCCCTGTTGTGACCTCAGGTAC
```
25
```
CAGGCATACACAATGAACCTGCACACATACAAAGTCCATAGAGCCATAGTTACCATTGTGAGCT
CTGAGAACCAAATCCGTGTTCTCTGCAAGAGCGACATGCACGCTGAGAACCAGGCACCTTTCCCA
CTGCCTCTTGAGACAAGATCTCACTATGTAGTTCACACTGGCTTCCGACTTGCCACCATCCTCCT
GCCTCTGCCTATAAAGAATGCTAGGATTATATAGGTACAAAATCACACCTGGCTGTTAAGGTTTT
TCTGGCTGTTTTTTTTTTCACCCCCATGAATGATTTTGAAAATAGTTGAGCTGTTTACATTAATA
```
30
```
AAACAAAATCAGATGGAGACTATATGTCATTATTCATGAATCAAATGACTAGTAACAATACTGAG
TTATTTTTATAGCTTTTCTATTTTTGTTTTAAATTTTATTTTTTCCTTTTTTTTTTTTTTCTTTT
TAGTTTTGCTTTGTTTTGTTTTGAGCAGGCTCTCACTGTGTAGTCCTGGGTGATCTGGAACTTAC
TAGGTAAACAAGGATAGCCTTAAACTCAAGAAATTGCTTGCCTCTGTCTCCAGAGTGCTGCAGT
TAAAGTTGTACACCGCCATGTTTAGGTGTTTTTATTAGTGTGTGTATGTCTGTGTGTCTGTGT
```
35
```
GTGTGTGTGTGTTCCCCGGAGGCCATGTAGGCGCATGCTTGAACCAGAACCAGAGGAAGTGTGTT
TACAGTTACCCTGGGAGGCCAGAAGAGGGCAGGAGATGCCCTGGAACTGGAATTTCTGGTAGTGG
TTAACTGCCTAAAGTGCTGGGACCTAACACTCTTAACTTCTGAGCCATGGCTCTAGTCCTGGGGT
CCCCCCTCCTTCTTTTTATGACTATGCAGACTATACAAATTTATTTTATATATTAAGGTCTACGG
GAGCAGTTTGCCCTGGCAGAGAGTATATATCTCATGGTGACATACATATCTCATGGTGACACA
```
40
```
CATATCTCATGGTGACACACATATCTCATGGTGACATACATATCTCATGGTGACATACATATCAT
CTCATGGTGACACAATTGAGCATTGAGAGCAGCTACAGACCGATTAGATCAGACTTATTAAATTC
TTGCCAAGTATGTGGTGACGCAGGCCTGCAATGCCAGTAACTTTGGAGACTGAGCCAAGCAGATC
ACCTGAGCCTAGAGACTCAAGGCCACCCTGGACAACATAGAGATATCCTGTTTCAAAATGAAACA
AGCTAAGTTCTTTGTACATAGCAGCCTCTCTATTGACTGTGGCAGGGCAGCTGACAGTGTTCTCA
```
45
```
CCTAGTCACAGATGTTCTTTCTAGAGGGAACAGACCCGATGAATACAAACATTTTAGCTCAAGT
AAAAGTCTATACTATGAAGGAACTACTTCTTCAAACATCATAACATTTAAAATGAGAGATTTTAC
AAACCTTTTTTTAAAGATTTATTTGTTTATGATAAGTACACTGTCACTGTCTTCAGACACACCAG
AATTGGGCATCAGATCTCATTACAGATGGTTGTGAGCCACCATGTGGTTGTTGGGAATTGAACTC
AGGACCTCTGGAAGGACAGTCAGCACTCTTTTTTTTTTTTTTTTTTTTCTTTCATTTTTTCGGAG
```
50
```
CTGGGGACCGAACCCAGGGCCTTGTGCTTGCTAGGCAAGCGCTCTACCACTGAGCTAAATCCCCA
```

```
     ACCCCCAGCCAGTGCTCTTAACTGCTGAGCCATCTTCCCAGCCCCAACATCAATTTTTGGTCTAG
     ATGTTTTACCCTGGTGCTGCCATGCCATCTCGATGGCCCTTGTGGCAGGGGTGCCGGTAAGGCAG
     CCCCTAGGGCATGAGTTAGGGAGAGCAAAACCTGACCCAGAACCTGACTGCCATGAAGTGATGGA
     GATGCCGTTTGAGTACATGGGGTTTTTTGGTGGTTGTTGTTTTGTTTTGTTTTTGTTTTTGTTG
5    ACTTGACACATGCTACAGTCATCTGAGAGTGAAACTTAATTGAGAAAATGCCTCTGTATTTTCTC
     CGGCCCCCTAAGTTGCTTTTGATGAGTGTATTTTTATCACAGCAATAGAAACTCTAACTAAGATA
     GATTGGTATTAGAAGTAGAATATTGCTGTAACAGACCCTAACCATGTTCTCTTGGGGAGGATTGT
     GGGAAGACTTTGGAACTTGGAACTTGGAACAGGAGAAGCCATTGGGTACTTAGAGCTTAATGGGC
     TGTTCTGTGGAGCTTGGAAAGGTGCTGGAGAAATGCGGATGATACTTGTAAAGTTTGAGAGCACC
10   TCAAAGATGTTCAGGACAGTGTGTGCAATACATTTGAGTTAAGAATCTATGGTGTCTGGTCAGCT
     GGAGCTGAAGATTCAGCTGTGATTAATAAGACCACTAAAGTAAAACTTTTGCTTTACTGGTACAA
     TCAGTGCTGGTTAGCTAAGGGTTGACAGATGAGCAGTGACTAATAAGAGACTGGCATCAGAAACT
     GATCCAGAGAGAGCCAAGGCTGCATCTCAAACTGGCAGCCAAATTTGATCACATGTAAGAATCTC
     CCTCATGGGGGTTGGGGATTTAGCTCAGTGGTAGAGCGCTTGCCTAGGAAGCACAAGGTCCTGGG
15   TTCGGTCCCCAGCTCCGAAAAAAAAAGAACAAAAAAAAAAAAAAAAAGAATCTCCCTCATGTTA
     CAGGCTTTGGTGGCATGAGAGCTTTAGGGTTGAAGGATCATGGAGAGCAGCCGAGGCTCCGCACC
     ATGTGGCGGGGCAGAGGTACAGCCCAGTTACCACAGAGACACCAGCATATTTGGAGGTGCCAGGA
     TCATGGATAATTGCCTAAGACAGGAGGCTGGCCTGACTTTGTAGGACAAGCTCCATGATCTGTTT
     GGCAGGACTGGAGAAACAGAGCTGTAAGGGAAAATGAGGACACAGCTGTTCCAAGATATGATTGG
20   AGAGAAGGGTTTCATTGCAGATCTGAGGAAGAGGACAGCCAGAGAGGCATCTGGAAGGGTCCAGA
     TTGAACTGGGTCATGAGAGGAGAGAGGGCTAAGAGGACCAAAAGAGCCTGTGACCAAATTATCAG
     GGTTATAGAGAAACAGATGCTTGGGAAAGAGAAGGGGGAGCCCCTGAGCTGGAGAGATTTAAAG
     TAGGGGGCAGGATGAGAAGTGGCTGGGGCAGGATGAGAAGTGCTGAGGAGCCAAAGGCACTCAGT
     GAACCTAGAGGCCAAGGATACATTTTGACATGCTAATAGGCATTTTAGTCATTTGTCCTGCATTT
25   CTTTAGGACAGGCCAAGCTGCCTGGGTCATTGTGAGTCCCAGATAATTCTCTTGAAATAAAATGT
     TTTTTAAAGAGAGGAGGGGAAGGTTGGGGAGGGTGGTCTGAAGTTAAGAGACTTTGGAGTATTAA
     GACATTGGATATTTTAGAGAAAATTTTGAACTTTTAAGAAGACTGACCTTTTAAAGTGTTTGAAT
     TTTTAAAGACCAGGATACATCAGGGTGTAGGGACACATGACCCTGTCTCGCCCCCCCCCCCAAA
     ATTATAATTTTTTTAAAAAGACTGTGGGAGCTGGGTGGTGGTATAGGCCTTTAATCCTAGCACCC
30   AGGAGGCAGAAGCAGGCAGATCTCTGAGTTTGAGACCAGCCTGATCTATAGCATGATTTCCAGGA
     CAATCAAGGCTACACAGTGAAGCCTATCTTAGAAAAAAAAGATTGTAGTTTTAGTTTGCGATGT
     ATTTTATATTGAGGTGCTGACATTAATATGAAATCTTTGTGAGTGGGCAAGAAAATAAAGACTAA
     AGCTGAATACTGATGCCACTTGTGTGTCAGATTGACAAGGGGTTTTGGAATTTTTTTATTTTTTT
     ATTTTTTTTAGGAATATATCAACCAATTGTTTATTACACAGCATGAACAAACACAAAAATCAAG
35   CCTTTTCCAGATCTTGCTGACAAGCCTATGGTGTCAAAACTCGGAAACGAGAGGCAGGACCAGGA
     GTTAAAAGACCAGCGAGGCCTCATGGAGACCTTGTCTCAAGCAGAAATAAACAGGGTTGGTAGCA
     CACACGAACTCTGAACATCACGAGTGTGCACATACCCACACATGCACCTGTAAAAACAAATCCCC
     CATCTCCAATGTCTCGTTCTAATCTGTTCTTGTATTTATTAAAGATAACAAATTGCCTTTATTA
     CAAATTTCTCTGCAAACTAGAAAATCTGAAGATCTATTCCAATTACCTTCTAAATCAAACTACC
40   AGGCTTTGACTCATGCTCAATTCTTGGGTAAATTTGTCATTCGCATGAATCCAAATGTCACACAT
     CCTATATAATTTAAAGGTTAACAAGTAGAAGAGATGTCCCTAGCACCAAGAAAGTTTAATCTTA
     ACAGAAAACAGCTTTCACATCTGCTGTGTGGCACCTTTAACGGCAAGGACGGCGTACAATTCGAA
     CTGCCCTAATTCTTCTGGTTCTGCCCGATTTTAGCATTCTCAGACGGATCCCATCTCTGATAATG
     GCAGAAAGTGCAGAGACATCTAAATGGCTCATCTCTGTTCTCATTCCTTCAAGCTGTCTTTGTC
45   TCTGCTCAATCCGAACAAATCTTCTCATCCTTGCTACAGGTTCTTTCAGCACCGACGACAACAAT
     GTGTGGACCCTTCTCTTGGGAAAGGCGCTTTGAACTTCCCTCATGATTCTTTCACTTCTGTTCTC
     CACAGGCTGGTTCTGAACCCGGTGACGAAGGCTGTGATGACGATGATATTTTGGCCACTTGGCAC
     TGGGGTTCAGGGTTAGCTTTTTCATGACCTTTACTAGTGTTTCTGGTTGTAGGGTTTCTGAATCA
     TTGGGGTGAGTCCTCTCCACCTTTCCTCTGAGATCTATCATCTGAGTTTCTGGATACACAACTGG
50   GTCAACTTTCTGTGATGGCTCGTCCATGGCGGTGGGCAGAAGCCTCAAAGCCAGCTCCGAACAA
     AATTGCTAGCTAATCTTTGGAAAGACCTAGACTTTGGCCCCAACTAGCAGACTGAAGTGCTGGAA
     TTTTTTTTTTTTTTTTTTTTTTTTTTGTAATCAACTTGAAAACACAATTGAGAAAATGCTTCCA
     TAAGGTTAAATCCTTGTGCCACCATGCCTGGACCTAAGCTTTTCATGGCCACTATTCCTCGAGGT
     CTGGATCAGAAGCTTGTGTATTTCATTTCCGGATTGTCGTTCACTCCAGATTAAAAGTCCAAATG
55   AAAGCAATAGCCATGTAATAATGCCTAGATATAACTCTTCCTTGTTCAGCAGCAAATGCATAAGC
```

AATAAGCTTAGCTGGGTGGGATCTTCCAAAGCTACTCTGCTCTTTTTCTTCTTGGACATAGGATT
CAGCAACATTCTACTTCTTGATGCCCCTTTATTCTTTGAACCATACATTTTTACTTTTCCTTTCG
TAGCTTCTTCCTTTTCATCAAAAGATTCTTCATAAGAGTGAAATTTGGGGTTAGAGAGATGGTTC
AGTGGTTAATAGCACTGACTGCTCTTCCAGAGGTCCTGAATTCAATTCCTAGCAACCACATGGTA

5 GCTCATAACCATCTGTAATAGGATCTGATGCCCTCTTTTGGTGTGTCTGAAGAAGACAGCAACAG
TACTCAACATACATAAAATAAAATAAATCAACATACATAAAATAAAATAATTTTTAAAAAAAA
AAGGTGAAATTTAACCACACAACAGAATTTATGCCAGGCTTGTTTGAGACTTTTGTCAAAGCAAT
TAATCTAAATCTCTTCACCTTAGCCTCAGGTAGACTCTCTGGACAATGGCAAAAAGCAGCCACAT
TCTTCATCAAAATATTACAAGAACGGTCTCTCAGCCACATACTAAAATTCTTCTCTGAAACTTCT

10 AGAGCCAGGCTTCCACAGTTCAAACCACCTTCAGCAACAAAGTCTTCTATATTCCTACGATGATA
GCCCTTTAAGCCCCACTTAAAGCATTTCACTGAATTCCAAATCTAAAGTCTCCAAATCTATATTC
TTCCAAATAAAAGCATGGTCAGACCTACCTATCACAGCAATATCCCAGTCCCTGGTACCAACCTC
TGTCTTAGTTAGGGTTTCCATTGTTGTGAAGAGACACCATGACCAAAGAAACACTTTTTTTTTTT
TTAATATTTATTTTATGTCTATGAGTACACTGTTGCTGTCTTCAGACACACCAGAAGAGGGCATC

15 AGATCTCATTACAAATGGCTGTGAGCCACTACGTAGTTGCTGGGAATTGAACTCAGGACCTCTGG
AAGAGCAGCCAGTGCTCTTAACCGCCGAGCCATTTTCTCCAGTCCCAAAGAAACACTTATAAAGG
ACAATGTTTTTTTTGGTTTTTTTTAAAGGTTTATTTATTTTATGTATATGAGTACACTGTAGCTG
TCTTCAGATACACCAGAAGAGGGCATCAGATCTTACTATAGATGGTTGTGAACCACCATGTGGTT
GCTGGGGATTGAACTCAGGACCTCTGGAAGAGCAGTCAGTGCTCTTAACCCCTTAGCCATCTCTC

20 CAGTTCTAAAGGACAATGTTTAATCGGGGCTGGCTCACAGGTTCAGAGGTTCAGTCCATTATCAT
TGAGACAGGAGCGTGGCAGCATCCAGGCAGGTGTGGGGCTGAAGGAGCTGAAAGTTCTACCTCTT
GATCCAAAGGCAGACCAAAAAAAAGACTGGCTTACGGGCTTACCATAAGCAGCTAAGAGGAAGGT
CTCAAAGCCCACCCTACAGTGGCATGTTCTCCAACAAGGCCACATCTCCTAATAGTGCCACTCCC
CGGGCCATGCATATTCAAGTCGCCACACCCACTGAGCCATCTCTCCAACCTGCTCCAGACCATCT

25 CCCCTGCTTTTACCTAAGCTCATTAGGCAGCAATATGCCTCTTATTGTTTGAGCTCAGCATCCTG
TTTTTCAAAAGGCTGCTTGTCATCACAGTGGTTTGTTCCACAACTCTCCCAGTTTCTTTGTNAAA
ACACCAATGCCTAGAGAGATGCTCTTCTGTACATATCGCATGTGCAGAAGAAAGGGTGCCAGATC
CTTTCATGTGGACCNTGTCATGTCTTTACCCACGTAGTCGTCTGCTCTGACTCTTCTCGAGATGC
TGANAACTGATTGAGCGTAGGATGCTCTGGGTATGTGCATGGACAATTTTG

30 **SEQ ID NO: 8 (RAT GCR2 HOMOLOGUE NUCLEIC ACID)**

Rat GCR2 (Stella) homologue genomic sequence; different intron-exon structure

from mouse-Stella (fused exons). AC103122 (11084 - 13244: contig of 2161 bp in length)

CGAAGGACGGTAAGGAGAGAAGAGGGGAGAGGATCAGGACTGAGGGGAGATATGCACTGAACGGG
GGAGTTAGTAACGAGGAAAAGATAGGGAGAAAGTGGGAGAAAAAGGCCGGGGAGGGGGAGGGC

35 ATGGAAAGAAAGGCGGGGGGGGGAGATAACATGCGGGGGAAGTAAGAGGGGGGGGGTAAGGAGGG
TACAGGTAGCACAGGTGGGGGGAAGAGAGGGGAGGGGGGGAATGGGAAAGGTGAGGGTGGGTGGG
GGAGTTTTCGGCGAAAGGGGCCGGAGTGTGGATTATCGCGTGGACCAGAACGGGGGAAGGGCCAC
ATTTGGGTGGGCGGGAACAGAAAGGAAATCTTTTTAAATCGGTTGGGTCGCAGGGTGGGTGGACA
TTGAGAAAAAATCATCAAAGCCCCTAAGGAGCATTTGTTTCGGAGTTATACGTATGGATATTTT

40 ATTATATGGGACGAGAGATAAAGAATACTTCTTAAGTAATCCCTTTAAAAATAATGTCAGGCTGG
AGAAATGGTTTCATGGGTAAGCAAGTGTGAGAGATGAGCGCAGACCCCCAGGACCTGTGTAGACT
TAATGCAGAGGTGGATGCACGCCTGTAATCTCAGCATGCCTACAGCCAGATAGGAGATGGGGACA
GAGAAGTGTGGGGGCCAACTAGCCTGGTGTCTACAGCCTGGTGTCAACAGCAGCCTCCTACCTCA
AACAAGGTGGAAGGTAAGGGCTGATACCTGAGATCGTTGTCTGACCTCCACACACATTGTGCTTA

45 TACTTTACACACATACTCACACTCACACATACATACACATATATACCTGGTCTCCATTAGGCTTC
TATTGCTGTGATAAGATTACGACCGAGGTCTTTCCAAAGACTAAGCAGTTTTGTTTGCAGCTAG
TTTTTGAGGCTTCTGCCCACCACCATGGAGGAGCCATTAGAGAAATCGACCCAGTTGTGGACCCA
GAAACTCCTCAGACGAAAGATGAAAAGGACGCATCCGCTGATTCAGAAGTCGTAAGCCAGAAACA
CTAGTAAAGGTCATGAAAACGCTAGCCCTGAACCCCAGTGCCAAGCGGTCAGCACATCGTCGCAG

50 CCTCCGTCTCCGGATTCAGAGAAGACCTGTGGAGAACAGAAGTGAAAGAATTTCGAGGGAAGTTC

AAAGCGCTTTACCCAAGAGAAGGGTCCGCACGTTGTTGTCGGTGCTGAGAGATCCTATAGCAAGG
ATGAGAAGACTTGTTGGGATTGAGCAGAGACAACACAGGCTGGAAGGAAATGAGTAGAAACGGAA
GAGTGTGCCATTCAGACTCACTGTGCTTTCTGCCATTATCAGAGACGGGATCCGTCTGAGAACGC
TAAAATCGGGAAGCATTAGGACAGCTTAGATTGTACACTGTCCTTGTGTTAATGATGCCATGCAG
CAGACCTGAAAGCTGGCTTTTGCTTTTTAAGATTAACCTTTTCCTGGTGCTGGGGACTCTTCTAA
CTTGTTAACCTTTAAATTATATAGGGTGCGTGATGTTTGGATTCATGTGAATGACTTAAATTTAC
CCAAAGAATTGAGAAGGAGTCAAAGCATTCTGTGAATTTTTGAAGCCTCAAGCCCGGGGCCGAGA
AACAATGTTAATAGAATTTGGAATAGTTTGGTTTAGAAGGTAATTGGGATAGATCTCTGAATTTT
CTAGTTTGCAAAAACAAAAACAAAAAAAAGACTAAAAAAACAACTGGGGAGGAGTAAGGTTATT
TCAGCCTCCATGTCTTGATCCCAGTCCATCATGAAAGGAAGTCAGGACAGGAACTCAAGTCAGGA
CCGTGGAAGTAGGTAGCATCTGAAGCAGAGACTTCTGGGATGAAAGCGCTGCTTCCTGACTCGCT
CCCCACAAATTGGTCCCTGAGCCTTCTTGTCCACCCTCGGACCCCTTGCCTAGGGTTGGCACCAC
CCACAATGGGCTGAGCCTTCCCATGTCAATCACTAATTAAGAAAATGCTGTACAGCGTTGCCTAC
AAACCAGTCTTAAGGAGGCGTTTTCTCCATTGTGGCTCTCTCTTCTCTGATAACTCTAGCTTGTG
TCAAATTGACAACCAACCAGCCAGCACACAAACANTTAAAAGATAGAAATAATGTTAGTGNNTC
NCATCGAGCAAGAGTC

SEQ ID NO: 9 (RAT GCR2 HOMOLOGUE NUCLEIC ACID)

Rat GCR2 (Stella) homologue genomic sequence; different intron-exon structure
from mouse-Stella (fused exons). AC099436 (1 - 21688: contig of 21688 bp in length)

TTTATGATTTTAAAAGTTTAATTCTGGACTGGAGAAATGGCTCAGTGGTTAAGAGTAGTAACTGC
TCTTCCAGAGGTCCTGAGTTCAAGTCCCAGCAACCACATGGTGGCTCACAACCATCTGTAATGAG
ATCTGATGCCCTCTTCTGGTGTGTGAAGACAGCTACAGTGTATTCACATACATAAAATAAATAAG
TAAGTCTTTAAAAAAAAAGTTTAATTGTGTGTGTGTGTGTGTGTGTGTGTGTGTAAGCTTGCA
AATAAGAGGACAACTTTGAGGAGCTGATACTCTTGTTCTACTGTGTAGGGACCAACAGTTGAACT
CAGGTTGTCCGGCTTATGCAACAAGCTTTTTTACTTGTCTTCGCCAGCCCACCAGTCCTGTGTAA
AGCTGCATACAGCTCACGTTGTAACATGCTTGTCTAGTACTTGCAGGACATAAACTAGCAAGCAC
TTGGGTGAAAACGGGAGGATCAGAAGTTCAATACTATCCTTGGCTACTTAACAAGTTTAAGGCTA
TAGGAATAGGGATATAGGAAACCCTAAGAAAGTAAAATTTATTTACTGTGCTTTAGGTGATCAAA
CCTACAGCTTTGCATGTGATAGACAAATGTTCTACCACTAAGCTACATCCTCAGTGTTCTTTATT
ATCTATTTTTTTAATAAATCTTTTTTTTTAAACATTGTTGTGAGCCACCGTGTGGTTGCTGAGAA
TTGAACTCGGGACCTCTGGAAAAGCAGTCAAGGAAGCCAGAGTGGCCGGAACTCCTGAAAATGGA
GTAACAACAGGTTGTTGTGAGGGTAATTGAACTCAGGTCCTATGCAAGAGCAACAAGAGGTCTTA
GCCCTTTATTATTTTTTAATATCTAATTATTTTTTTATTTTTTTATTTTTATTTATTTATTATAT
ATAAGTACACTGTAGCTGTCTTCAGATACACCAGAAGAGGGCATCAGATCTCTTTACAGATGGTT
GTGAGCCACCATGTGGTTGCTGGGAATTGAACTCATGACCTCTGGAAGAGCAGTCGGGTGCTCTT
AACCACTGAGCCATCTCTCCAGCCCTAATTATTTATTTATGTATGTGAGTACACTGTAGTTGTC
TTAAGACACACCAGAAGAGGGCATCGGGTATCAGATCACCATTACAGATGGTTGTGAGCCACCAT
GTGGTTGCTGGGAATTGAACTCAGGACCTCTGAAGAGCAGTCAGCATTCTTAACGACTGAGCCAT
CTCTCCAGCCCAACCCCCCCCTCCATTTTTTTTAATACCAAAAGGAGCTTCCTGCAAGAGAACA
TGGCCATATACATCCACCCCTCTTTCTTTGAGGTTTTGATAGTGCTGCTGCTCCTGCTGCTTGGA
AAAGAAAATCCTCTAGGACTAAGCTAAAAGAGCCAGATGGATGGAATTGCGGTTGCCATGGCAAC
ACCATCTGAGGATACTGAGCCTGCTGTCTCTCCCAGTTATGTTGACATTTGGTGTGGTTTCCATG
CTTGAACACTGAAGTGTCTGTCCACCTATGAAAGAGAGGCCGTTCCCAGAGGTCTTAATTTATCT
GCTCCATCAGTAGCATTTGGACTGCTTACATTTATGTCTGGACAACCATTGGCCAGGAGGTAGAA
GAGGATGGAGGAAGGCCCAGACCTGGCTGGGTACTATCGGATCTAGTGAAGCTGTATAGAATCTG
TCTGGGGTTTATTTACTCCCAACTGGAGCAGAGGCAGGTGCTCAGGAAGGCAGTAATGAGATCGA
CCTTACCACAGGAAATAAAGTGACTACTGTGGATACCATCTGGGATGGATCACCGCTGAGCCACT
CCACCCTCAGAACAAAGCTACCATATCGTTAAAGTGTCCTGAGCTCAGGGGAAGGCCCCTGCTGC
CTGTGAGTAGAGCCAGGTAACCTTAACAAGCCTATCTACACTTCATCTTAAGGCATTCTGTTAC
ATACAAAGAATTCTACTCTTTAATGAGCAGACTTTAAAAAAAATGAGCCAACTTACACTTTCAGA

```
       AGTTTGATCCTTGATTGCACATGCCTGAGACAGATGGCCAGTCTCAAGGACAGGCCTCCCACACT
       GAAGTTAGTCTTCAGCAGTATGTCATGTCACCTAGGCAACCAATAAGAGCTCACCTAAGAAATTT
       CCACTTTACCTGGTAAAGAGCGTATCTTCCCTCCCTTTCTCTCCAATTAGCATCCTCACTTCCAG
       ACTTCCCTACTACCGACTTTAAAAGATCAAAGCCAGGCACGATAGCACAGGCTGAGGTCGGAAGG
   5   CAGAAGCCAGAAAGATCTATGTGATTCCCAGGCTACTTAGCACCACAGTTGAGACCCTGTCTA
       ACAAATGGAGGTGGGAGGCATGGCAGTAACCTGAACCTACAAATTTATCAAAATTTCAATTAAGA
       ACATTTTGTTTTGTTTTTGAGGCAGAATCTCACTACGTAGAGTGGGCTTACACCCAGTTCCAATT
       AAGAACATTTTAAGGGCTGGAGAGATGGCTCAGCTGTTAAGAGCACTGGCCACTCTTCCCAAGGT
       CCTGAGTACAATTCCCAGCAACCACATGATGGCTCACAACCATCTGTAATGAGGCCTGATGCCCT
  10   CTTCTCTTGTGTCTGAAGACAGCTACAGTGTCCTCATTTAAATAAAAAAACATTTTAAATAGAAA
       ATCCAACAGGGAGGCTGATGAGAAACGACATAACCTTTGTCCAGGAGTGTGGTTAAGGGGAATGG
       AACCATAGTAGAGTCCATTTCTTTTTCTCTTTTGAGCCAAAAAAGTTTTATTTATTCATGTCTTC
       CATTTGAAGTACTCCTTGGTGGCATCCTAAGCCTGAGATTCTTTGCCATACGTAGTTCTTAACCA
       CTACCCAACTGCAACCAACTGTTTTCTGTGGCATCCCTCTTGATGACTTTTACACAGGGGTTGGG
  15   GATTTAGCTCAGTGGTAGAGCGCTTGCCTAGGAAGCACAAGGCCCTGGGTTCGGTCCCCAGCTCC
       GGAAAAAAAAAGATTTTTACACGGGCACACCCACTCCACTAGTTTCTCATGATCAAGTATAATC
       AGATTGATCTGGTGCTCGGCACAAAGTGCCTCCTCCAGCTCGACACACGAGCTCATCACAGTC
       GGATTCGAGCACACAGATGGGTTTGGCACTTGTCTAAGGCTTCAGGAGCTTTGTGTTTGCCAACG
       TGCTGGGCTATCGTGGATGAGGGCGGTCTTCAGCACCTCTTGTAGAGCAGTGTTGACATCCACAC
  20   CTCCAGTGGCAGTGCCCTGCTCCGCTCTCGGAAGCTGAGGTGGAATAGCAAGTCAGTTTCTTCTC
       TCATTTCCCAGACACCATTATGGATGCCTCAGTGTCAGCTGTTCATTTGTCACTTACTTTTCACA
       ATTGTGTTATTATTATTGATAGATTATTGTCTCTGTCACTAGCTACCGAGGCAGGGTCTCACAGG
       ACTTATCCAATTGTTTCTGCCTCCCTCGAGCTAAGCCTGAAGGCATATATGAATCATCTCACCAA
       GCAGCATCAGCTTTTAAGAGTTTCTGAACGTCAACACGTTAACACTGGGGCCATATTATGTACGA
  25   TGTAATTAATCCTCGAGCAACTGGCCACACAGCCCTAAAAGAAAAAAAATCCAGAACCAAACAA
       ACCAAAAACAGGCACGAATGGTGGCACACACCTTCAATCTTTACACTTGGAAGGTGGATCCAGGA
       GGAGTAGGAATTCGAAGCCGGCCTAGAGTACCAGTAGTTGAAGGCCAGCATCTGTCTCAAAGCAA
       ACAACGATAATAAAGTACTTGTTTCAGCTGGGAGGTGGTGGTACATTGTGGAGGGAGAGGCAGAC
       CTTGAACACTGGGTTCAAGGCCAGCCTGGTCTAGAGATCAGATCCCCAAAACAGCCAGGGATAGA
  30   CAGAGAAGCCCTGTCTCAAAACGTGAGGCTGGAGAGATGGCTTAGTGGTTAAGAGCACTGACTGC
       TCTTCTAGAGATCCTGAGTTCAATTCCCAGCAGCTATATGGTGGCTCACAACCATCTGTAATGGG
       ATCTGATGCCCTCTTCTGTGTGTCTGAAGACAGCTACAGTGTACTTATATACATGAAATAAATCT
       AAAAATAATAATAACGTGCACAATGTTCTGCCTGCCTATATGCCTGCAAGCCATCCCTCCAACCC
       AATAAATAAATATTAAAAAAAAAAAAAGCACAAAACCAAACCAAAAGTAAAATAAATAAACAAC
  35   TTTTATTCCTACCAAGAGAAGACACATTTCCTTGAGAACTAAGGACAACATGTTTATGGTTAGAA
       CACAGAAGAGAATAAGAGCACAGCTCAGCTGGAAGAAACAAAGTGTTCTGGGGACAAGGAGCCTT
       CTTCCCTGCCCCCATAACAGTGGCCAGATTGAACCTCTGGTACGACAGTCAAGTTGGTGCTGAGT
       TCAAGTTGGAAAGTCACACTTTCTAAATCAGGATCAAAGCAAGCTGGAGGCTCCCTCACTCAGCT
       CACAAGTCCTGTGAAATCAGGAAAAAAATATCAGTTAGACACTGAGTTCCCAGGCAGCCAAAAAC
  40   CAAAGATTTCCCACCACCAAAGACAAGGTATCTTGGATTTCCAAGGGAACAGAATGAGAACTTAT
       ATCTCTGACTGGCATTTAAATCCTACAGCCATCCCTCTCCAGCACATCCTTTCTCCAGGGAATG
       GTCCCAGCACCCATGTCAGGCACTCACCCAAGTAGTCATCCATCAGAGAGCCAATAGCAAACTGC
       GAGAGGAAAGGGAGAAAGGATGGTGAGGTGGGGCCCCACCCCATTCCGAGCCTTCTGTCATCTAT
       TCCCTGCTCATGGACACAGAGCACAGAGCCCCCAACAACTGTGGATGGCAAGAGGTCAACAGCGC
  45   AGATGGGGAAAGAGCTTGCTCCAACCCTGATGACCTGACCTCCACCCCCAAAATCCACAGCAGCA
       TGCGATGACCTGAAGGCGGTCTAAATGTCACACTGTGGCGAGTGTGTATGCCCACACATCCACAT
       AAATATGTTCTACAAAGAAACGAGAAACCCACAGCTGTCAGCTGTGAATGATGACTTTGGATTA
       TTTATAATCCTACTACCCAGGAGGCTAAGGCAGGCCAGTCAAGCAAGAGACTCACAATGTCATTC
       TTGTCTACACGTGTCCCTACAATCTTCAAGCGTATCTCATCGTCCTGCTGAATTACAATGTCCTG
  50   TGGAAAGGAGAGAGCAGGGTCATCAAGCAGACTCAGGCCTGGTCCTCATCCCTCTCACCAACTCC
       TCCTCATTCGCTCACCTCATCCATGGTCTTGTAACAAGGGGGGTTCGAATTTGGATCAAACTCCA
       TCTCTGAAGGGATGGACTAGAAGGAAATTGACACAAAGGTTAGCATTTCAAATAGCTGCATCAAA
       GGATGAGAGTCAGGGGCTGGTTTCTCCTCCTCGGCCTCACCCCACACGCCCAGACTCACGTGTCG
       AGAGATGAAGCAGGACATGGGCCCAATTTCTGTGAAAAGTCCAACCTAGAAGGAAAATGACCGTG
  55   CTTCAAACGCTCTGAAGCATCTTTACCTGATTTCTAGGCACATTATTCATGTTTCTTAACAGTTT
```

```
          AAATTGTAGCATTTGTTTTAATTTCTCTCTGTGTAATCTTTCATTTCTTTACATTTTTGTTCTTC
          ATTATTTTTATGTGTAAGAATATTCTGACCTCACATGTGCCTGTGCACCATGTACCTGCAGTGCC
          CATGGAAGCCAGGAGAGGGTATTGGGACCCTGCAGAATTAGGAGTTACAGATTATTGTGAGCCAT
          TGGCTGGGTGCTGGGAGTCAAACCCAGGTCTTATAGAACCAGTAGGTGCTCTAAACCACTGAGCT
    5     ATAGACCCCTTAGCCTTTAAGAAACTTAATTTCTGAGGCTAGAGAGATAGCTCAGTGGTTAAGAG
          CACTGACTGCTCTTCCATGGGTCCTGAGTTCAATTCCCAGCAACCACATGGTGGCTCACAACCAT
          CTGTAATGAGATCTGATGCCCTCTTCTGGTGTGTCTGAAGAGAGCTACAGAGGAGTGTGTATAAT
          AAATAAATCAGGGGCTAGAGAGATGGCTCAGCGGTTAAGAGCACTGATTGCTCTTCCAATGATCA
          TGAGTTCAATTCTCAGCAATCACATAGTGGCTCATAATCATCTGTAATGGGATCTGATGCCCTCT
   10     TCTGATGTGTCTGAAGACAACAGTGTACTCATATAAATAAAAATAAACAAACAAACCTTAAAAAA
          AAAAAAAAAAAAAGAAAGAAACCCAAAACTAAGATAAAATAAAATAAATCTTGACAACCACA
          AAAGGCTTAAGGCAACTAATAAGTGGACTGGGAATTGAACTCTCACCTTAGGAAATACCCCGTAA
          CCTTTCTTTTTTTTTTTTTTTTTTTCTTCTTTTTTTTCGGAGCTGAGGACCGAACCCAGGACCT
          TGCACTTCCTAGGCAAGCGCTCTACCACTGAGCCAAATCCCCAACCCCATAACCTTTCTATAAAT
   15     AATACTCTTACCTTGTTGACCTGAGTGACCACAGCATCCACCACTTCCCCTTTAAAGGGCCGGAA
          AACAATAGCTTTGTATTTCACTGGATAAAGAACAAAACCTCGGCCCGGCTGGATCACACCAGCAC
          CAATATTGTCGATGGTAGTGACAGCAATCACAAAGCCATATCTGCAGGAAAGATGAAAAAGACA
          GCTACTGTATGTGAAGAGCCTCTAAAAAGCCACCAGCAATAGTCTGCGTGTGATGGAACCTCTGC
          TCGAACAGCTCGATGACCAAGAAGAGACAGAACTCAGATTAGCACCTGAAATATTAAATGGTGCT
   20     CTCACAATTGTACAGTAAATGCCCAAGAAGGCACAGATATGCTGACATACACCTATTCTCTCAGT
          ACCAGGACTTGCCAGGTCAGTGGTGAGACAGGTCTTTCGAAAACCACAAATCAGACAGAAAATTG
          TGACGAAAACCTTTAATCCCAGCACTCAGTGGCAGGCAGTTCTCTGAATTAGAGGCCAGCTTGGT
          CCACATAGTGAGGCCATCTCGAAACCCAAAACATTTGCATAATAACGGTCTGATCTCGCATAAGC
          GAAGAAAATTTGGTTTAGCAACCTTTTAGAAGGCCCAAAATAGGCAAAAACTGGCTGCTTCGGAT
   25     GCCTGGAGTGGTGAAAGAGTTCCTCAGAGTAAGTAACAAGCCCTGACTGAAGGAGTGAAGTAGAG
          GTTACAGAGTAGCGTTATTGTGCCTGCATTCAGCAGACGACACTGTGAATCAGACACTTACTTCC
          CAGTGCAGGTCCCCTCCACCTCGGTGAACAGCTTCTGCTTCACCGTGTTGAGCAAGTTGGGACCA
          AGTAGCGTGGGTGCAGTAGGATCTCGTGCTCCAGGGAAATCTGCAGAGAAGGAAGATGAAGAC
          TCCGCCAGCCACACTGAGAACAGGAGGCGACCCGTCGGCCCTCCAGGCTCCTCCTGTCCCTGCCC
   30     TCACCGCTACCCCGCGTCCAGCTCACATGATAAACATCTTCTGCAGAAGCTTGGACCGCAGAGG
          CCAGAACTCCCCAGGAAGGGACCTCGCCGGAAGCACTAGCAGAAGTCCCACCAAGTCTCCGCAGT
          CGCTTCCGCAGATTTGAGTCTTAACGCCATGGGCGGGGAAACGTGAAGCCCCGCCCCTCAGGCCT
          TCCCATCAGCGCTCATCAGCACAGCCAGGATTACACAGAAAAACCCGGTCTCGAAAAACCTTAAA
          AAAAAAAAAAAAAAAAAAAAAAAGGTTAAGAGGTCTGGCTTGTCGCCACATGCCTTTAAACCC
   35     AGCCGTGGCAGACAGATCTCTAAATTCAAGGCTAAGCCACATCTACAAAGTGAGTTCCAGGATAA
          CCAAGACTGTGTATACAAACCCTATAAAAAATTTGTTTTTGGGGTTGGGGATTGGCTCAGAGG
          TAGAGCGCTTGCCTAGCAACCGCAAGGCCCTGGGTTCGGTCCCCAGCTCCGAAAAAGAGAAAAAA
          AAATTGTTTTTTAAATTTTATTTTAGGGGCTGAAGAATTAGCTCAGTCCTTAAGAGCACTTGCCA
          GCCCCCACAGGATAGCTCACAATCTTATCTGTAACTACAGTTCAGAGAGAACTGACACCCTCTTC
   40     TGGCTTCATTCAGCACTGCATGCTAGTGGTACACAGACATAATGCAGGCAGAACACCGATGCTTG
          TAAAATAAAAATAAAGATGAGGTAGTTGGGGAGATTGCTCAACAGTTAAAATCAATGGTTGCTCC
          TCCGAAGGATCCAGGTTTGATTCCTAGAACAAACATGGTAACTCAACTAGCTATATTTCAATCCT
          AGGGGATCCAGTGCCATCTGGGGCCTCCATGGACACTTCTCCCTTGTGGTGAACAGGCATAGATA
          CAGCCAGAACATTCATACATATAAAATAAAATAAAGGTTTTACACATAAAATAAAAATAAAGC
   45     TCTCGAAGAGGACCTGAGTTCAATTACTAACACTGCACCCGAGGTCTCACAACTCCAGCTCGAAG
          GGGATCTGAAACTTTCTCATTGCCTCAGGAGGTACCAGCACTTGTGGGCTTGTACTCACATACAG
          ATAACAGACATCATTGAGTACACCTAATTAAGAAGAAGTCACTTGGAAGTGTGGCACACGCCTTA
          AATCCCAATATTCAGGAACAAAAGGCAGGTGGGTCTTCAAGTTCAAGGCCAACCTGGTCTACAGC
          ATGAGTTCCAGAACAGCCAGGGATACATTAAAAATGAAGGTGTCGGGGTTGGGGATTTAGCTCAG
   50     CGGTAGAGCGCTTGCCTAGCAAGTGCAAGGCCCTGGGTTCGGTCCCCAGCTCCGGAAAAAAAAA
          TGAAAGTGTCTTGTTAAACAAAACAAAAGACAACAAGCAAAAGATTACTTATGTGGGCACGCA
          CTGGGCTTACTTTCTTTTCTATTTGAGGGACGGTTTTATTATGTGACCATGGATGACCTGAGATT
          TGCTTTGTAGAGTAAGCTTGCCCTGAACTTTTTTTTCCCTGGAGCTGAGGACCTAACCCAGGGT
          GGTGGGTTTATAGGCAAGCGCTCTACCACTGAGCTAAATCCCCAACCCCCCACCCTTCACTTTTA
   55     GGATACCAAGCAGACTCCTTGGTCTAGGAACAACCTCAGCCTCGGGACTTTTTTTTTTTTTACAC
```

```
      TAGGTTCCGCTCCTGTTAGACTAGACTCTTCCACCCCTCAGTACATTATACTACTAGGACACTAG
      GACAAACCATAGCAAATCTGTCACAGCACCAGTGACAGCCCTAAGCCTGACTCCATCTTTTCTTT
      TCTTTTTTTAAATATTATTTATTTTATGTATATGAGTACACTGTCATTGTTCTCAGACACACCAG
      AAGAGGGCATCGGATCCCATTACAGATGGTTGTGAGCCACCATGTGGTTGCTGGGAATTGAACTC
  5   AGGACCTCTGGGAGAGCAGTCAGTGCTCTTAACCGCTGAGCCATCTCTCCAGCCCCCACTGAAGA
      CTTTTGATCTGGTTACCATCTGACCCCAATCTCTTGCAAAGCCTCCCTTCCTCCTTCGAAGAAA
      CTCTTACGTCTTTTATGTCCTTGGCCCATGACTTTGTATTAAATCAGCAACAATGACAAGACCTG
      TATGTCTCTCCCTAGCTCAGAAGACAGATCCTTGTTCCTTGTTAATGTTTTGATTTTCTGGTCTG
      TCCGTGGGGACAGTCTGATAGTTCTAAGACTGATAGCTTTGAGGGATTCTAAACTCACAACAGGG
 10   CTATTGTTACCGATGGGCACAATACAAGGCTGCCATTGCTTTGGAGTGGGACCATTATCTTGACA
      GAAAGAATTACCATAAACCCTAGCTGTGATTGCTCCGGGAGTCCATGCTAATGAAACACTGCCCA
      CGGCCTTCAGGAAACTTCTCACAGAGTGCTGCCTCTTGGAATGACTGTGTGAACTCTCTACTGTC
      CACCTGCAGCAGCCATACCGAAATACAGTCTAATAACCTCTCAACTTCTGCATTCTTAGTCTTGG
      TGAACTCTTTCGCCTCCAATGTCATGACCTTTCAAAGTCACCTCACATAGCAGTCTGCAGCGAGA
 15   ACAGGTAATTCAGGGGCTGGGGATTTAGCTCAGTGGTAGAGCGCTTACCTAGGAAGCGCAAGGCC
      CTGGGTTCGGTCCCCAGCTCCGGAAAAAAAAAGAACCAAAAAAAAAAAAAAAAGAGAGAACAGG
      TAATTCAGCTAAGACTGGTGACACAAGTGTAATTTTAATACTTAGGAGGTTGAGGCGAGCGCATC
      TGGAGTTTGGATTAACCTGGACTCCATAGTGAATATTGGGCTAGCTTAGGCTACATAAGCAAGCC
      TCTCTCTCTCTGTCTGTGTCTCTGTCTCTATCTCTGTCTCTGTCTCTCAACCACAAAAGAGAG
 20   AACGGAAAAAAGGAAGAAATTAAGAGAAGAAAAACAAAGAAATTTCTCTAAGCAAAGCATATT
      TATTTATTTATTTATTGTTTTTCAAGACAGTGTTTGTCTATGTAGCATTGGCTGTCCTAGAACAA
      TCGTTGTAGGCCAAGCTGGCCTTGAACTCATAGGCCTGCCTTTGCCTTCCAAATACTGGAATTGA
      AGCCTTGTGGCAGCACTGCCCAGCGACACCTGGAATTTTTTAAAATTTATTTATTTATTTATTTA
      TTTATTTATTTATTTATTTATACACTCCAGATATTATTCCCCTCTTGGTCCATCCCCCAAC
 25   TGTTCCACATGTCATACCTTCCCCCACCCCCCAGTCTCCACAAGGATGTCTCCAACCCACCCACC
      CTCTCTAATTTTTATTGTACATTCCTCTTTCTTTCTTTTTTTTTTTTTTTTTTTGGGTCTTTT
      TTTCCGGAGCTGGGGACCGAACCCAGGGCCTTGCGCTTCCTAGGTAAGCGCTCTACCACTGAGCT
      AAGTCCCCAGCCCCTACATTCCTCTTTCTAACTTCTTTGGCACAGCATCTTGGAGGGTGCAAATC
      AAGAGACAGCTTTTCTTTTCTTTTGTGATGCCAACTTTCAAGCATTTACATTTTGGGTTGGGTTG
 30   GGTTGTGATTTTTTTTTGTCTTCGAAATCTGCATTTTTTTCTTTCCTTTTTTTTTTTTCA
      GAGCTGGGGACCTAACCCAGGGCCTTGCGCTTGCTAGGCAAGCGCTAAAACACTGAGCTAAATCC
      CCAACTCCTAAATCTGTATTTTTATTTGTAACAACTGTATTTCTTTTTCTATATCCTTTAACTCT
      GGAGTTTTCATTTCTTCCCTCCTGCCCCCATAACTATAGTCACAGTTAAACTGTGTTATCAGGAA
      ATTCAGGAAGGTGCCTTGATGAACAGATCAGGACAGGAGCTCTGACCAGTAGTCACTGTCTTCC
 35   TCTTCCTTAGAATAAGTAAAAATGAAACCAACCAAACTTTCTTCTCTTTCTTTCTTTCTTTTTTT
      TTTTTTTTTTTGACGTGTCTCCTGTGCTTTGTCAGTAGCATGAATTTCATTTTTTTTTTTT
      TTTTGGTTTAAAAAAGGCAACCTCAAAACCCAAACCTCTTTATTGTCAGGGAAAAGGGAACTGCA
      ATGACTTGAATTTGAGGATGTGGGTACTGCCTCACTCACACACATTCTCAGACTGTGTGATGCCC
      TGCACACCTGTAGAACAGTTACATGTATGTGCACCTGTATTTGTGCCTATTAGAACAGGACCTGC
 40   AGGGAAGTCTACCTAACCCGAAACTCCCCAGTGGAACAGGCAGGGTGGGTGGAGGGCTGGGACAG
      ACAAGGACTCGGCGCACACATACAGTACCACATAAACAGTACAGTGAAGGTGGGCTCAAGACCC
      AGGCAGCTTCCTTCTTTTCAGTAACAGGGCCCAGGCTGCCTTTCACAGCACAACCCCACAGCTGA
      ACCCAGGTCTCTCTTCAAAACCAGCCATCTCACTCAGCAGCGCCAAAGGAAAAGTAGATGTAGCC
      TCCCTGCAGAGAAACAGCTTTTCTTGTTGTTTTAAATAAGTAAGTAAATCCACCATCCCTCTGC
 45   TCCAAGATGGCTGATGTTACACTTTTCTACCAGATTGGTGCCTGCTTAGCTCACTAACAGTGCTG
      CCTCCGCCGGCTGTGGCAGAGTTTCCAGTGTGGTGTTTTCAAGCCTCACCCACTCATCCTCTCAT
      TCCCAAACATTCAGTGCCCTCCTCACTTAGGGGTTTTCGAAATGTTTAAATTTTGTATTACTTTA
      AATATATATTTGTTTTATTTTCATGCGTCTGTGTGTATGCTTGTGAGTTTCACACATGCTGTGTG
      TGCACAGGAATCTATGAAAGCCAGAACAGGGCATCAGATCTACAGGAAGAAACCAAGTGTCCAAA
 50   AAGGGAAGAAACGAGATCCATCTGCCTCTGTGGTGCTGGAATTGAAGGTGTACATCACTACAACC
      ACCGGGGATGGGTATGTATGTATATATATATATATATATGTGTGTGTGTGTGTGTGT
      GTGTGTGTGTGTAAGGGTGTCAGACCTTCTGGAACTGGAGTTAGACAGTTGTGAGCTGCCATG
      TGGGTGCTGGGAATGAACCCTGGCCCTCTAGAAGAACAGCTGATGCTCTTAACTGCTGAGCCATC
      TCTCCGGCCCCTTATTTTTTATTTGTGTGAGAGAGTGGAGGTCAGGGGACAAACTGAGAGACTTG
 55   GTTCTCTCCTTCTGCCATGTGAATGCCAGGGATTGAATGCAGGTTGTTAGCCTTGGCAGTGAGTG
```

```
      CTTTCCCCGCAGGGCCATCTTGTCAGCTCTTTGATTACATTGTAAACCCTGGCACTGTGTTATTT
      GCTGGGAAATGTTTTTAGTTGTGGGATGACTCAGCTTTAGCACATGCCTTTAATCCGAGAGCTTT
      CTGCTTGTATATTGTAAGCAGGATTAAATAAAGTCAAATCTTAGGTCAAGAGATGGAGCAAGCAA
      AGAGTTGACAGGAAATGAACATAGAATTATTGAGAAAAAACATATAGGGGTTGGGGATTTGGCTC
   5  AGTGGTAGAGCGCTTACCTAGGAAGCGCAAGGTCCTGGGTTCGGTCCCCAGCACCGGAAAAAAAA
      AAAAAAACATATAGAGTAAGGGGGAGTCGGGTTTAAACTGTACAGAAGTCTCCATGTCTTATTT
      ATAATGTAAGCAGGTCTGCAAAGCCTGCCGTTGTGTCCTGTTGCCTTTCTTCTGGCAGTGAAGA
      GGATCAGTTTTGAAGGCAGGCAGAATAGGTGCGGAGAGATGGCTTGGCAGTTAAGAGTATATGCT
      GCTCTTGCAGAGGACCTGCATGCAACTGCCAGCACCCACACAGTGGTTCGTAGCTACCTGTAACT
  10  TCGTTCCATGGGATCCGATGCCTTCTTCTGACCTCTGAGAGCACCGACCATGCACATAGTGCATG
      AACATACATGCGGGTGAAAGACTCACATAAAGTAAAGTGAATACATCTAATTAAAATAAAGACCA
      CTTTATGGGCTGGAGAGATGGCTCAGCGGTTAAGAGCACTGACTGCTCTTCCTGAGGTTCTGAGT
      TAAATTCCCAGCAACAGATGGTGGCTCACAACCATCTGTAATGAGATGTGATCCCCTCTTCCTGG
      TGTGTGTGAAGACAGCTCCCAGTGTACTCAATACACCCCTCCCCTCCCTGAATGGGAAAAAAAAA
  15  AAAAAGCCTGGGGTTGGGGATTTGGCTCAGTGGTAAAAAAAATACCTATGAAGCACAAGGTCCT
      GGGTTCGGTCCCCAGCCCCGAAAAAAAAAAAGAAAAAAAAAAAGACCACTTTACACGTAAAAAA
      TAAAGATGGGCAGATTAGGCCCTGTACTAAACAGGATTCTTTAGAGGAACTGAAATGAGTGTGT
      GTGTGTGTGTATTCATTTTTTTTAAAGATTTATTTATTTTATGTATATGAAGACACTGTTGCTAT
      CTTCAGACACACCAGAAGAGGGCATCAGATCGCCTTAAAGATGGCTGTGAGCCATCATGTGGGTA
  20  CTGGGATTTGAACTCAGGACCTCTGGAAAAGCAGCCCCGTGTGTACTCATTTTATATATGAAATA
      TATACACATACACACGTGTGTGTTAGATTGGCTTCCTTGATGGTCCAGGTAATTCATCAATGA
      GAATCAGTAGTTACTCAGTCTACAAAGCTGAATGTCGCGACAATTCTGATCTGGCACTTTAGACC
      TAGAGGACTCCTGGAGAGTCTACATGGGAATCCTGGACATCTGGAGATCCTACACAAAATCCCTG
      CCATTCCCACCAAGGGCAGCTGTGAATGGCTGTGGGGAAACATTCCTTAAGCTAAGCCTGAAGAC
  25  CTAAATCCAATCCCTGGAACCCGTGTGGTAGATGGAGAGAACTGACTTCTGTTTCATCTGACCTC
      CACTGGTGTAGCCGCACATACATGCATGCAAACAGTCGTGATAAATAAATCTAAAAAAAGTTAG
      AGCACCTGTCAATAGATAAGTATAACTTAAAAGTGAAACGAAGCCTATGCTTTTAAATCGTAAGG
      ACTGGGAGGCAGTCAGGCACATATCCAGGTTCCAGACCAGCCTGATGTATGTAATGAGTTCCAGA
      CCAATTAGGGCTATATCATGAGACCATGTCTCAAAACCAAAAAACAAAAGAAAGAAGAAAAAAG
  30  AAGAACATCAAGTCAAGCATGATAAATCACATAATCCTATAATCCTAATAATGGGGAGGCTGAAG
      CAGAATGGCCATGCCTTTGAGCTTAGCCTGGGCAGGACAACCAACTGGGCTACACAGGAATACAT
      AATACACTGCCATTAGAAAAAAAAGCATGGCTGACTTCGTCACTGCTAGTTGGGGCTTGGGTTTA
      GGTCTTTTCAAACACTAAGCAATTTGGTTCGGAGCTAGTTTTTGAGCCCTCTGCCCACCGCCATG
      GAGGAGCCACCAGAGAAAGTCGACCCAGTTGTAGTCCCAGAAGCTCCTCAAATGAAAGATGACGA
  35  GGACGCGTCCGCTGATTCAGAAGTCCTACAACCAGAAACACTAGTAAAGGTCATGAAAACGCTAA
      CCCTGAACCCCAGTGCCGAACGGTCAGCACGTCATCACAGCCTCAGTGTCCGGATTCAGGGCAGG
      CCTGTGGAGAACAGATGTGAAGGAATCTTGAGGGAAGTTCAAAGCCTTTCCCAAGAGAAGGGTCC
      ACACATTGTTGGTGGTGCTGAGAGATGCCGGAGCAAGGATGAGAAGATTTGTTGGGATTGAGCAG
      AGACAACAAAGGCTTGAAGGAAATGAGTAGGAAGGGAAGAGTGAGCCACTCAGACGTCTCTGTGC
  40  TTCCTGCCATCGTCAGAGATGGAATCCGTCTAAGAAAGCTAAAATCCGGAAGAATTAGGACAGTC
      GGTTTATGTACACTATCCTTGCTGCTCATGATGCCATGCAGCAGACCTGAAAACTGGTTTTTGTT
      TTTTAAAGATAAAACTTTTCCTGGTGCTGGGGAACACGTCTTGTTAACCTTTCAACTATGTAGGA
      AGTGTGACGGTTGAATTCATGTGAAGGACTTAAATTTACCCAAAGTATGGAGAATGAGTTAAAGC
      ATTCTGTGAACTTTAGAAGCCTCAAGCTGGGGGCTGAGAAACACTGTAACTAGAATTTGGGGTAG
  45  TTTGCTTTAGAAGGTAATTGGAATAGGCCTTTGGATTTTCTAGTTTGCAGAAATGTGTAATAAAG
      GCAATTTTGTTATCTTTAACAAACACACAGAACAGATTAGAATGAGCCATTGGAGATGGGGGGTT
      GTTTTTACAGGAGCACGTGTGGGTGCGCACACTCCTGATGTCCAGAGTTCAATGTGTGTTGCTAA
      CCCTGTTTATTTCTGCTCCAGGCAGGGTCTCCATGAGCCTAGCCAGTCTCTCAGCTCGTGGTCCT
      GCCTCCCTTGTTGCCCAAGTTTTGACGCCACAGGCTTGACAGCAAGATCTAGAAAATGCTTGTCT
  50  TGATTTTGTGTTTGTTCATGCTGTGTAATAAAAGAACAATTGGTTGATGTATTCCTAAATTTAA
      AAAAAAAAAAAAAAGCACCAGGTGATGGTGGCTCACCCCTTTAATCCCAACGCTCAGAAGGCAGA
      GACGGGTGGATCTCTGAATTCATGGCCAGCCAGGGCTACACAGCAAAACCCTGTCTTGAGAAAAG
      AGACTTGTGGGGGTTGGGGATTTGGCTCAGTGGTAGAGCGCTTGCTACCCTGGGTTCGGTCCCCAG
      CTCCGAAAAAAGAATAGAAAAAAAAGAAAAAGAAAAAGAGACTCGTAAGCAAGCAAAGCTT
  55  GGTAGTCTAAAGAAATGAGAAATCCTTAGAGCTACCTTAGAGCTAGAAAAGGCAGGACATTTCAG
```

```
      GCAGAGAGCTGGTACGGCAAGCCCAAAGGCTCAGGGCCCGGTTTATACCATGTAAGGTTATCCTG
      AGGGGCTGGAGAAGAAATGCACAGCAACACTAACACGTCATACTGTCTGGCCAAGTATCAACTAC
      CATGGCTTTATAGATCCTGCTCTTGAGGAAAGGGGTAGATCAAGGGGTAATCAAGGATAGATTAC
      CCCTTTGGCAATAGGACGGAGGGTGGCTAGATCCCTCCAACAGTGTGAGTAGGTCCAAGAGTATG
  5   AATCATCTATGGCTCCTAATAAACACTGCTAGGCTAATTTACCATTGAGCTACATCCCAAATATC
      AAAGTTGTTTTGGGAGAGGGGATGCATGGGAGACAGGTTCTAATGTGAATCTTACTGTCCTGGA
      ACTCCCTCCATAGACCGTGCTGGCTTTGAACTTACAGAGTTCTCACAGGAGACTTAACTGCCTTT
      GTCTCCAAAGTGCTGGGATCAAAGGCGTGCACCACCACATCCAGCCTTATTTTAATTAATTATAA
      TCAATTATTAATTAATTATAATCATAATTTTAATTAGTTTTGATCATATTTATCGATGTATTATG
 10   GAAGTGGGGCCTTGCATGTCATTCTTGTTGGTAAAGGTCAGGAGATAAAAATACTACTTGGTAAA
      TAAGAAACCCAAGTTAAGAAAGATGGAGAAAAAAAACAATATTATAGTTAAAAAAAAAAAAAAC
      TTGGTCTTTTAAAAATAAAATACAGGGGGCTGGGGATTTAGCTCAGTGGTAGAGCGCTTACCTAG
      GAAGCACAAGGCCCTGGGTTCGGTCCCCAGCTCTGAAAAAAAGAACCAAAAAAAAAAAAAGAAAA
 15   AAGAAAATACAGGGCTGGAGAGATGCTCAGCGGCTAAGAGCACTGACTGCTCTTCCAGAGGTCCT
      GAGTTCAATTCCCAGCAACCACATGGTGGCTCACAACCATTTGTAATGGGATCTGATGCCCTCTT
      CTGGTGTGTCTGAAGACAGCTACAGTGTACATGAATACATAAATAAATTCTTTAAAAAAATGAAA
      AATAAAATACATGTCATATGATTTATCAAAAAAAAATACTACTTGGACAGGGTTGGAGATTTAG
      CTCAGTGGCCGAGCACTTGCCTAGCAAGTGCAAGACCCTGGGTTCGGTCCTCAGCTCTGAAAAAA
      AAAATTACTACTTGGAGAAGTAGGTTCTCCCCTTCCACTCAAGTTGTAGAAATCCAACTTAGATG
 20   TCAGGAGGCAAGCTCTCGTACCAACGGAACTTAAGATTTTGGTTTTTGAAGTCTTGTAGAGACCA
      GGCTATCCTGAAATCAAGATTTAATTTACCCAGCTCCAAAAAAAAAAAAAAAAAGATTTAATTTAA
      AGTAGCTGTTCCATGCCTTTGATCCCAGCACTCTGGACAAGAGAGGCAGATGCAGGTTGGTGTGT
      GAGTTTGAGATCAGTCTCAAAGCTTGGTCCACATGGAAAGTTCTAGAACAGCCAAGGCTTCATGA
      GATCGTGTCTCAAAACAGCAAAGACAGTGACGATGACGTGATGATGATGAGCAACATAGACTCAA
 25   GCGTGCTAGGCCAAAACACCACTAGATCTGCTCCCTAGCCCCTGACAAGTAATTTGCTAACAACA
      TGCATAGTGGTTATTCTTCCAATTTCTCCTTCTCCTTCTCCTTCTCCTCCTTCTCCTTCTTCTTC
      TGTTTATTTATTTATGTGAGTACACTGTAGCTGTCCTCAGACACACCAGAAGAGGGCATCGGATC
      TCATTACAGATGGCTGTGAGCCACCATGTGGTTGCTGGGATTTGAACTCAGGACCTCTGGAAGAG
      CAGTCAGTGCTCTTAGCTGCTGAGCGTCTCTCCAGCCCCCAATTTCTTCTTTTAAAATTACATAA
 30   TCACCACTAGGTGGGGTGGCACATGCAGGCAGATCTCTGTGGGTTTGAGGTCTGCCTGGTCTTGG
      TATTGAGTTCCAGGTCAGCCAGAGCTATATTCTGAGACCCTGTCTCAAAAAGACAGAAATAGAAG
      TAAAAAAGAAACGGAAAATTAAAAAACACAGGGAGGCGGTGGTGACACACTTTGATCCCAGTAC
      TGCATTTGGGAGGCAGAGGCAGGTGGATCTCTTTGTATTACAGGCCAGCCTGGTCTACAGAGAAT
      TCCAGGACATCAAGTACTATGCAGAGAAACTCTGTCTCAAAACACCAATAAACAAACAAACAAAC
 35   AAACAAGTAAAATAAATAAATAAAATTAAAAAAGGAAAAGAAAAACGAAAAGAAAGAAGAGA
      ATAAAATTGTATTGCTTATCATGAATGCTCCAACTCGTGTGTTTAGGTCAGAAGACAACTAACAG
      GAATCCTTTTTTCTCTGGTATCAAACTCGTGGGTCTTAGGAATCGAACTCACATACTTCGGTTGG
      GCGGCAAGCGATTTTACCCGCTGATCCATGACACAGGCCCTCTTTAATTTCTAAAGCCCTACATG
      CGGGTCTGGACTTTATTCACGGTGGGTGGGTCTTCTTCCTGTCAGTTTCCGTCCGCAGATGTCCC
 40   CGCCCACCAGGAAGGATCTTTCGGGCTCTCGTCGGCACCCGTCCACCCTGTCTCCACGTGACACA
      AACAGACAGGGCACTTCCGCTTCCCGTCCACTCTCCTCACTCAGTGTCTACACCCCCGTCCCCG
      GGTCCCCGCCCGGTGAGTTAGCGAGCGCCGGGAGGGCGGCGTCGCGGGCGGAGTCGCCCCGGGC
      TGACCCTTGCCGCCTTCCTTCTTCTCACCGCAGGTCCCGCGGTAGCGGAGGCGGGCGCCATGGC
      GGAGCTGACGGCTCTGGAGAGCCTCATCGAGATGGGCTTTCCCAGGGGACGCGCGTAAGGGAACC
 45   TCCCCTCTAGCCTGTGGTGGGAGGCCGCGGGCCTGCCGGGCCTCACTGTCACCATGGCTGGTGGG
      CGCTATTCACGGTGTTTCTGCCCTCAGGGAGAAGGCTCTGGCCCTCACAGGGAACCAGGGCATCG
      AGGCTGCGATGGACTGGTGAGCGACTGGCACGGGTGGAGGAAGTTTGGGGGCCTCTGGGAAAGGC
      GGCCTCAAGGCTAACCCCCTGCCAACTTTCTCTGCCCAGGCTTATGGAGCATGAAGACGACCCCG
      ATGTGGACGAGCCTCTAGAGACTCCTCTCAGCCATATCCTGGGACGAGAACCCACGCCCTCAGAG
 50   CAAGTTGGTCCTGAAGGTCCTGACTGGGAGACATCTTGTGATTCTAGCTATCTAGTGAGGGCCTG
      AGGAAACCAGAATGCTTTCACTATAAATAATAATACTAGTTGCTTGTTTGTAGGATCTGGGTCTG
      CTGCTGGAGAAAGCAAACCCGTTTTGACTGAAGAGGAGAGGCAAGAACAGACTAAGAGGTAACTG
      TGCAAGTTCAGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTGTG
      TGTGTGTTTTGTTTGGAGCCTGCCTCACTCCTGTCCAGGCTGAACTCTGGATCCTGCTGCCTCAG
 55   CCTCCAGAGTGCTGGGATTACAGGTCTTCACCACTGTGCCCTGTATTATTTTTTGAGACAGGGTC
```

```
     TAGCTGTGTACCTCAGGCTGGCCTGGAACCTAGGCTAAATGCAACGCCACATTCTTCTGAGTGTT
     GTGATCACCATAGCTAGCCCATTAACACACTTTCCCAAGGGTCATGGGTCATCTTCCTTTCTTCT
     CAAATACAAACACAAGTCAGGACAGACCTGGCCTTTCCAGTTAGTGGATGTTGGGGGAGTCACCA
     GGAAACATCTCATACAGCACAAGACTGTCTAAACTCCTGCGTGGCTGCAGACTCCCCTGAAATCC
5    CAATTCTCTGGCCCCTACTTTGCAAGTGCAGGGACTGTAGGTATTCACCACCGTGCCTGGCTCTT
     GTCTGCCCTTTTTAAAAAAACAAAAAACAAAAAGGCCCCATGCATAATGTATGTGCTCTAACACT
     GAGCTACCTTTTTTTTTTCTTTTGGTTTTGGTTTTGTTTTTTTCAAGCCAGAGTCTGTCTCTAT
     CCCCGCTGTCCTTAAACTGGCTCTATAGACCTGGCTGGACTGAAACTCAAGAAATCCACCTGCCT
     CTGCCTTCTGAGCACTGAGGGGTGCACTGTCACCACCTAGCTTGCCCTTTTATGTTACTGTCTT
10   GGCTTTGTTTTTTTTTTCTTTTTTTTTTCTTTTTTTTGGAGCTGGGGACCGAACCCAGGGCCTT
     GTGCTTGCTAGGTAAGCGCTCTACCATCGAGCTAAACCCCCAACCGGGCTTTGTTTTCTTTTATC
     TGTCTTGGAACACAATCCTTTAATCTGTTAATTCTCTGTTTAAACTCACCTTCCCACTCCATATC
     CAGCTTCAGCTTTTTCTTCTCTGCAAAACAGAATGTTGGAACTTGTGGCGCAGAAGCAGCGGGAA
     CGTGAAGAAAGAGAGGAGCGAGAAGCTTTAGAACGAGAGAAGCAGCGGAGGAGACAAGGGCAAGA
15   GCTGTCAGCTGCACGACAGAAACTACAGGAAGATGAGATACGCCGGGCTGCTGAGGAGCGCAGGA
     GGGAGAAGGCTGAAGAGCTAGCTGCCAGGTCTGAAGACTCATAGGTCACTAACGGAGGAAGAAAT
     GAAGACTTGCCTTGCCCATGTCTGACCTATCTTCCTCCTGTCTCTCTTCTAGACAAAGGGGGCGA
     GAGAAAATTGAAAGGGACAAAGCAGAGAGAGCCCAGAAGGTGGGTGATGAGGAAGTCTGTGGGTA
     TAATGGAGTAGGGGGGTGCGGGGCCGTGGGGGCGTGCGGGCGAGGGGGGGGGGGGGGGCGCGGG
20   TGGGCGGGGGACGGAGAGGGGGCGGGGCAGGCGGGGGGGGGCGCGGAGGTGCGGGGGGTTTCTC
     ACGGGTGGAGGAGGGGCGGGGGGGGGGGGAGGTGGGGTCGTGCGGTTGATGGTGCGGCGGGGTTG
     ATAGACGCCGTGCGAGTTGGCGGCGGGGGGCGGGCGGTGGAGGGGCGGCTGAGACGGGGGGCAGG
     GGGTGCGTTGGGGGTGGAGGGCAGTGGGGCGGGTGCGGTTGCTGGCGCGGGCGGCGCGGAACGGT
     AGCCGGGGCGCGCGGGAGCGCGCGCGCGCTCGCGAGGGGGTGCGGCCGGAGAGGGGTGCGGAG
25   GTCCGGTGAGCTGACTGACGATGCCCGGTAGCTGCTGGCGCGTGGGCGACGCGTCATGCCGTGGC
     GCGGGTGGGGCGGGCGCGGTGCATGCGCGAGCGTCCTCGGTCTGGCGACCGTAGCGCGCTCTCTG
     TCGGGGCCGCGGACCGGCGGTGAGGGTCGGGGCGGGGGTGCGTGGTGGCTGGAAGGCGAGTGGT
     GTCGGGTAGAGGGCGGCGATAGGGGGCGCGCGTGATGTGATAT
```

CLAIMS

1.   A GCR1 polypeptide, or a fragment, homologue, variant or derivative thereof

2.   A polypeptide according to Claim 1, which has at least 50%, 60%, 70%, 80%, 90% or 95% homology to a sequence shown in SEQ ID NO: 2.

5   3.   A GCR2 polypeptide, or a fragment, homologue, variant or derivative thereof

4.   A polypeptide according to Claim 3, which has at least 50%, 60%, 70%, 80%, 90% or 95% homology to a sequence shown in SEQ ID NO: 4.

5.   A nucleic acid encoding a polypeptide according to any preceding claim.

6.   A nucleic acid having at least 90% homology with the sequence set forth in SEQ
10   ID NO: 1, or a fragment, variant or derivative thereof.

7.   A nucleic acid having at least 75% homology with the sequence set forth in SEQ ID NO: 3, SEQ ID NO: 5, SEQ ID NO: 6, SEQ ID NO: 7, SEQ ID NO: 8 or SEQ ID NO: 9, or a fragment, variant or derivative thereof

8.   A nucleic acid comprising a sequence of 25 contiguous nucleotides of a nucleic
15   acid according to Claim 5, 6 or 7.

9.   A nucleic acid comprising a sequence of 15 contiguous nucleotides of a nucleic acid according to any of Claims 5 to 8.

10.   The complement of a nucleic acid sequence according to any of Claims 5 to 9.

11.   A nucleic acid according to any of Claims 5 to 10, comprising one or more nucleotide substitutions, wherein such substitutions do not alter the coding specificity of said nucleic acid as a result of the degeneracy of the genetic code.

12.   A polypeptide encoded by a nucleic acid according to any preceding claim.

5   13.   A polypeptide according to Claim 12, in which the polypeptide comprises a sequence shown in SEQ ID NO: 2 or SEQ ID NO: 4.

14.   A method for identifying a pluripotent cell, comprising detecting the presence of a polypeptide according to any of Claims 1 to 4, 12 or 13 or the expression of a nucleic acid according to any of Claims 5 to 11, or a homologue thereof.

10   15.   A method according to Claim 14, comprising the steps of amplifying nucleic acids from a putative pluripotent cell using 5' and 3' primers specific for GCR1 and/or GCR2, and detecting amplified nucleic acid thus produced.

16.   A method according to Claim 14, wherein the expression of the nucleic acid sequence is detected by *in situ* hybridisation.

15   17.   A method according to Claim 8, wherein the expression of the nucleic acid sequence is determined by detecting the protein product encoded thereby.

18.   A method according to Claim 14 or Claim 18, wherein the protein product is detected by immunostaining.

19.   An antibody specific for a polypeptide according to any of Claims 1 to 4, 12 or 13.

20   20.   An antibody according to Claim 19, which is capable of specifically binding to an extracellular domain of GCR1.

21. Use of an antibody according to Claim 19 or Claim 20 for the identification and/or isolation of a pluripotent cell.

22. A pluripotent cell identified by a method according to any one of Claims 14 to 18 and 21.

5 23. A method for isolating a gene specifically expressed in a pluripotent cell, comprising the steps of:

(a) providing a population of cells containing a pluripotent cell;

(b) isolating one or more pluripotent cells therefrom and providing single-cell pluripotent cell isolates;

10 (c) amplifying the transcribed nucleic acid present in a single pluripotent cell;

(d) conducting a subtractive hybridisation screen to identify transcripts present in pluripotent cells but not in somatic cells; and

(e) probing a nucleic acid library with one or more transcripts identified in (d) to clone one or more genes which are specifically expressed in pluripotent cells.

15 24. A method according to any of Claims 14 to 18 or 23, a use according to Claim 21, a pluripotent cell according to Claim 23, in which the pluripotent cell is selected from the group consisting of: a primordial germ cell (PGC), an embryonic stem cell (ES) and an embryonic germ cell (EG).

ABSTRACT
GENES

The invention provides two primordial germ cell-specifically expressed genes, GCR1 (Fragilis) and GCR2 (Stella), which are markers for primordial germ cells and may

5   be used to identify such cells in cell populations.

Figure 3

GCCGCAGAAAGGGCAGACCCGCAGCGCGCTCCATCCTTTGCCCTCCAGTGCTGCCTTTGC   60

TCCGCACCATGAACCACACTTCTCAAGCCTTCATCACCGCTGCCAGTGGAGGACAGCCCC   120
       M   N   H   T   S   Q   A   F   I   T   A   A   S   G   G   Q   P   P

CAAACTACGAAAGAATCAAGGAAGAATATGAGGTGGCTGAGATGGGGGCACCGCACGGAT   180
  N   Y   E   R   I   K   E   E   Y   E   V   A   E   M   G   A   P   H   G   S

CGGCTTCTGTCAGAACTACTGTGATCAACATGCCCAGAGAGGTGTCGGTGCCTGACCATG   240
  A   S   V   R   T   T   V   I   N   M   P   R   E   V   S   V   P   D   H   V

TGGTCTGGTCCCTGTTCAATACACTCTTCATGAACTTCTGCTGCCTGGGCTTCATAGCCT   300
  V   W   S   L   <u>F   N   T   L   F   M   N   F   C   C   L   G   F   I   A   Y</u>
            TM I

ATGCCTACTCCGTGAAGTCTAGGGATCGGAAGATGGTGGGTGATGTGACTGGAGCCCAGG   360
  <u>A   Y</u>   S   V   K   S   R   D   R   K   M   V   G   D   V   T   G   A   Q   A

CCTACGCCTCCACTGCTAAGTGCCTGAACATCAGCACCTTGGTCCTCAGCATCCTGATGG   420
  Y   A   S   T   A   K   C   L   N   I   S   T   <u>L   V   L   S   I   L   M   V</u>
                TM II

TTGTTATCACCATTGTTAGTGTCATCATCATTGTTCTTAACGCTCAAAACCTTCACACTT   480
  <u>V   I   T   I   V   S   V   I   I</u>   I   V   L   N   A   Q   N   L   H   T   *

AATAGAGGATTCCGACTTCCGGTCCTGAAGTGCTTCACCCTCCGCAGCTGCGTCCCTCCT   540

TGCCCCTCCCTACACGCAGGTGTAACACTCATTTATCTATCCACAGTGGATTC<u>AATAAAG</u>   600

TGCACTTGATAACCACC

FIGURE 1

GGATCACAGACTGACTGCTAATTGGGTCTTGGTTTTAGGTCTTTTCAAAGACTAAGCAAT 60
CTTGTTCCGAGCTAGCTTTTGAGGCTTCTGCCCATCGCATCGCCATGGAGGAACCATCAG 120
                                                              M E E P S E

AGAAAGTCGACCCAATGAAGGACCCTGAAACTCCTCAGAAGAAAGATGAAGAGGACGGCTT 180
  K V D P M K D P E T P Q K K D E E D A L

TGGATGATACAGACGTCCTACAACCAGAAACACTAGTAAAGGTCATGAAAAAGCTAACCC 240
  D D T D V L Q <u>P E T L V K V M K K L T L</u> **Helix I**

TAAACCCCGGTGTCAAGCGGTCCGCACGCCGGCGCAGTCTACGGAACCGCATTGCAGCCG 300
  <u>N P G V K R S A R R R S L R N R I A A V</u>
                                                    Helix II

TACCTGTGGAGAACAAGAGTGAAAAAATCCGGAGGGAAGTTCAAAGCGCCTTTCCCAAGA 360
   <u>P V</u> E N K S E K I R R E V Q S A F <u>P K R</u>

GAAGGGTCCGCACTTTGTTGTCGGTGCTGAAAGACCCTATAGCAAAGATGAGAAGACTTG 420
   <u>R V R T L L S V L K D <u>P I A K M R R</u> L V</u>

TTCGGATTGAGCAGAGACAAAAAAGGCTCGAAGGAAATGAGTTTGAACGGGACAGTGAGC 480
   R I E Q R Q K R L E G N E F E R D S E P

CATTCAGATGTCTCTGCACTTTCTGCCATTATCAAAGATGGGATCCCTCTGAGAATGCGA 540
  <u>F</u> R C L C T F C H Y Q R W D P S E N A K

AAATCGGGAAGAATTAGGAGCTTACATTGTACGCTGCCCTGGCTGTCGACGATGCCGCAC 600
  I G K N *

AGCAGATGTGAAAGCTATTTTTTGTTTAAGATTAAACTTTTTCTGGTGCTGGGAAATCTT 660
AACTTGTTAACCTTTAAATTGTAGATAGGATGCACAACGATCCAGATTTATGTGAAGTTT 720
AGAAGCCTCAAGCTGTGAGGCCCAGGGCTGAGG<u>AATAAAG</u>TAAATAGAATTTGGAGTATG 780
TACGTTCTAATTTCCAGAAATTTGT<u>AATAAA</u>AGCATTTTTGTT

FIGURE 2

Figure 3

Figure 4

Figure 5

Figure 6

FIGURE 7

Figure 8A

Exp. No.	1				2				3			4			5						
Clone No.	1	9*	10*	11	17	24*	27	30*	34	46*	49	50*	69	76*	77	81	83*	85	87*	88	89	98*

Hoxb-1

1   9   10   11   17   24   27   30   34   46   49   50   69   76   77   81   83   85   87   88   89   98

Fragilis

1   9   10   11   17   24   27   30   34   46   49   50   69   76   77   81   83   85   87   88   89   98

Stella

1   9   10   11   17   24   27   30   34   46   49   50   69   76   77   81   83   85   87   88   89   98

Evx1

1   9   10   11   17   24   27   30   34   46   49   50   69   76   77   81   83   85   87   88   89   98

Oct4

1   9   10   11   17   24   27   30   34   46   49   50   69   76   77   81   83   85   87   88   89   98

T(Brachyury)

1   9   10   11   17   24   27   30   34   46   49   50   69   76   77   81   83   85   87   88   89   98

Fgf8

Figure 8B